

GREEN (17)+18
 Line Survey
 NORTH 3rd Line


PLAT OF A 1190.25 FOOT LONG PROPERTY LINE FOR CHRISTOPHER GOSS AND CAROL BUSH

Situated in Green Township, Hocking County, Ohio; being a 1190.25 foot long property line; being part of the North line of Section 17, Township 13, Range 16.



REFERENCES:

- Tax maps
- Deed descriptions
- Previous surveys
- Existing monumentation
- Existing public roads



REFERENCE BEARING:

The North line of Section 17 at the South line of a 2.5081 acre survey as North 90 degrees 00 minutes 00 seconds West.

I hereby certify that an actual survey was made under my supervision of the premises shown hereon on the 19th day of April, 1995 and that the plat is a correct representation of the premises as described by said survey.

Approved: _____
 Hocking County Surveyors Office
 By *R-PN* Date *4-21-95*

Larry P. Gerstner
 Registered Surveyor No. 6344

Survey by: Larry P. Gerstner - Engineering and Surveying
 119 West Main St., Logan, Ohio 43138 385-4260

SURVEY DESCRIPTION OF A 1190.25 FOOT LONG PROPERTY LINE

FOR CHRISTOPHER GOSS AND CAROL BUSH


Situated in Green Township, Hocking County, Ohio; being a 1190.25 foot long property line; being part of the North line of Section 17, Township 13, Range 16; and being more particularly described as follows:

Beginning at a 2" OD iron pipe found in the gravel of the intersection of County Road 16, Maysville Greendale Road, and Township Road 350, Scout Road, at the Northeast corner of the Northwest quarter of Section 17;

thence with the North line of Section 17 North 90 degrees 00 minutes 00 seconds West a distance of 509.56 feet to a 5/8 iron pin set to replace a fence post described in a February 13, 1984 2.5081 acre survey by registered surveyor no. 6650 and passing 5/8" iron pins set at distances of 40.01 feet, 100.01 feet, 170.01 feet, and 270.00 feet;

thence continuing with the North line of Section 17 South 89 degrees 14 minutes 20 seconds West a distance of 680.69 feet to a 1-1/2" OD iron pipe found, passing 5/8" iron pins set at distances of 80.16 feet, 186.24 feet, 346.24 feet, and 514.28 feet, and being the end of a 1190.25 foot long property line survey.

The above 1190.25 foot long survey is intended to describe part of the North line of a 105.05 acre tract as deeded to Christopher Goss and Carol Bush, deed reference Volume OR 12, Page 759, Hocking County Recorder's Office. This survey was based upon information obtained from tax maps, deed descriptions, previous surveys, existing monumentation, and an existing public road. The reference bearing for this survey is the North line of Section 17 at the South line of a 2.5081 acre survey as North 90 degrees 00 minutes 00 seconds West. All iron pins set by this survey are capped by a 1-1/4" plastic identification cap labeled LPG-6344. The above described property was surveyed by Larry P. Gerstner, Ohio Registered Surveyor No. 6344, on April 19, 1995.





Approved: Mathematically
Hocking County Engineer's office
By *KAH* Date 4-21-95

Survey by:


Larry P. Gerstner - Engineering and Surveying
119 West Main Street, Logan, Ohio 43138 385-4260

GREEN 17

5.988 AC.


PLAT OF A 5.988 ACRE TRACT FOR THE BOY SCOUT PROPERTY

Situated in Green Township, Hocking County, Ohio; being part of the South half of the Southwest quarter of Section 17, Township 13, Range 16.



Approved - Mathematically
Hocking County Engineer's Office

LPG DATE 11-21-00



SCALE:
1" = 200'

REFERENCES:

- Tax maps
- Deed descriptions
- Previous surveys
- Existing monumentation
- Existing public road

LEGEND

- Stone found
- 5/8" x 30" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 set
- ▲ MAG nail set
- 5/8" iron pin with 1-1/4" plastic ID cap stamped SEYMOUR & ASSOC. found

REFERENCE BEARING:

South line of Section 17 as South 90 degrees 00 minutes 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only.

CERTIFICATION:

I hereby certify that an actual survey was made under my supervision of the premises shown hereon on the 31st day of October, 2000 and that the plat is a correct representation of the premises as described by said survey.

Larry P. Gerstner
 Registered Surveyor No. 6344

Survey by:

Larry P. Gerstner - Engineering and Surveying
 9 East Second Street, Suite A, Logan, Ohio 43138
 (740) 385-4260

SURVEY DESCRIPTION OF A 5.988 ACRE TRACT FOR THE BOY SCOUT PROPERTY

Situated in Green Township, Hocking County, Ohio; being part of the South half of the Southwest quarter of Section 17, Township 13, Range 16; and being more particularly described as follows:

Commencing for reference at a stone found at the Northeast corner of the South half of the Southwest quarter of Section 17; thence South 89 degrees 57 minutes 28 seconds West a distance of 584.11 feet to a 5/8" iron pin with 1-1/4" plastic ID cap stamped SEYMOUR & ASSOC. found; thence South 89 degrees 57 minutes 19 seconds West a distance of 425.01 feet to a 5/8" iron pin with 1-1/4" plastic ID cap stamped SEYMOUR & ASSOC. found and being the point of **Beginning** of the tract of land to be described;

thence South 17 degrees 56 minutes 09 seconds West a distance of 423.09 feet to a 5/8" iron pin set;

thence North 83 degrees 36 minutes 22 seconds West a distance of 651.81 feet to a MAG nail set in the center of Township Road 356, Mowery Lehman Road, and passing 5/8" iron pins set at distances of 440.16 feet and 627.82 feet;

thence with the center of said Township Road 356 North 1 degree 43 minutes 43 seconds East a distance of 327.57 feet to a MAG nail set;

thence leaving the center of said Township Road 356 North 89 degrees 48 minutes 43 seconds East a distance of 768.17 feet to the point of beginning, passing 5/8" iron pins set at distances of 18.14 feet and 203.41 feet, containing 5.988 acres more or less, and subject to the public easement of said Township Road 356 and any other public or private easements of record.

The above 5.988 acre survey is intended to describe part of the 82.5 acre Tract Six as deeded to Larry P. Gerstner by deed reference Volume OR167, Page 827, Hocking County Recorder's Office. This survey was based upon information obtained from tax maps, deed descriptions, previous surveys, existing monumentation and an existing public road. The reference bearing for this survey is the South line of Section 17 as South 90 degrees 00 minutes 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only. All iron pins set by this survey are 5/8" by 30" and are capped by a 1-1/4" plastic identification cap stamped LPG-6344. The above described property was surveyed by Larry P. Gerstner, Ohio Registered Surveyor No. 6344, as completed on October 31, 2000.

Approved - Mathematically
Hocking County Engineer's Office

J. A. W. DATE 11-21-00

Larry P. Gerstner




Survey by:

Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138 385-4260

BEING A PART OF THE TAVE NW 1/4 AND PART OF FRAC. LOT NO. 6 OF SEC. 17,
GREEN TWP., T-13N, R-16W, HOCKING CO., OHIO

NOTE: CURVED BEARINGS ARE BASED ON THE BEARING SYSTEM OF THE 6.55 AC. TRACT DESCRIBED IN VOL. 214, PG. 444.

C. GOSS & C. BUSH
O.R. VOL. 12, PG. 759



7.4369 ACRES
(PT. OF O.R. VOL. 12, PG. 759)


C. GOSS & C. BUSH
O.R. VOL. 12, PG. 759

Approved: *[Signature]*
Hocking County Engineer's office
By *[Signature]* Date 8-4-93

REFERENCES:

COUNTY TAX PLATS
1880 PLAT RECORDS
SURVEYS OF RECORD
DEEDS (AS NOTED)

SE COR. OF FRAC.
LOT NO. 6 OF
SEC. 17, GREEN TWP.



PLAT PREPARED FROM SURVEY
MADE JULY 30, 1993, BY:

[Signature]
OHIO REGISTERED SURVEYOR NO. 6803

11.55' SEC. 17
 M. 10.50.05
 66.915
 GREEN 17
 7-4369A.

DESCRIPTION OF SURVEY FOR MR. JOHN GOSS

Being a part of a tract of land last transferred in Vol. 12, Pg. 159, Hocking Co. Official Records, situated in the NW $\frac{1}{4}$ and in Frac. Lot No. 6 of Sec. 17; Green Twp., T-13N, R-16W, Hocking Co., Ohio, and being more particularly described as follows:

Beginning, for reference, at a point on the east line of Sec. 17, said point being referenced by the SE corner of said Frac. Lot No. 6 which bears S 0° 05' 01" W a distance of 579.99 ft.;

Thence N 89° 54' 59" W a distance of 1684.34 ft. to a point in the center of Twp. Rd. No. 350, said point being the principal place of beginning for the tract herein described;

Thence with the center of said Twp. Rd. 350 the following two (2) courses:

- 1) S 4° 30' 39" W a distance of 219.84 ft. to a point;
- 2) S 1° 56' 42" E a distance of 56.80 ft. to a point;

Thence, leaving said road and with a new line, N 88° 08' 31" W, passing an iron pin set at 19.96 ft., going a total distance of 1283.56 ft. to an iron pin set;

Thence N 12° 14' 10" E a distance of 257.90 ft. to an iron pin set;

Thence S 86° 33' 36" E a distance of 346.58 ft. to an iron pin set;


Thence N 89° 48' 17" E, passing an iron pin set at 876.38 ft., going a total distance of 897.63 ft. to the principal place of beginning, containing 7.4369 acres, more or less, and being subject to the right-of-way of Twp. Rd. No. 350 and all valid easements.

Cited bearings are based on the bearing system of the 6.55 acre tract described in Vol. 214, Pg. 444.

All iron pins described as being set are 1/2" X 30" with an attached plastic identification cap.

The above description is the result of an actual survey made by Michael P. Berry, Ohio Registered Surveyor No. 6803, on July 30, 1993.

Approved - Mathematically
Hocking County Engineer's Office
By J. C. K. Date 8-4-93


Michael P. Berry #6803

GREEN 17

PLAT OF A 1.837 ACRE TRACT FOR THE BOY SCOUT PROPERTY


1.837Ac

Situated in Green Township, Hocking County, Ohio; being part of Fractional Lot 1 of Section 17, Township 13, Range 16.

Recorded - Mathematically
Hocking County Engineer's Office

ALL DIVISION REGULATIONS WAIVED
PENDING HEALTH DEPT. APPROVAL

MAW DATE 3-8-01 BY JM DATE 3-8-01



Larry P. Gerstner
OR167-827
1.837 acres

Southeast corner
of Section 17
Center of
Township Road 352,
Jake Tom Road



Larry & Lorie
Ellinger
OR115-183

LEGEND

- ✱ Point
- 5/8" x 30" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 set
- ▲ MAG nail set

REFERENCES:

- Tax maps
- Deed descriptions
- Previous surveys
- Existing monumentation
- Existing public road

REFERENCE BEARING:

East line of Section 17 as North 0 degrees 06 minutes 44 seconds West. Bearings are based upon an assumed meridian and are to denote angles only.

CERTIFICATION:

I hereby certify that an actual survey was made under my supervision of the premises shown hereon on the 8th day of February, 2001 and that the plat is a correct representation of the premises as described by said survey.

Larry P. Gerstner
Registered Surveyor No. 6344

Survey by: Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138
(740) 385-4260

SURVEY DESCRIPTION OF A 1.837 ACRE TRACT FOR THE BOY SCOUT PROPERTY

Situated in Green Township, Hocking County, Ohio; being part of Fractional Lot 1 of Section 17, Township 13, Range 16; and being more particularly described as follows:

Commencing for reference at a point at the Southeast corner of Section 17; thence with the East line of Section 17 North 0 degrees 06 minutes 44 seconds West a distance of 684.19 feet to a 5/8" iron pin set and passing a 5/8" iron pin set at a distance of 492.19 feet; thence leaving the East line of Section 17 South 77 degrees 04 minutes 08 seconds West a distance of 408.66 feet to a 5/8" iron pin set and being the point of **Beginning** of the tract of land to be described;

thence South 34 degrees 11 minutes 12 second West a distance of 329.16 feet to a MAG nail set in the center of Township Road 352, Jake Tom Road, and passing 5/8" iron pins set at distances of 195.87 feet and 312.33 feet;

thence with the center of said Township Road 352 North 70 degrees 35 minutes 02 seconds West a distance of 248.62 feet to a MAG nail set;

thence leaving the center of said Township Road 352 North 21 degrees 42 minutes 31 seconds East a distance of 43.86 feet to a 5/8" iron pin set;

thence North 15 degrees 47 minutes 50 seconds East a distance of 181.12 feet to a 5/8" iron pin set;

thence North 61 degrees 03 minutes 54 seconds East a distance of 16.71 feet to a 5/8" iron pin set;

thence South 89 degrees 49 minutes 28 seconds East a distance of 80.75 feet to a 5/8" iron pin set;

thence South 80 degrees 39 minutes 58 seconds East a distance of 210.78 feet to a 5/8" iron pin set;

thence North 88 degrees 54 minutes 53 seconds East a distance of 50.54 feet to the point of beginning, containing 1.837 acres more or less, and subject to the public easement of said Township Road 352 and any other public or private easements of record.

The above 1.837 acre survey is intended to describe part of the 30 acre Tract 21 as deeded to Larry P. Gerstner by deed reference Volume OR167, Page 827, Hocking County Recorder's Office. This survey was based upon information obtained from tax maps, deed descriptions, previous surveys, existing monumentation, and an existing public road. The reference bearing for this survey is the East line of Section 17 as North 0 degrees 06 minutes 44 seconds West. Bearings are based upon an assumed meridian and are to denote angles only. All iron pins set by this survey are 5/8" by 30" and are capped by a 1-1/4" plastic identification cap stamped LPG-6344. The above described property was surveyed by Larry P. Gerstner, Ohio Registered Surveyor No. 6344, on February 8, 2001.



Hocking County Engineer's Office
37 AW 3-8-01
LARRY P. GERSTNER
DIVISION REGULATIONS WAIVED
PENDING HEALTH DEPT. APPROVAL
BY 37 DATE 3-8-01

Survey by:

Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138 385-4260

West 1/4 Section 17 NE Cor Lot 5
S84°09'E 100.06 11'

North Line Sec 17
S83°09'E 506.97



County Road


NE Cor
Sec 17 & C
Lot 5

0.35 ac Parcel
Pt Lot 5 Section 17 Green Twp
Hocking County Ohio

For
Ted Lemon.

Approved - Mathematically
Hocking County Engineer's office
By _____ Date _____

Survey by
Albert W. Seabright
Dec 14 1962



NE Pr.
Green 17
135 ac
Soft
Maple

Donated, June 1982, by
ALBERT W. SEABRIGHT, P.E., P.S.
COUNTY ENGINEER 1949 - 1964

TED LEMON
Part Lot 5, Section 17, Green Twp.

Being a part of Part Lot 5, Section 17, Green Township, T13N, R16W, Hocking County and State of Ohio, and further described as commencing at an iron pin in the center line of the County Road, which pin bears west on the north line of said Section 17, a distance of 14 chains from the northeast corner of said Lot 5; thence with said County road two courses, South $84^{\circ} - 09'$ East 180.06 feet to an iron pin; thence with the township road South $83^{\circ} - 07'$ East 506.97 feet to an iron pin; thence South $45^{\circ} - 37'$ East 193.78 feet to an iron pin; thence South $2^{\circ} - 25'$ East 60.97 feet to an iron pin and the place of beginning for the tract of land herein conveyed; thence continuing with said bearing South $2^{\circ} - 25'$ East and with the center line of Township Road 110.83 feet to an iron pin; thence again on the center line of said township road to an iron pin, the long chord of for the course bears South $38^{\circ} - 39'$ East 74.43 feet; thence South $23^{\circ} - 57'$ West 18.21 feet to a 12" Soft Maple Tree; thence leaving said township road, South $76^{\circ} - 53'$ West 106.48 feet to a stake; thence North $6^{\circ} - 43'$ West 152.18 feet to a second stake; thence North $53^{\circ} - 02'$ East 97.29 feet to the place of beginning, a Sycamore bears West 9.8 feet, containing 0.35 Acres, more or less.

Approved - Mathematically
Hocking County Engineer's office
By _____ Date _____

Donated, June 1982, by
ALBERT W. SEABRIGHT, P.E., P.
COUNTY ENGINEER 1949 - 196

Donated, June 1982, by
ALBERT W. SEABRIGHT, P.E., P.S.
COUNTY ENGINEER 1949 - 1967


Approved - Mathematically
Hocking County Engineer's office
By _____ Date _____

Ted Lemon
Reserve
Pt Lots Sec 17 Green Twp
Hocking County Ohio
RW Seabright
Mar 23, Apr 6 1967

Albert W Seabright
Apr 9 1967

Part Lot 5
Sec 17 Green Twp
3.7692 ac.

Green 17
3.7692 ac.



Green 17

RECORD COPY
1967

**Reserve Parcel Ted Lemon
Pt. Lot 5, Green Sec. 17**

Being a part of Lot 5, Section 17, Green Township, T13N, R16W, Hocking County and State of Ohio, and further described as beginning at the southeast corner of said Lot 5 at an iron pin set on the east line of said Section 17, a 16-inch Pignut bears North 45 degrees West 25 feet and the northeast corner of said Section 17 bears North 10 chains; thence from said iron pin and on said east line of the section North 4 degrees - 40 minutes East 132.70 feet to a point in the center line of the Township Road; thence on the center line of the road, North 59 degrees - 32 minutes West 111.84 feet to a point, North 74 degrees - 41 minutes West 80 feet to a spike; thence North 71 degrees - 14 minutes West 283.70 feet to a spike; thence North 69 degrees - 43 minutes - 30 seconds West 206.27 feet to an iron pin; thence leaving said road South 25 degrees - 25 minutes West 18.33 feet to a blazed 12-inch Maple tree; thence South 31 degrees - 32 minutes - 30 seconds West 303.01 feet to an iron pin on the south line of said Lot 5, an 18-inch Beech bears North 40 degrees - 30 minutes East 12.7 feet; thence on said south line South 82 degrees - 56 minutes - 45 seconds East 797.37 feet to the place of beginning, containing 3.7692 acres, more or less, but subject to the rights of said Township road.

The description herein prepared from survey by Albert Seabright March 23-April 6, 1967.


Approved - Mathematically
Hocking County Engineer's office
By _____ Date _____

Donated, June 1982, by
ALBERT W. SEABRIGHT, P.E., P.S.
COUNTY ENGINEER 1949 - 1967

SURVEY PLAT OF .5399 ACRE TRACT FOR CHESTER LEMON

Green 17
.5399 AC.

Situated in Green Township, Hocking County, Ohio; being part of the North-east quarter of Section 17, Township 13, Range 16.



CHESTER & EVA LEMON
200-544
.5399 ACRES

VIVIAN THOMPSON et al
(CALL AROUND)
109-238

SCALE

1" = 40'
0 10 20 30 40

LEGEND

- 3/4" iron pin found
- 5/8" iron pin with 1/4" plastic ID cap set to reset lost monumentation

REFERENCES

- Existing deed description
- Tax maps
- Existing monumentation

REFERENCE BEARING

North line of Section 17 as N 90° 00' 00" W.

Approved - Mathematically
Hocking County Engineer's Office
By D. Sn Date 10-30-86
* Existing Parcel

I hereby certify that an actual survey was made under my supervision of the premises shown hereon on the 29th day of October 1986 and that the plat is a correct representation of the premises as described by said survey.

Larry P. Gerstner
Registered Surveyor No. 6344

Survey by: EARTH WORKS - Surveying, Engineering, & Construction
119 West Main Street, Logan, Ohio 43138 385-4260

SURVEY DESCRIPTION OF .5399 ACRE TRACT FOR CHESTER LEMON

Situated in Green Township, Hocking County, Ohio; being part of the Northeast quarter of Section 17, Township 13, Range 16; and being more particularly described as follows:

Commencing for reference at the Northwest corner of the Northeast quarter of Section 17; thence with the North line of Section 17 North 90 degrees 00 minutes 00 seconds West a distance of 511.50 feet to a point; thence South 30 degrees 50 minutes 16 seconds East a distance of 1247.98 feet to a 5/8" iron pin set and being the point of Beginning of the tract of land to be described; thence North 60 degrees 07 minutes 47 seconds East a distance of 175.55 feet to a point in the center of Township Road 350, Scout Road, and passing a 3/4" iron pin found at a distance of 159.33 feet; thence along said Township Road 350 for 77.00 feet and then leaving said Township Road 350 South 29 degrees 02 minutes 33 seconds East a total distance of 135.99 feet to a 3/4" iron pin found; thence South 62 degrees 31 minutes 51 seconds West a distance of 180.14 feet to a 3/4" iron pin found; thence North 27 degrees 01 minutes 13 seconds West a distance of 128.59 feet to the point of beginning containing .5399 acres more or less, subject to the public easement of said Township Road 350 and any private easements of record.

The above .5399 acre survey is intended to describe the entire tract of land as deeded to Chester and Eva Lemon, deed reference Volume 200, Page 544, Hocking County Recorder's Office. This survey was based upon information obtained from the existing deed description, tax maps, and existing monumentation. The reference bearing for this survey is the North line of Section 17 as North 90 degrees 00 minutes 00 seconds West. The iron pin set by this survey is to reset monumentation of a previous survey that has been lost and is capped by a 1-1/4" plastic identification cap. The above described property was surveyed by Larry P. Gerstner, Ohio Registered Surveyor No. 6344, on October 29, 1986.



Larry P. Gerstner

Approved - Mathematically
Hocking County Engineer's office
By *D. Sm* Date *10-30-86*
** Existing Parcel*

Survey by:
EARTH WORKS - Surveying, Engineering, and Construction
119 West Main Street, Logan, Ohio 43138 385-4260

PLAT OF A 50.000 ACRE TRACT FOR ROBERT AND CAROL FREY

GREEN 16, 17, 22, 23


TOTAL 50.00 ac

Situated in Green Township, Hocking County, Ohio; being part of the Southeast quarter of the Southeast quarter and the Southwest quarter of the Southeast quarter, both of Section 23, part of the Northeast quarter of Section 22, part of the South half of the Southwest quarter of Section 17, and part of the Northwest quarter of Section 16, all of Township 13, Range 16.

LEGEND

- 5/8" x 30" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 set
- ▲ MAG nail set
- Stone found

Northeast corner of the Southeast quarter of the Southeast quarter of Section 23
Point of Beginning



REFERENCES:

- Tax maps
 - Deed descriptions
 - Previous surveys
 - Existing monumentation
 - Existing public road
- Approved - Mathematically
Hocking County Engineer's Office

DATE 1-27-00

REFERENCE BEARING:

North line of Section 16 as North 90 degrees 00 minutes 00 seconds East. Bearings are based upon an assumed meridian and are to denote angles only.


CERTIFICATION:

I hereby certify that an actual survey was made under my supervision of the premises shown hereon on the 18th day of September, 2000 and that the plat is a correct representation of the premises as described by said survey.

Larry P. Gerstner
Registered Surveyor No. 6344

Survey by:

Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138
(740) 385-4260



SURVEY DESCRIPTION OF A 50.000 ACRE TRACT FOR ROBERT AND CAROL FREY

Situated in Green Township, Hocking County, Ohio; being part of the Southeast quarter of the Southeast quarter and the Southwest quarter of the Southeast quarter, both of Section 23, part of the Northeast quarter of Section 22, part of the South half of the Southwest quarter of Section 17, and part of the Northwest quarter of Section 16, all of Township 13, Range 16; and being more particularly described as follows:

Beginning at a stone found at the Northeast corner of the Southeast quarter of the Southeast quarter of Section 23; thence with the East line of Section 23 South 0 degrees 13 minutes 23 seconds West a distance of 612.93 feet to a 5/8" iron pin set;

thence going into Section 17 South 85 degrees 53 minutes 12 seconds East a distance of 199.82 feet to a 5/8" iron pin set;

thence North 86 degrees 30 minutes 31 seconds East a distance of 609.62 feet to a MAG nail set in the center of Township Road 356, Mowery Lehman Road, and passing 5/8" iron pins set at distances of 335.61 feet and 577.89 feet;

thence with the center of said Township Road 356 the following seven bearings and distances:

1) South 24 degrees 04 minutes 53 seconds West a distance of 22.09 feet to a MAG nail set;

2) South 27 degrees 12 minutes 14 seconds West a distance of 198.23 feet to a MAG nail set;

3) South 24 degrees 59 minutes 47 seconds West a distance of 351.40 feet to a MAG nail set;

4) South 30 degrees 06 minutes 27 seconds West a distance of 350.20 feet to a MAG nail set and passing into Section 16 at a distance of 291.19 feet;

5) South 26 degrees 39 minutes 46 seconds West a distance of 72.68 feet to a MAG nail set;

6) South 17 degrees 05 minutes 24 seconds West a distance of 71.75 feet to a MAG nail set;

7) South 6 degrees 45 minutes 47 seconds West a distance of 34.11 feet to a MAG nail set;

thence leaving the center of said Township Road 356 North 64 degrees 08 minutes 09 seconds West a distance of 368.31 feet to a 5/8" iron pin set, passing 5/8" iron pins set at distances of 30.59 feet and 206.74 feet and passing into Section 22 at a distance of 366.09 feet;

thence North 85 degrees 43 minutes 22 seconds West a distance of 461.71 feet to a 5/8" iron pin set and passing a 5/8" iron pin set at a distance of 184.57 feet;

thence South 88 degrees 17 minutes 34 seconds West a distance of 1130.02 feet to a 5/8" iron pin set and passing a 5/8" iron pin set at a distance of 483.87 feet;

thence North 20 degrees 22 minutes 25 seconds East a distance of 1131.31 feet to a 5/8" iron pin set, passing into Section 23 at a distance of 60.81 feet, and passing a 5/8" iron pin set at a distance of 649.82 feet;

thence North 73 degrees 38 minutes 03 seconds East a distance of 1254.43 feet to the point of beginning, containing 50.000 acres more or less, with 10.499 acres more or less being in Section 17, 1.219 acres more or less being in Section 16, 1.460 acres more or less being in Section 22, and 36.822 acres more or less being in Section 23, and subject to the public easement of said Township Road 356 and any other public or private easements of record.

The above 50.000 acre survey is intended to describe part of the 168 acre Tract Four, part of the 82.5 acre Tract Six, part of the 165 acre Tract Seven, part of the 40 acre Tract Nine, and part of the 40 acre Tract Thirteen all as deeded to Larry P. Gerstner by deed reference Volume OR167, Page 827, Hocking County Recorder's Office. This survey was based upon information obtained from tax maps, deed descriptions, previous surveys, existing monumentation and an existing public road. The reference bearing for this survey is the North line of Section 16 as North 90 degrees 00 minutes 00 seconds East. Bearings are based upon an assumed meridian and are to denote angles only. All iron pins set by this survey are 5/8" by 30" and are capped by a 1-1/4" plastic identification cap stamped LPG-6344. The above described property was surveyed by Larry P. Gerstner, Ohio Registered Surveyor No. 6344, as completed on September 18, 2000.



Approved - Mathematically
Hocking County Engineer's Office

BY LPG DATE 9-27-00

A handwritten signature of Larry P. Gerstner in cursive script, written over a horizontal line.



Survey by:

Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138 385-4260

PLAT OF A 1.283 ACRE TRACT FOR THE PATRICIA TOLLIVER

GREEN 17
1.283 Ac.

Situated in Green Township, Hocking County, Ohio; being part of Fractional Lot 1 of Section 17, Township 13, Range 16.



SCALE:
1" = 100'

REFERENCES:

- Tax maps
- Deed descriptions
- Previous surveys
- Existing monumentation
- Existing public road

LEGEND

- ★ Point
- 5/8" x 30" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 set
- ▲ MAG nail set

CONDITIONAL APPROVAL/
TRANSFER Not to be used as
separate building site or
transferred as an independent
parcel in the future without
Planning Commission and/or
Health Department approval

Mathematically
Engineering's Office

MAW DATE 3-8-01

REFERENCE BEARING:

East line of Section 17 as North 0 degrees 06 minutes 44 seconds West. Bearings are based upon an assumed meridian and are to denote angles only.

CERTIFICATION:

I hereby certify that an actual survey was made under my supervision of the premises shown hereon on the 8th day of February, 2001 and that the plat is a correct representation of the premises as described by said survey.

Larry P. Gerstner
Registered Surveyor No. 6344

Survey by:

Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138
(740) 385-4260

SURVEY DESCRIPTION OF A 1.283 ACRE TRACT FOR PATRICIA TOLLIVER

Situated in Green Township, Hocking County, Ohio; being part of Fractional Lot 1 of Section 17, Township 13, Range 16; and being more particularly described as follows:

Commencing for reference at a point at the Southeast corner of Section 17; thence with the East line of Section 17 North 0 degrees 06 minutes 44 seconds West a distance of 492.19 feet to a 5/8" iron pin set and being the point of **Beginning** of the tract of land to be described;

thence leaving the East line of Section 17 South 35 degrees 12 minutes 04 second West a distance of 402.59 feet to a MAG nail set in the center of Township Road 352, Jake Tom Road, and passing a 5/8" iron pin set at a distance of 388.02 feet;

thence with the center of said Township Road 352 the following four bearings and distances:

- 1) North 40 degrees 04 minutes 17 seconds West a distance of 11.64 feet to a MAG nail set;
- 2) North 51 degrees 14 minutes 39 seconds West a distance of 54.15 feet to a MAG nail set;
- 3) North 65 degrees 05 minutes 40 seconds West a distance of 73.93 feet to a MAG nail set;
- 4) North 70 degrees 18 minutes 08 seconds West a distance of 52.33 feet to a MAG nail set;

thence leaving the center of said Township Road 352 North 31 degrees 32 minutes 27 seconds East a distance of 180.89 feet to a 5/8" iron pin set and passing 5/8" iron pins set at distances of 15.36 feet and 94.33 feet;

thence North 74 degrees 39 minutes 53 seconds East a distance of 314.70 feet to the point of beginning, containing 1.283 acres more or less, and subject to the public easement of said Township Road 352 and any other public or private easements of record.

The above 1.283 acre survey is intended to describe part of the 30 acre Tract 21 as deeded to Larry P. Gerstner by deed reference Volume OR167, Page 827, Hocking County Recorder's Office. This survey was based upon information obtained from tax maps, deed descriptions, previous surveys, existing monumentation, and an existing public road. The reference bearing for this survey is the East line of Section 17 as North 0 degrees 06 minutes 44 seconds West. Bearings are based upon an assumed meridian and are to denote angles only. All iron pins set by this survey are 5/8" by 30" and are capped by a 1-1/4" plastic identification cap stamped LPG-6344. The above described property was surveyed by Larry P. Gerstner, Ohio Registered Surveyor No. 6344, on February 8, 2001.



Approved - Mathematically
Hocking County Engineer's Office

J. H. Hester

DATE: 3-8-01

Larry P. Gerstner

CONDITIONAL APPROVAL/
TRANSFER Not to be used as
separate building site or
transferred as an independent
parcel in the future without
Planning Commission and/or
Health Department approval

Survey by:

Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138 385-4260

GREEN 16+17

PLAT OF A 5.0028 ACRE TRACT FOR THE BOY SCOUT PROPERTY


5.0028 AC.

Situated in Green Township, Hocking County, Ohio; being part of the South half of the Southwest quarter of Section 17 and part of the Northwest quarter of Section 16, both of Township 13, Range 16.

Hocking County Engineer's Office

DATE 11-22-00

Northeast corner of the Northwest quarter of Section 16



SCALE: 1" = 200'

REFERENCES:

- Tax maps
- Deed descriptions
- Previous surveys
- Existing monumentation
- Existing public road

LEGEND

- 5/8" x 30" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 set
- ▲ MAG nail set
- ✱ Point

REFERENCE BEARING:

North line of Section 16 as North 90 degrees 00 minutes 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only.

CERTIFICATION:

I hereby certify that an actual survey was made under my supervision of the premises shown hereon on the 31st day of October, 2000 and that the plat is a correct representation of the premises as described by said survey.

Larry P. Gerstner
Registered Surveyor No. 6344

Survey by:

Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138
(740) 385-4260

SURVEY DESCRIPTION OF A 5.0028 ACRE TRACT FOR THE BOY SCOUT PROPERTY

Situated in Green Township, Hocking County, Ohio; being part of the South half of the Southwest quarter of Section 17 and part of the Northwest quarter of Section 16, both of Township 13, Range 16; and being more particularly described as follows:

Commencing for reference at a 5/8" iron pin set at the Northeast corner of the Northwest quarter of Section 16; thence with the North line of Section 16 North 90 degrees 00 minutes 00 seconds West a distance of 1300.93 feet to a 5/8" iron pin set; thence leaving the North line of Section 16 South 0 degrees 00 minutes 00 seconds West a distance of 32.38 feet to a 5/8" iron pin set, and being the point of **Beginning** of the tract of land to be described;

thence continuing South 0 degrees 00 minutes 00 seconds West a distance of 72.40 feet to a 5/8" iron pin set;

thence North 82 degrees 25 minutes 41 seconds West a distance of 641.36 feet to a 5/8" iron pin set and passing a 5/8" iron pin set at a distance of 489.37 feet;

thence South 60 degrees 00 minutes 00 seconds West a distance of 185.04 feet to a 5/8" iron pin set;

thence North 72 degrees 01 minute 14 seconds West a distance of 200.00 feet to a MAG nail set in the center of Township Road 356, Mowery Lehman Road, and passing a 5/8" iron pin set at a distance of 183.05 feet;


thence with the center of said Township Road 356 the following two bearings and distances:

1) North 30 degrees 06 minutes 27 seconds East a distance of 350.20 feet to a MAG nail set and passing into Section 17 at a distance of 59.01 feet;

2) North 24 degrees 59 minutes 47 seconds East a distance of 106.03 feet to a MAG nail set;

thence leaving the center of said Township Road 356 South 63 degrees 35 minutes 08 seconds East a distance of 855.05 feet to the point of beginning, passing 5/8" iron pins set at distances of 11.17 feet, 424.97 feet, and 519.42 feet, passing back into Section 16 at a distance of 782.26 feet, containing 5.0028 acres more or less with 3.5294 acres more or less being in Section 17 and 1.4734 acres more or less being in Section 16, and subject to the public easement of said Township Road 356 and any other public or private easements of record.

The above 5.0028 acre survey is intended to describe part of the 168 acre Tract Four and part of the 82.5 acre Tract Six, as deeded to Larry P. Gerstner by deed reference Volume OR167, Page 827, Hocking County Recorder's Office. This survey was based upon information obtained from tax maps, deed descriptions, previous surveys, existing monumentation and an existing public road. The reference bearing for this survey is the North line of Section 16 as North 90 degrees 00 minutes 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only. All iron pins set by this survey are 5/8" by 30" and are capped by a 1-1/4" plastic identification cap stamped LPG-6344. The above described property was surveyed by Larry P. Gerstner, Ohio Registered Surveyor No. 6344, as completed on October 31, 2000.



Reviewed - Mathematically
Hocking County Engineer's Office

M. H. ... DATE 11-22-00

Larry P. Gerstner

Survey by:



Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138 385-4260

PLAT OF A 54.491 ACRE TRACT FOR THE BOY SCOUT PROPERTY

GREEN 16+17

Situated in Green Township, Hocking County, Ohio; being part of the South half of the Southwest quarter of Section 17 and part of the Northwest quarter of Section 16, both of Township 13, Range 16.

54.491 Ac.



REFERENCES:

- Tax maps
- Deed descriptions
- Previous surveys
- Existing monumentation
- Existing public road

Approved - Mathematically
Hocking County Engineer's Office

LEGEND

[Signature] DATE 11-21-00

- × Point
- 5/8" iron pin with 1-1/4" plastic ID cap stamped SEYMOUR & ASSOC. found
- 5/8"x 30" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 set
- ▲ MAG nail set
- Stone found

REFERENCE BEARING:

North line of Section 16 as North 90 degrees 00 minutes 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only.

CERTIFICATION:

I hereby certify that an actual survey was made under my supervision of the premises shown hereon on the 31st day of October, 2000 and that the plat is a correct representation of the premises as described by said survey.

[Signature: Larry P. Gerstner]
Registered Surveyor No. 6344

Survey by: Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138
(740) 385-4260

SURVEY DESCRIPTION OF A 54.491 ACRE TRACT FOR THE BOY SCOUT PROPERTY

Situated in Green Township, Hocking County, Ohio; being part of the South half of the Southwest quarter of Section 17 and part of the Northwest quarter of Section 16, both of Township 13, Range 16; and being more particularly described as follows:

Beginning at a 5/8" iron pin set at the Northeast corner of the Northwest quarter of Section 16; thence leaving the North line of Section 16 South 53 degrees 26 minutes 25 seconds West a distance of 254.05 feet to a 5/8" iron pin set;

thence South 53 degrees 24 minutes 29 seconds West a distance of 1720.37 feet to a MAG nail set in the center of Township Road 350, Scout Road, and passing 5/8" iron pins set at distances of 461.14 feet, 801.91 feet, 1046.30 feet, 1182.51 feet, 1554.02 feet, and 1708.21 feet;

thence with the center of said Township Road 350 North 52 degrees 02 minutes 58 seconds West a distance of 150.00 feet to a MAG nail set;

thence leaving the center of said Township Road 350 North 37 degrees 57 minutes 02 seconds East a distance of 654.82 feet to a 5/8" iron pin set and passing 5/8" iron pins set at distances of 13.23 feet and 287.35 feet;

thence North 0 degrees 00 minutes 00 seconds East a distance of 1021.19 feet to a 5/8" iron pin set and passing 5/8" iron pins set at distances of 121.61 feet, 463.48 feet, and 535.88 feet, and passing into Section 17 at a distance of 568.26 feet;


thence North 17 degrees 56 minutes 09 seconds East a distance of 955.96 feet to a 5/8" iron pin with 1-1/4" plastic ID cap stamped SEYMOUR & ASSOC. found and passing a 5/8" iron pin set at a distance of 532.87 feet;

thence South 89 degrees 57 minutes 19 seconds East a distance of 425.01 feet to a 5/8" iron pin with 1-1/4" plastic ID cap stamped SEYMOUR & ASSOC. found;

thence South 89 degrees 57 minutes 28 seconds East a distance of 584.11 feet to a stone found at the Northeast corner of the South half of the Southwest quarter of Section 17;

thence South 0 degrees 06 minutes 32 seconds West a distance of 1361.68 feet to the point of beginning, passing a 5/8" iron pin with 1-1/4" plastic ID cap stamped SEYMOUR & ASSOC. found 3.93 feet West of the property line at a distance of 118.77 feet, containing 54.491 acres more or less with 16.843 acres more or less being in Section 16 and 37.648 acres more or less being in Section 16, and subject to the public easement of said Township Road 350 and any other public or private easements of record.

The above 54.491 acre survey is intended to describe part of the 168 acre Tract Four and part of the 82.5 acre Tract Six, as deeded to Larry P. Gerstner by deed reference Volume OR167, Page 827, Hocking County Recorder's Office. This survey was based upon information obtained from tax maps, deed descriptions, previous surveys, existing monumentation and an existing public road. The reference bearing for this survey is the North line of Section 16 as North 90 degrees 00 minutes 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only. All iron pins set by this survey are 5/8" by 30" and are capped by a 1-1/4" plastic identification cap stamped LPG-6344. The above described property was surveyed by Larry P. Gerstner, Ohio Registered Surveyor No. 6344, as completed on October 31, 2000.



Approved - Mathematically
Hocking County Engineer's Office

[Signature] DATE 11-21-00 *[Signature]*

Survey by:


Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138 385-4260

GREEN 16+(17)

PLAT OF A 7.558 ACRE TRACT FOR THE BOY SCOUT PROPERTY

Situated in Green Township, Hocking County, Ohio; being part of the South half of the Southwest quarter of Section 17 and part of the Northwest quarter of Section 16, both of Township 13, Range 16.

7.558Ac.



REFERENCES:

- Tax maps
- Deed descriptions
- Previous surveys
- Existing monumentation
- Existing public road

LEGEND

- 5/8" x 30" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 set
- ▲ MAG nail set
- ✱ Point

Logan County, Ohio
LPG 11-22-00

REFERENCE BEARING:

North line of Section 16 as North 90 degrees 00 minutes 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only.

CERTIFICATION:

I hereby certify that an actual survey was made under my supervision of the premises shown hereon on the 31st day of October, 2000 and that the plat is a correct representation of the premises as described by said survey.

Larry P. Gerstner
 Registered Surveyor No. 6344

Survey by: Larry P. Gerstner - Engineering and Surveying
 9 East Second Street, Suite A, Logan, Ohio 43138
 (740) 385-4260

SURVEY DESCRIPTION OF A 7.558 ACRE TRACT FOR THE BOY SCOUT PROPERTY

Situated in Green Township, Hocking County, Ohio; being part of the South half of the Southwest quarter of Section 17 and part of the Northwest quarter of Section 16, both of Township 13, Range 16; and being more particularly described as follows:

Commencing for reference at a 5/8" iron pin set at the Northeast corner of the Northwest quarter of Section 16; thence with the North line of Section 16 North 90 degrees 00 minutes 00 seconds West a distance of 1300.93 feet to a 5/8" iron pin set, and being the point of **Beginning** of the tract of land to be described;

thence leaving the North line of Section 16 South 0 degrees 00 minutes 00 seconds West a distance of 32.38 feet to a 5/8" iron pin set;

thence North 63 degrees 35 minutes 08 seconds West a distance of 855.05 feet to a MAG nail set in the center of Township Road 356, Mowery Lehman Road, passing into Section 17 at a distance of 72.79 feet and passing 5/8" iron pins set at distances of 335.63 feet, 430.08 feet, and 843.88 feet;

thence with the center of said Township Road 356 the following two bearings and distances:

- 1) North 24 degrees 59 minutes 47 seconds East a distance of 245.37 feet to a MAG nail set;
- 2) North 27 degrees 12 minutes 14 seconds East a distance of 198.23 feet to a MAG nail set;

thence leaving the center of said Township Road 356 South 62 degrees 47 minutes 46 seconds East a distance of 642.56 feet to a 5/8" iron pin set and passing 5/8" iron pins set at distances of 10.74 feet and 285.24 feet;

thence South 0 degrees 00 minutes 00 seconds West a distance of 452.94 feet to the point of beginning, containing 7.558 acres more or less with 7.534 acres more or less being in Section 17 and .024 acres more or less being in Section 16, and subject to the public easement of said Township Road 356 and any other public or private easements of record.

The above 7.558 acre survey is intended to describe part of the 168 acre Tract Four and part of the 82.5 acre Tract Six, as deeded to Larry P. Gerstner by deed reference Volume OR167, Page 827, Hocking County Recorder's Office. This survey was based upon information obtained from tax maps, deed descriptions, previous surveys, existing monumentation and an existing public road. The reference bearing for this survey is the North line of Section 16 as North 90 degrees 00 minutes 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only. All iron pins set by this survey are 5/8" by 30" and are capped by a 1-1/4" plastic identification cap stamped LPG-6344. The above described property was surveyed by Larry P. Gerstner, Ohio Registered Surveyor No. 6344, as completed on October 31, 2000.



Hocking County Engineer's Office

MAW DATE 11-22-00

Larry P. Gerstner


Survey by:

Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138 385-4260

PLAT OF A 5.998 ACRE TRACT FOR THE BOY SCOUT PROPERTY

5.998 ac.

Situated in Green Township, Hocking County, Ohio; being part of the South half of the Southwest quarter of Section 17, Township 13, Range 16.



- REFERENCES:**
- Tax maps
 - Deed descriptions
 - Previous surveys
 - Existing monumentation
 - Existing public road

- LEGEND**
- Stone found
 - 5/8"x 30" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 set
 - ▲ MAG nail set
 - 5/8" iron pin with 1-1/4" plastic ID cap stamped SEYMOUR & ASSOC. found

REFERENCE BEARING:
 South line of Section 17 as South 90 degrees 00 minutes 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only.

CERTIFICATION:
 I hereby certify that an actual survey was made under my supervision of the premises shown hereon on the 31st day of October, 2000 and that the plat is a correct representation of the premises as described by said survey.

Larry P. Gerstner
 Registered Surveyor No. 6344

Survey by: Larry P. Gerstner – Engineering and Surveying
 9 East Second Street, Suite A, Logan, Ohio 43138
 (740) 385-4260

SURVEY DESCRIPTION OF A 5.998 ACRE TRACT FOR THE BOY SCOUT PROPERTY

Situated in Green Township, Hocking County, Ohio; being part of the South half of the Southwest quarter of Section 17, Township 13, Range 16; and being more particularly described as follows:

Commencing for reference at a stone found at the Northeast corner of the South half of the Southwest quarter of Section 17; thence South 89 degrees 57 minutes 28 seconds West a distance of 584.11 feet to a 5/8" iron pin with 1-1/4" plastic ID cap stamped SEYMOUR & ASSOC. found; thence South 89 degrees 57 minutes 19 seconds West a distance of 425.01 feet to a 5/8" iron pin with 1-1/4" plastic ID cap stamped SEYMOUR & ASSOC. found; thence South 17 degrees 56 minutes 09 seconds West a distance of 423.09 feet to a 5/8" iron pin set and being the point of **Beginning** of the tract of land to be described;

thence continuing South 17 degrees 56 minutes 09 seconds West a distance of 532.87 feet to a 5/8" iron pin set;

thence North 62 degrees 47 minutes 46 seconds West a distance of 642.56 feet to a MAG nail set in the center of Township Road 356, Mowery Lehman Road, and passing 5/8" iron pins set at distances of 357.32 feet and 631.82 feet;

thence with the center of said Township Road 356 the following three bearings and distances:

1) North 24 degrees 04 minutes 53 seconds East a distance of 168.23 feet to a MAG nail set and passing a MAG nail set at a distance of 22.09 feet

2) North 12 degrees 07 minutes 42 seconds East a distance of 84.14 feet to a MAG nail set;

3) North 1 degree 43 minutes 43 seconds East a distance of 49.99 feet to a MAG nail set;

thence leaving the center of said Township Road 356 South 83 degrees 36 minutes 22 seconds East a distance of 651.81 feet to the point of beginning, passing 5/8" iron pins set at distances of 23.99 feet and 211.65 feet, containing 5.998 acres more or less, and subject to the public easement of said Township Road 356 and any other public or private easements of record.

The above 5.998 acre survey is intended to describe part of the 82.5 acre Tract Six as deeded to Larry P. Gerstner by deed reference Volume OR167, Page 827, Hocking County Recorder's Office. This survey was based upon information obtained from tax maps, deed descriptions, previous surveys, existing monumentation and an existing public road. The reference bearing for this survey is the South line of Section 17 as South 90 degrees 00 minutes 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only. All iron pins set by this survey are 5/8" by 30" and are capped by a 1-1/4" plastic identification cap stamped LPG-6344. The above described property was surveyed by Larry P. Gerstner, Ohio Registered Surveyor No. 6344, as completed on October 31, 2000.



Approved - Mathematically
Hocking County Engineer's Office

LPG DATE 11-22-00

Larry P. Gerstner

Survey by:

Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138 385-4260



Green Twp.
Sec. 17
Easement only

PLAT OF A CENTERLINE SURVEY OF A 30.00 FEET WIDE BY 620.85 FEET LONG
SHARED EASEMENT OF INGRESS AND EGRESS FOR THE BOY SCOUT PROPERTY

Situated in Green Township, Hocking County, Ohio; being part of Fractional Lot 1 of Section 17, Township 13, Range 16.



Approved - ~~Mathematically~~ ^{Easement Only}
Hocking County Engineer's Office
BY JL WB DATE 10-27-03



- REFERENCES:
- Tax maps
 - Deed descriptions
 - Previous surveys
 - Existing monumentation
 - Existing public road

- LEGEND
- 5/8" iron pin found
 - 5/8"x 30" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 set
 - ⊙ 5/8" iron pin with 1-1/4" plastic ID cap stamped SEYMOUR & ASSOC found

REFERENCE BEARING:
East line of Section 17 as North 0 degrees 06 minutes 44 seconds West. Bearings are based upon an assumed meridian and are to denote angles only.

CERTIFICATION:
I hereby certify that an office survey was made on October 21, 2003 under my supervision of the premises shown hereon from an actual field survey done on the 8th day of February, 2001 and that the plat is a correct representation of the premises as described by said survey.

Larry P. Gerstner
Registered Surveyor No. 6344

Survey by: Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138
(740) 385-4260

CENTERLINE SURVEY DESCRIPTION OF A 30.00 FEET WIDE BY 620.85 FEET LONG SHARED EASEMENT OF INGRESS AND EGRESS FOR THE BOY SCOUT PROPERTY

Situated in Green Township, Hocking County, Ohio; being part of Fractional Lot 1, Section 17, Township 13, Range 16; being a 30.00 feet wide by 620.85 feet long shared centerline easement of ingress and egress; and being more particularly described as follows:

Commencing for reference at a 5/8" iron pin found at the Northeast corner of Fractional Lot 9; thence with the East line of Section 17 South 0 degrees 06 minutes 44 seconds East a distance of 1998.85 feet to a 5/8" iron pin set; thence leaving the East line of Section 17 South 73 degrees 22 minutes 18 second West a distance of 912.52 feet to a 5/8" iron pin with 1-1/4" plastic ID cap stamped SEYMOUR & ASSOC. found in the center of Township Road 352, Jake Tom Road, and being the point of **Beginning** of a 30.00 feet wide by 620.85 feet long shared easement of ingress and egress;

thence leaving the center of said Township Road 352 North 21 degrees 42 minutes 31 seconds East a distance of 43.16 feet to a 5/8" iron pin set;

thence North 15 degrees 47 minutes 50 seconds East a distance of 185.64 feet to a 5/8" iron pin set;

thence North 30 degrees 15 minutes 40 seconds East a distance of 38.19 feet to a 5/8" iron pin set;

thence North 75 degrees 10 minutes 53 seconds East a distance of 44.82 feet to a 5/8" iron pin set;

thence South 89 degrees 49 minutes 28 seconds East a distance of 93.45 feet to a 5/8" iron pin set;

thence South 80 degrees 39 minutes 58 seconds East a distance of 215.59 feet to a 5/8" iron pin set and being the end of a 30.00 feet wide by 620.85 feet long shared easement of ingress and egress, subject to the public easement of said Township Road 352 and any other public or private easements of record.

The above surveyed 30.00 feet wide by 620.85 feet long shared easement of ingress and egress is intended to describe part of the 30 acre Tract 21, as deeded to Larry P. Gerstner by deed reference Volume OR167, Page 827, and part of the 8.08 acre surveyed tract as deeded to Donald D. Taylor Jr. and Roseann M. Warden by deed reference Volume OR89, Page 162, both of the Hocking County Recorder's Office. This survey was based upon information obtained from tax maps, deed descriptions, previous surveys, existing monumentation, and an existing public road. The reference bearing for this survey is the East line of Section 17 as North 0 degrees 06 minutes 44 seconds West. Bearings are based upon an assumed meridian and are to denote angles only. All iron pins set by this survey are 5/8" by 30" and are capped by a 1-1/4" plastic identification cap stamped LPG-6344. The above described property was office surveyed on October 21, 2003 by Larry P. Gerstner, Ohio Registered Surveyor No. 6344, from an actual field survey done on February 8, 2001.



Easement Only
Approved - Mathematically
Hocking County Engineer's Office
BY JWSB DATE 10-27-03

A handwritten signature of Larry P. Gerstner in black ink, written over a horizontal line.



Survey by:
Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138 385-4260

GREEN 17

PLAT OF A 2.696 ACRE TRACT FOR THE BOY SCOUT PROPERTY

2.696 ac

Situated in Green Township, Hocking County, Ohio; being part of Fractional Lot 1 of Section 17, Township 13, Range 16.



REFERENCES:

- Tax maps
- Deed descriptions
- Previous surveys
- Existing monumentation
- Existing public road

LEGEND

- × Point
- 5/8" x 30" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 set
- ▲ MAG nail set

REFERENCE BEARING:

BY *[Signature]* DATE 3-8-01

East line of Section 17 as North 0 degrees 06 minutes 44 seconds West. Bearings are based upon an assumed meridian and are to denote angles only.

CERTIFICATION:

I hereby certify that an actual survey was made under my supervision of the premises shown hereon on the 8th day of February, 2001 and that the plat is a correct representation of the premises as described by said survey.

[Signature]
Registered Surveyor No. 6344

Survey by: Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138
(740) 385-4260

SURVEY DESCRIPTION OF A 2.696 ACRE TRACT FOR THE BOY SCOUT PROPERTY

Situated in Green Township, Hocking County, Ohio; being part of Fractional Lot 1 of Section 17, Township 13, Range 16; and being more particularly described as follows:

Commencing for reference at a point at the Southeast corner of Section 17; thence with the East line of Section 17 North 0 degrees 06 minutes 44 seconds West a distance of 492.19 feet to a 5/8" iron pin set and being the point of **Beginning** of the tract of land to be described;

thence leaving the East line of Section 17 South 74 degrees 39 minutes 53 second West a distance of 314.70 feet to a 5/8" iron pin set;

thence South 31 degrees 32 minutes 27 seconds West a distance of 180.89 feet to a MAG nail set in the center of Township Road 352, Jake Tom Road, and passing 5/8" iron pins set at distances of 86.56 feet and 165.53 feet;

thence with the center of said Township Road 352 the following two bearings and distances:

- 1) North 70 degrees 18 minutes 08 seconds West a distance of 52.55 feet to a MAG nail set;
- 2) North 70 degrees 35 minutes 02 seconds West a distance of 144.24 feet to a MAG nail set;

thence leaving the center of said Township Road 352 North 34 degrees 11 minutes 12 seconds East a distance of 329.16 feet to a 5/8" iron pin set and passing 5/8" iron pins set at distances of 16.83 feet and 133.29 feet;

thence North 77 degrees 04 minutes 08 seconds East a distance of 408.66 feet to a 5/8" iron pin set on the East line of Section 17;

thence with the East line of Section 17 South 0 degrees 06 minutes 44 seconds East a distance of 192.00 feet to the point of beginning, containing 2.696 acres more or less, and subject to the public easement of said Township Road 352 and any other public or private easements of record.

The above 2.696 acre survey is intended to describe part of the 30 acre Tract 21 as deeded to Larry P. Gerstner by deed reference Volume OR167, Page 827, Hocking County Recorder's Office. This survey was based upon information obtained from tax maps, deed descriptions, previous surveys, existing monumentation, and an existing public road. The reference bearing for this survey is the East line of Section 17 as North 0 degrees 06 minutes 44 seconds West. Bearings are based upon an assumed meridian and are to denote angles only. All iron pins set by this survey are 5/8" by 30" and are capped by a 1-1/4" plastic identification cap stamped LPG-6344. The above described property was surveyed by Larry P. Gerstner, Ohio Registered Surveyor No. 6344, on February 8, 2001.



Hocking County Engineer's Office
MHW 3-8-01
DIVISION REGULATIONS WAIVED
PENDING HEALTH DEPT. APPROVAL
BY JY DATE 3-8-01

A handwritten signature of Larry P. Gerstner in cursive script, written over a horizontal line.

Survey by:


Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138 385-4260

PLAT OF A 69.825 ACRE TRACT FOR THE BOY SCOUT PROPERTY

Green Twp.
Tot. 69.825 Ac.

Situated in Green Township, Hocking County, Ohio; being part of the South half of the Southwest quarter of Section 17 and part of the Northwest quarter of Section 16, both of Township 13, Range 16.

32.177 Ac. Sec. 16
37.648 Ac. Sec. 17



SCALE:
1" = 400'

Approved - Mathematically
Hocking County Engineer's Office

BY *gnwb* DATE 2-7-03



- REFERENCES:
- Tax maps
 - Deed descriptions
 - Previous surveys
 - Existing monumentation
 - Existing public road

LEGEND

- Point
- 5/8" iron pin with 1-1/4" plastic ID cap stamped SEYMOUR & ASSOC. found
- 5/8"x 30" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 set
- ▲ MAG nail set
- Stone found

REFERENCE BEARING:

North line of Section 16 as North 90 degrees 00 minutes 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only.

CERTIFICATION:

I hereby certify that an actual survey was made under my supervision of the premises shown hereon on 5th day of february, 2003 from actual field work completed the 31st day of October, 2000 and that the plat is a correct representation of the premises as described by said survey.

Larry P. Gerstner
Registered Surveyor No. 6344

Survey by: Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138
(740) 385-4260

SURVEY DESCRIPTION OF A 69.825 ACRE TRACT FOR THE BOY SCOUT PROPERTY

Situated in Green Township, Hocking County, Ohio; being part of the South half of the Southwest quarter of Section 17 and part of the Northwest quarter of Section 16, both of Township 13, Range 16; and being more particularly described as follows:

Beginning at a 5/8" iron pin set at the Northeast corner of the Northwest quarter of Section 16; thence leaving the North line of Section 16 South 53 degrees 26 minutes 25 seconds West a distance of 254.05 feet to a 5/8" iron pin set;

thence South 53 degrees 24 minutes 29 seconds West a distance of 801.91 feet to a 5/8" iron pin set, and passing a 5/8" iron pin set at a distance of 461.14 feet;

thence South 36 degrees 45 minutes 36 seconds East a distance of 259.96 feet to a 5/8" iron pin set;

thence South 81 degrees 03 minutes 02 seconds East a distance of 540.83 feet to a MAG nail set in the center of Township Road 350, Scout Road, and passing a 5/8" iron pin set at a distance of 329.61 feet;

thence with the center of said Township Road 350 the following twelve bearings and distances:

- 1) South 31 degrees 05 minutes 04 seconds West a distance of 115.82 feet to a 5/8" iron pin set;
- 2) South 51 degrees 54 minutes 41 seconds West a distance of 397.52 feet to a 5/8" iron pin set;
- 3) South 54 degrees 34 minutes 02 seconds West a distance of 324.74 feet to a 5/8" iron pin set;
- 4) South 46 degrees 40 minutes 27 seconds West a distance of 109.28 feet to a 5/8" iron pin set at

the end of Township Road 351, Davis Chapel Road;

5) South 50 degrees 37 minutes 04 seconds West a distance of 57.95 feet to a MAG nail set;

6) North 82 degrees 43 minutes 05 seconds West a distance of 272.76 feet to a MAG nail set;

7) North 67 degrees 37 minutes 51 seconds West a distance of 67.79 feet to a MAG nail set;

8) North 41 degrees 36 minutes 42 seconds West a distance of 80.98 feet to a MAG nail set;

9) North 36 degrees 09 minutes 09 seconds west a distance of 128.36 feet to a MAG nail set;

10) North 48 degrees 54 minutes 17 seconds West a distance of 92.89 feet to a MAG nail set;

11) North 52 degrees 02 minutes 58 seconds West a distance of 168.61 feet to a MAG nail set;

12) North 52 degrees 02 minutes 58 seconds West a distance of 150.00 feet to a MAG nail set;

thence leaving the center of said Township Road 350 North 37 degrees 57 minutes 02 seconds East a distance of 654.82 feet to a 5/8" iron pin set and passing 5/8" iron pins set at distances of 13.23 feet and 287.35 feet;

thence North 0 degrees 00 minutes 00 seconds East a distance of 1021.19 feet to a 5/8" iron pin set and passing 5/8" iron pins set at distances of 121.61 feet, 463.48 feet, and 535.88 feet, and passing into Section 17 at a distance of 568.26 feet;

thence North 17 degrees 56 minutes 09 seconds East a distance of 955.96 feet to a 5/8" iron pin with 1-1/4" plastic ID cap stamped SEYMOUR & ASSOC. found and passing a 5/8" iron pin set at a distance of 532.87 feet;


thence South 89 degrees 57 minutes 19 seconds East a distance of 425.01 feet to a 5/8" iron pin with 1-1/4" plastic ID cap stamped SEYMOUR & ASSOC. found;

thence South 89 degrees 57 minutes 28 seconds East a distance of 584.11 feet to a stone found at the Northeast corner of the South half of the Southwest quarter of Section 17;

thence South 0 degrees 06 minutes 32 seconds West a distance of 1361.68 feet to the point of beginning, passing a 5/8" iron pin with 1-1/4" plastic ID cap stamped SEYMOUR & ASSOC. found 3.93 feet West of the property line at a distance of 118.77 feet, containing 69.825 acres more or less with

32.177 acres more or less being in Section 16 and 37.648 acres more or less being in Section 16, 17, and subject to the public easement of said Township Road 350 and any other public or private easements of record.

The above 69.825 acre survey is intended to describe part of the 168 acre Tract Four and part of the 82.5 acre Tract Six, as deeded to Larry P. Gerstner by deed reference Volume OR167, Page 827, Hocking County Recorder's Office. This survey was based upon information obtained from tax maps, deed descriptions, previous surveys, existing monumentation and an existing public road. The reference bearing for this survey is the North line of Section 16 as North 90 degrees 00 minutes 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only. All iron pins set by this survey are 5/8" by 30" and are capped by a 1-1/4" plastic identification cap stamped LPG-6344. The above described property was surveyed on February 5, 2003 by Larry P. Gerstner, Ohio Registered Surveyor No. 6344, from an actual field survey completed on October 31, 2000.



Approved - Mathematically
Hocking County Engineer's Office

BY J. W. B. DATE 2-7-03


Larry P. Gerstner

Survey by:
Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138 385-4260


GREEN 17
5.09 Ac.

PLAT OF A 5.090 ACRE TRACT FOR MARK LEHMAN

Situated in Green Township, Hocking County, Ohio; being part of Fractional Lot 11 of Section 17, Township 13, Range 16.



Center of Township Road 356, Mowery Lehman Road



LEGEND

- 5/8" x 30" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 previously set
- 5/8" x 30" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 set
- ▲ MAG nail set

REFERENCES:

- Tax maps
- Deed descriptions
- Previous surveys
- Existing monumentation
- Existing public road

REFERENCE BEARING:

West line of Section 17 as North 0 degrees 33 minutes 38 seconds East. Bearings are based upon an assumed meridian and are to denote angles only.

CERTIFICATION:

I hereby certify that an actual survey was made under my supervision of the premises shown hereon on the 11th day of July, 2001 and that the plat is a correct representation of the premises as described by said survey.

Larry P. Gerstner
Registered Surveyor No. 6344

Survey by: Larry P. Gerstner – Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138
(740) 385-4260

SURVEY DESCRIPTION OF A 5.090 ACRE TRACT FOR MARK LEHMAN

Situated in Green Township, Hocking County, Ohio; being part of Fractional Lot 11 of Section 17, Township 13, Range 16; and being more particularly described as follows:

Beginning at a 5/8" iron pin previously set at the Northwest corner of Fractional Lot 11 of Section 17; thence leaving the West line of Section 17 South 89 degrees 41 minutes 17 seconds East a distance of 471.99 feet to a MAG nail set in the center of Township Road 356, Mowery Lehman Road, and passing 5/8" iron pins set at distance of 333.03 feet and 455.76 feet;

thence with the center of said Township Road 356 the following three bearings and distances:

- 1) South 10 degrees 24 minutes 57 seconds East a distance of 65.20 feet to a MAG nail set;
- 2) South 5 degrees 32 minutes 10 seconds East a distance of 115.25 feet to a MAG nail set;
- 3) South 9 degrees 41 minutes 53 seconds East a distance of 106.27 feet to a MAG nail set;


thence leaving the center of said Township Road 356 South 58 degrees 44 minutes 48 seconds West a distance of 606.71 feet to a 5/8" iron pin set on the West line of Section 17 and passing 5/8" iron pins set at distances of 16.66 feet, 215.19 feet, and 398.43 feet;

thence with the West line of Section 17 North 0 degrees 33 minutes 38 seconds East a distance of 600.96 feet to the point of beginning, containing 5.090 acres more or less, and subject to the public easement of said Township Road 356, and any other public or private easements of record.

The above 5.090 acre survey is intended to describe part of the 41 acre Fractional Lot 11 as deeded to James and Mary Lehman, deed reference Volume 198, Page 517, Hocking County Recorder's Office. This survey was based upon information obtained from tax maps, deed descriptions, previous surveys, existing monumentation, and an existing public road. The reference bearing for this survey is the West line of Section 17 as North 0 degrees 33 minutes 38 seconds East. Bearings are based upon an assumed meridian and are to denote angles only. All iron pins set by this survey or previously set are 5/8" by 30" and are capped by a 1-1/4" plastic identification cap stamped LPG-6344. The above described property was surveyed by Larry P. Gerstner, Ohio Registered Surveyor No. 6344, on July 11, 2001.

Approved - Mathematically
Hocking County Engineer's Office

BY L.P.G. DATE 2-13-01







Survey by:

Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138 740-385-4260

PLAT OF A 7.647 ACRE TRACT FOR JAMES LEHMAN

Green Twp.
Sec. 17
7.647 Ac.

Situated in Green Township, Hocking County, Ohio; being part of the Northwest quarter of the Southwest quarter of Section 17, Township 13, Range 16.



LEGEND

- Point
- 5/8" X 30" iron pin with 1-1/4" plastic ID cap stamped SVE-8127 set
- 5/8" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 found
- △ MAG nail found
- Stone found

REFERENCES:

- Tax maps
- Deed descriptions
- Previous surveys
- Existing monumentation
- Existing public road

REFERENCE BEARING:

The West line of the Northwest quarter of the Southwest quarter as North 00 degrees 33 minutes 38 seconds East.
Bearings are based upon an assumed meridian and are to denote angles only.

CERTIFICATION:

I hereby certify that an actual survey was made under my supervision of the premises shown hereon on the 19th day of September, 2005 and that the plat is a correct representation of the premises as described by said survey.

S. Vince Evans
Registered Surveyor No. 8127

Survey by: SVE Surveying - S. Vince Evans P.S. 8127
37381 Davis Chapel Road, Logan, Ohio 43138
Phone (740) 380-3884
FAX (740) 380-0134

Approved - Mathematically
Hocking County Engineer's Office

BY *JM CW* DATE *9-28-05*

SURVEY DESCRIPTION OF A 7.647 ACRE TRACT FOR JAMES LEHMAN

Situated in Green Township, Hocking County, Ohio; being part of the Northwest quarter of the Southwest quarter of Section 17, Township 13, Range 16; and being more particularly described as follows:

Being part of a 35.91 acre tract as described in deed book Volume 198, Page 517 to James and Mary Lehman.

Commencing at a Stone found at the Southwest corner of the Northwest quarter of the Southwest quarter; Thence with the West line of Section 17, North 00 degrees 33 minutes 38 seconds East a distance of 263.51 feet to a 5/8" iron pin set, and being the point of **Beginning** of the tract of land to be described;

Thence with the West line of Section 17, North 00 degrees 33 minutes 38 seconds East a distance of 492.89 feet to a 5/8" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 found;

Thence leaving the West line of Section 17, North 58 degrees 44 minutes 47 seconds East a distance of 606.71 feet to a MAG nail found in the centerline of Township Road 356 (Mowery-Lehman Road), passing a 5/8" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 found at a distance of 208.28 feet, 391.52 feet, and 590.05 feet;

Thence with the centerline of said Township Road 356 (Mowery-Lehman Road), South 12 degrees 30 minutes 20 seconds East a distance of 109.30 feet to a Point;

Thence leaving the centerline of said Township Road 356 (Mowery-Lehman Road), North 65 degrees 57 minutes 47 seconds East a distance of 83.70 feet to a 5/8" iron pin set, passing a 5/8" iron pin set at a distance of 9.95 feet;

Thence South 07 degrees 39 minutes 01 seconds East a distance of 131.49 feet to a 5/8" iron pin set;

Thence South 73 degrees 10 minutes 46 seconds West a distance of 51.15 feet to a Point in the centerline of said Township Road 356 (Mowery-Lehman Road), passing a 5/8" iron pin set at a distance of 39.92 feet;

Thence with the centerline of said Township Road 356 (Mowery-Lehman Road), South 22 degrees 17 minutes 49 seconds East a distance of 96.40 feet to a Point;

Thence with the centerline of said Township Road 356 (Mowery-Lehman Road), South 19 degrees 55 minutes 47 seconds East a distance of 201.91 feet to a Point;

Thence leaving the centerline of said Township Road 356 (Mowery-Lehman Road), South 65 degrees 58 minutes 37 seconds West a distance of 763.69 feet, passing a 5/8" iron pin set at a distance of 15.39 feet and 192.85 feet, to the point of beginning and containing 7.647 acres, more or less, subject to the public easement of said Township Road 356 (Mowery-Lehman Road) and any other public or private easements of record.

The above 7.647 acre survey was based upon information obtained from tax maps, deed descriptions, previous surveys, existing monumentation, and an existing public road. The reference bearing for this survey is the West line of the Northwest quarter of the Southwest quarter as North 00 degrees 33 minutes 38 seconds East. Bearings are based upon an assumed meridian and are to denote angles only.


All iron pins set by this survey are 5/8" by 30" and are capped by a 1-1/4" plastic identification cap stamped "SVE-8127".

The above described property was surveyed by S. Vince Evans, Ohio Registered Surveyor No. 8127, on September 19, 2005.


S. Vince Evans, P. S. 8127

Survey by: SVE Surveying
S. Vince Evans, P. S. 8127
37381 Davis Chapel Road
Logan, Ohio 43138
Phone (740) 380-3884
FAX (740) 380-0134




Approved - Mathematically
Hocking County Engineer's Office
BY  DATE 9-28-05

PLAT OF A 8.178 ACRE TRACT FOR MIKE LEHMAN

Green Twp.
Sec. 17
8.178 Ac.

Situated in Green Township, Hocking County, Ohio; being part of the Northwest quarter of the Southwest quarter of Section 17, Township 13, Range 16.



LEGEND

- Point
- 5/8" X 30" iron pin with 1-1/4" plastic ID cap stamped SVE-8127 set
- 5/8" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 found
- △ MAG nail found
- Stone found

Approved - Mathematically
Hocking County Engineer's Office

BY JVEW DATE 9-28-05

REFERENCES:

- Tax maps
- Deed descriptions
- Previous surveys
- Existing monumentation
- Existing public road

REFERENCE BEARING:

The West line of the Northwest quarter of the Southwest quarter as North 00 degrees 33 minutes 38 seconds East.

Bearings are based upon an assumed meridian and are to denote angles only.


CERTIFICATION:

I hereby certify that an actual survey was made under my supervision of the premises shown hereon on the 19th day of September, 2005 and that the plat is a correct representation of the premises as described by said survey.

S. Vince Evans
Registered Surveyor No. 8127

Survey by:

SVE Surveying - S. Vince Evans P.S. 8127
37381 Davis Chapel Road, Logan, Ohio 43138
Phone (740) 380-3884
FAX (740) 380-0134



SCALE:

1" = 200'

SURVEY DESCRIPTION OF A 8.178 ACRE TRACT FOR MIKE LEHMAN

Situated in Green Township, Hocking County, Ohio; being part of the Northwest quarter of the Southwest quarter of Section 17, Township 13, Range 16; and being more particularly described as follows:

Being part of a 35.91 acre tract as described in deed book Volume 198, Page 517 to James and Mary Lehman.

Beginning at a Stone found at the Southwest corner of the Northwest quarter of the Southwest quarter; Thence with the West line of Section 17, North 00 degrees 33 minutes 38 seconds East a distance of 263.51 feet to a 5/8" iron pin set;

Thence leaving the West line of Section 17, North 65 degrees 58 minutes 37 seconds East a distance of 763.69 feet to a Point in the centerline of Township Road 356 (Mowery-Lehman Road), passing a 5/8" iron pin set at a distance of 570.84 feet and 748.30 feet;

Thence with the centerline of said Township Road 356 (Mowery-Lehman Road), South 22 degrees 40 minutes 13 seconds East a distance of 387.62 feet to a Point;

Thence with the centerline of said Township Road 356 (Mowery-Lehman Road), South 15 degrees 44 minutes 15 seconds East a distance of 131.11 feet to a Point;


Thence with the centerline of said Township Road 356 (Mowery-Lehman Road), South 05 degrees 52 minutes 41 seconds East a distance of 88.06 feet to a MAG nail found;

Thence leaving the centerline of said Township Road 356 (Mowery-Lehman Road), South 89 degrees 48 minutes 43 seconds West a distance of 894.10 feet, passing a 5/8" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 found at a distance of 28.76 feet, 200.64 feet, and 449.18 feet, to the point of beginning and containing 8.178 acres, more or less, subject to the public easement of said Township Road 356 (Mowery-Lehman Road) and any other public or private easements of record.

The above 8.178 acre survey was based upon information obtained from tax maps, deed descriptions, previous surveys, existing monumentation, and an existing public road. The reference bearing for this survey is the West line of the Northwest quarter of the Southwest quarter as North 00 degrees 33 minutes 38 seconds East. Bearings are based upon an assumed meridian and are to denote angles only.

All iron pins set by this survey are 5/8" by 30" and are capped by a 1-1/4" plastic identification cap stamped "SVE-8127".


The above described property was surveyed by S. Vince Evans, Ohio Registered Surveyor No. 8127, on September 19, 2005.


S. Vince Evans, P. S. 8127

Survey by: SVE Surveying
S. Vince Evans, P. S. 8127
37381 Davis Chapel Road
Logan, Ohio 43138
Phone (740) 380-3884
FAX (740) 380-0134



Approved - Mathematically
Hocking County Engineer's Office

BY  DATE 9-28-05

GREEN 17


PLAT OF A 12.287 ACRE TRACT FOR THE BOY SCOUT PROPERTY

12-287A-2

Situated in Green Township, Hocking County, Ohio; being part of the South half of the Southwest quarter of Section 17, Township 13, Range 16

LEGEND

- 5/8" x 30" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 set
- ▲ MAG nail set
- stone found



REFERENCE BEARING:

South line of Section 17 as South 90 degrees 00 minutes 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only.

CERTIFICATION:

I hereby certify that an actual survey was made under my supervision of the premises shown hereon on the 18th day of September, 2000 and that the plat is a correct representation of the premises as described by said survey.



Larry P. Gerstner
Registered Surveyor No. 6344

Survey by: Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138
(740) 385-4260

GREEN 17
2.00A-c.

PLAT OF A 2.000 ACRE TRACT FOR ROBERT AND CAROL FREY

Situated in Green Township, Hocking County, Ohio; being part of the South half of the Southwest quarter of Section 17, Township 13, Range 16.



- REFERENCES:
- Tax maps
 - Deed descriptions
 - Previous surveys
 - Existing monumentation
 - Existing public road



LEGEND

- Stone found
- 5/8" x 30" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 set
- * **CONDITIONAL APPROVAL/TRANSFER** Not to be used as separate building site or transferred as an independent parcel in the future without Planning Commission and/or Health Department approval

Approved - Mathematically *
Hocking County Engineer's Office
by *[Signature]* DATE 5-3-01

REFERENCE BEARING:

South line of Section 17 as South 90 degrees 00 seconds 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only.

CERTIFICATION:

I hereby certify that an actual survey was made under my supervision of the premises shown hereon on the 27th day of April, 2001 and that the plat is a correct representation of the premises as described by said survey.

[Signature]
Registered Surveyor No. 6344

Survey by: Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138
(740) 385-4260

SURVEY DESCRIPTION OF A 2.000 ACRE TRACT FOR ROBERT AND CAROL FREY

Situated in Green Township, Hocking County, Ohio; being part of the South half of the Southwest quarter of Section 17, Township 13, Range 16; and being more particularly described as follows:

Beginning at a stone found at the Northwest corner of the South half of the Southwest quarter of Section 17; thence North 89 degrees 48 minutes 43 seconds East a distance of 444.92 feet to a 5/8" iron pin set;

thence South 48 degrees 38 minutes 12 seconds West a distance of 594.84 feet to a 5/8" iron pin set on the West line of Section 17 and passing a 5/8" iron pin set at a distance of 296.26 feet;

thence with the West line of Section 17 North 0 degrees 13 minutes 23 seconds East a distance of 391.63 feet to the point of beginning, passing a 5/8" iron pin set at a distance of 168.89 feet, containing 2.000 acres more or less, and subject to any public or private easements of record.

The above 2.000 acre survey is intended to describe part of the 82.5 acre Tract Six as deeded to Larry P. Gerstner by deed reference Volume OR167, Page 827, Hocking County Recorder's Office. This survey was based upon information obtained from tax maps, deed descriptions, previous surveys, existing monumentation and an existing public road. The reference bearing for this survey is the South line of Section 17 as South 90 degrees 00 minutes 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only. All iron pins set by this survey are 5/8" by 30" and are capped by a 1-1/4" plastic identification cap stamped LPG-6344. The above described property was surveyed by Larry P. Gerstner, Ohio Registered Surveyor No. 6344, as completed on April 27, 2001.

Approved - Mathematically **f**
Hocking County Engineer's Office

BY LPG DATE 5-3-01

*** CONDITIONAL APPROVAL/
TRANSFER** Not to be used as
separate building site or
transferred as an independent
parcel in the future without
Planning Commission and/or
Health Department approval






Survey by:
Larry P. Gerstner - Engineering and Surveying

GREEN 17
10.287A_c.

PLAT OF A 10.287 ACRE TRACT FOR THE BOY SCOUT PROPERTY

Situated in Green Township, Hocking County, Ohio; being part of the South half of the Southwest quarter of Section 17, Township 13, Range 16.



LEGEND

- Stone found
- 5/8"x 30" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 set
- 5/8"x 30" (15" in roadway) iron pin with 1-1/4" plastic ID cap stamped LPG-6344 previously set
- △ MAG nail previously set

Reviewed - Mathematically
Hocking County Engineer's Office

[Signature] DATE 5-29-01



REFERENCE BEARING:

South line of Section 17 as South 90 degrees 00 seconds 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only.

CERTIFICATION:

I hereby certify that an actual survey was made under my supervision of the premises shown hereon on the 27th day of April, 2001 and that the plat is a correct representation of the premises as described by said survey.

[Signature]
Registered Surveyor No. 6344

Survey by: Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138
(740) 385-4260

GREEN 17
25.534 Ac.



PLAT OF A 25.534 ACRE TRACT FOR THE BOY SCOUT PROPERTY

Situated in Green Township, Hocking County, Ohio; being part of Fractional Lot 1 and all of Fractional Lot 9, both of Section 17, Township 13, Range 16.



Mathematically
Engineering Office

MAN 3-8-01



- REFERENCES:**
- Tax maps
 - Deed descriptions
 - Previous surveys
 - Existing monumentation
 - Existing public road

- LEGEND**
- 5/8" iron pin found
 - 5/8" x 30" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 set
 - ▲ MAG nail set
 - ⊙ 5/8" iron pin with 1-1/4" plastic ID cap stamped SEYMOUR & ASSOC found
 - ⊗ 2" OD iron pipe found

REFERENCE BEARING:
East line of Section 17 as North 0 degrees 06 minutes 44 seconds West. Bearings are based upon an assumed meridian and are to denote angles only.

CERTIFICATION:
I hereby certify that an actual survey was made under my supervision of the premises shown hereon on the 8th day of February, 2001 and that the plat is a correct representation of the premises as described by said survey.

Larry P. Gerstner
Registered Surveyor No. 6344

Survey by: Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138
(740) 385-4260

SURVEY DESCRIPTION OF A 25.534 ACRE TRACT FOR THE BOY SCOUT PROPERTY

Situated in Green Township, Hocking County, Ohio; being part of Fractional Lot 1 and all of Fractional Lot 9, both of Section 17, Township 13, Range 16; and being more particularly described as follows:

Beginning at a 5/8" iron pin found at the Northeast corner of Fractional Lot 9; thence with the East line of Section 17 South 0 degrees 06 minutes 44 seconds East a distance of 1998.85 feet to a 5/8" iron pin set; thence leaving the East line of Section 17 South 77 degrees 04 minutes 08 second West a distance of 408.66 feet to a 5/8" iron pin set; thence South 88 degrees 54 minutes 53 seconds West a distance of 50.54 feet to a 5/8" iron pin set; thence North 80 degrees 39 minutes 58 seconds West a distance of 210.78 feet to a 5/8" iron pin set; thence North 89 degrees 49 minutes 28 seconds West a distance of 80.75 feet to a 5/8" iron pin set; thence South 61 degrees 03 minutes 54 seconds West a distance of 16.71 feet to a 5/8" iron pin set; thence South 15 degrees 47 minutes 50 seconds West a distance of 181.12 feet to a 5/8" iron pin set; thence South 21 degrees 42 minutes 31 seconds West a distance of 43.86 feet to a MAG nail set in the center of Township Road 352, Jake Tom Road; thence with the center of said Township Road 352 North 70 degrees 35 minutes 02 seconds West a distance of 60.05 feet to a 5/8" iron pin with 1-1/4" plastic ID cap stamped SEYMOUR & ASSOC. found. thence leaving the center of said Township Road 352 North 21 degrees 42 minutes 31 seconds East a distance of 43.16 feet to a 5/8" iron pin set; thence North 15 degrees 47 minutes 50 seconds East a distance of 185.64 feet to a 5/8" iron pin set; thence North 30 degrees 15 minutes 40 seconds East a distance of 38.19 feet to a 5/8" iron pin set; thence North 75 degrees 10 minutes 53 seconds East a distance of 44.82 feet to a 5/8" iron pin set; thence South 89 degrees 49 minutes 28 seconds East a distance of 93.45 feet to a 5/8" iron pin set; thence South 80 degrees 39 minutes 58 seconds East a distance of 215.59 feet to a 5/8" iron pin set; thence North 35 degrees 55 minutes 13 seconds West a distance of 844.44 feet to a 5/8" iron pin with 1-1/4" plastic ID cap stamped SEYMOUR & ASSOC. found and passing 5/8" iron pins with 1-1/4" plastic ID caps stamped SEYMOUR & ASSOC. found at distances of 13.15 feet and 142.00 feet; thence North 89 degrees 48 minutes 40 seconds West a distance of 198.64 feet to a 5/8" iron pin with 1-1/4" plastic ID cap stamped SEYMOUR & ASSOC. found; thence North 0 degrees 12 minutes 08 seconds East a distance of 85.01 feet to a 5/8" iron pin set; thence North 81 degrees 37 minutes 01 second East a distance of 772.56 feet to a 5/8" iron pin set, from which a 5/8" iron pin found bears South 0 degrees 08 minutes 31 seconds West at a distance of 7.02 feet; thence North 0 degrees 08 minutes 31 seconds East a distance of 1152.49 feet to a 5/8" iron pin found, passing a 2" OD iron pipe found at a distance of 815.98 feet and a 5/8" iron pin found at a distance of 1010.81 feet; thence South 89 degrees 35 minutes 27 seconds East a distance of 361.78 feet to the point of beginning, containing 25.534 acres more or less, and subject to the public easement of said Township Road 352 and any other public or private easements of record.

The above 25.534 acre survey is intended to describe part of the 30 acre Tract 21 and all of the 10 acre Tract 18 both as deeded to Larry P. Gerstner by deed reference Volume OR167, Page 827, Hocking County Recorder's Office. This survey was based upon information obtained from tax maps, deed descriptions, previous surveys, existing monumentation, and an existing public road. The reference bearing for this survey is the East line of Section 17 as North 0 degrees 06 minutes 44 seconds West. Bearings are based upon an assumed meridian and are to denote angles only. All iron pins set by this survey are 5/8" by 30" and are capped by a 1-1/4" plastic identification cap stamped LPG-6344. The above described property was surveyed by Larry P. Gerstner, Ohio Registered Surveyor No. 6344, on February 8, 2001.



Hocking County Engineer's Office
MJK 3-8-01

Larry P. Gerstner

Survey by:
Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138 385-4260

Donated, June 1982, by
ALBERT W. SEABRIGHT, P.E., P.S.
COUNTY ENGINEER 1949 - 1964

Green 17
5.9757 ac.
NE Pt.

NW Cor
NE 1/4
Sec 17
Green Twp.

931'

N 85°-30' W 6.12 ch.

Approved - Mathematically
Hocking County Engineer's office
By _____ Date _____

P+Lot 6

S 5°-30' W 6.55 ch.

Age Tract
F.T. Lemon
Vol 192/86

SKETCH
PLAT FOR TED. LEMON
P+Lot 6 Sec 17
GREEN TWP.
HOCKING COUNTY OHIO

START

1. P. ps

1. P. ps

S 84°-18' E 406.32'

o Poplar

S 26° E 16 Link

by
A.W. Seabright
May 2 1953

P+Lot 6
5.9757 ac.

N 5°-15' E 620.75'

S 5°-45' W 652.00'

Witness

10" Locust N 23° E 18.5'

TOWNSHIP ROAD

Witness

12" W. Cherry N 80°-40' E 38.1'

and 6" W. Cherry

N 56°-44' W 73.26'

1. P.

N 84°-45' W 335.98'

Witness

12" W. Cherry

S 48°-10' W 21.35'

1. P.

Ted Lemon Tract
Immediately south of 4 Acre Tract Vol. 92/86
Green Section 17


Being a part Lot 6 in the northeast quarter of Section 17, Green Township, T13N, R16W, Hocking County and State of Ohio, and further described as follows: Beginning at the southwest corner of a 4 acre tract, owned by the Grantees herein, and recorded in Volume 92, Page 86, Hocking County Deed Record, now marked by an iron pipe corner which bears from the northwest corner of said northeast quarter, East 931 feet, and North 85° - 30' West 6.12 chains and South 5° - 30' West 6.55 chains, and from which a poplar tree bears South 26° East 16 links; thence from said iron pipe corner and on the south line of said 4 acre tract, South 84° - 18' East 406.32 feet to a second iron pipe corner marking the southeast corner of said 4 Acre tract; thence South 5° - 45' West 652 feet to an iron pin; a 14" Wild Cherry bears South 48° - 10' West 21.35 feet; thence North 84° - 45' West 335.98 feet to an iron pin in the center of the township road, a 12" Wild Cherry bears North 80° - 40' East 38.1 feet and a 6" Wild Cherry bears North 24° - 45' East 20.95 feet; thence with the center line of said township road, the long chord being, North 56° - 44' West 73.26 feet to an iron pin, a 10" Locust bears North 23° East 18.5 feet; thence leaving said township road, North 5° 15' East 620.75 feet to the place of beginning, and containing 5.9757 Acres, subject to the rights of the township road.

Approved - Mathematically
Hocking County Engineer's office
By _____ Date _____

Donated, June 1982, by
ALBERT W. SEABRIGHT, P.E., P.S.
COUNTY ENGINEER 1949 - 1984

THIS PAGE
LEFT BLANK
INTENTIONALLY

GREEN
11.8273 AC



NEW Lot 5 & Sec 17

Section 17 Green Twp.
Hocking Co. Ohio
Part Lot 5 11.8273 AC
Ted Lemon

MAR 23-30 1969
A W Seabright
Logan Ohio

Revised plat

Albert W. Seabright
Apr 7 1969

Donated, June 1982, by
ALBERT W. SEABRIGHT, P.E., P.S.
COUNTY ENGINEER 1949 - 1964

Approved - Mathematically
Hocking County Engineer's office
By _____ Date _____



5" W Cherry 516° 30' E 21.85'
10" Beech 539° 30' W 29.50'

18" Beech N 40° 30' E 12.1'


THEODORE LEMON
Pt. Lot 5, Sec. 17, Green Twp.

Being a part of Lot 5, Section 17, Green Township, T13N, T16W, Hocking County and State of Ohio, and further described as beginning at a spike set on the North section line at the northwest corner of said Lot 5 and 24 chains west of the northeast corner of said Section 17; thence South 6 degrees - 41 minutes East 58.83 feet to an iron pin, a 16" Locust bears South 45 degrees East 5.5 feet; thence South 5 degrees - 18 minutes - 20 seconds West 600.73 feet to an iron pin, a 5" Wild Cherry bears South 16 degrees - 30 minutes East 21.85 feet; and a 10" Beech bears South 39 degrees - 30 minutes West 29.50 feet; thence South 85 degrees - 15 minutes - 45 seconds East 760.02 feet to an iron pin, an 18" Beech bears North 40 degrees - 30 minutes East 12.7 feet; thence North 31 degrees - 32 minutes - 30 seconds East 303.08 feet to a blazed 12" Maple tree Corner; an iron pin in the center line of said Public Road bears North 23 degrees - 57 minutes East 18.21 feet; thence from said Maple Tree Corner, South 76 degrees - 53 minutes West 106.48 feet to a fence post; thence North 6 degrees - 43 minutes West 152.18 feet to a fence post; thence North 53 degrees - 02 minutes East 97.29 feet to an iron pin in said public road; thence with the said public road to the place of beginning, the following courses in turn, North 2 degrees - 25 minutes West 60.97 feet, North 45 degrees - 37 minutes West 193.78 feet, North 83 degrees - 07 minutes West 506.97 feet, and North 84 degrees - 10 minutes West 180.06 feet, containing 11.8273 Acres, more or less, but subject to the rights of the public road. This deed description prepared by Albert W. Seabright from survey made March 23-30, 1967.

5.010 Ac Green Twp.
5.929 Ac Sec. 17

Plat of Survey

STATE OF OHIO, HOCKING COUNTY,
GREEN TOWNSHIP, FRAC. LOT 4,
TWP. 13, RG. 16, SEC. 17



Bearings are based on the south line of Fractional Lot #4 being N 90°00'00" West by previous surveys.

REFERENCE MATERIAL:

Previous survey of 6 tracts, including the 10.939 acre tract, by Tobin-McFarland Surveying, Inc.

Adjoining surveys east, south, and west by Larry P. Gerstner, P.S. #6344

Adjoining survey to the north by Seymour and Associates

Deeds as shown on plat

LEGEND

- Indicates a 5/8" by 36" rebar set with a 1 1/4" TOBIN-McFARLAND identification cap.
- ⊗ 5/8" rebar found with a 1 1/4" I.D. cap stamped LPG-6344
- ⊕ 5/8" rebar found with a 1 1/4" I.D. cap stamped Seymour & Assoc.
- 5/8" rebar found, uncapped
- ⊞ Stone with cross-cut found

Approved - Mathematically
Hocking County Engineer's Office

BY WBS DATE 02-03-2006



Scale: 1 Inch = 200 Feet

WALTERS.crd, WALTERS3.pl
DISK B-99

C. Scott & Julie A. Walters
OR 349, Pg. 972, 10.020 Ac.

C. Scott & Julie A. Walters
OR 349, Pg. 972, 10.939 Ac.

Eugene & Barbara Smith
OR 176-250, 5.00 Ac.

698.41'
section 16
Charles Claypool, OR 169-469

Larry & Lori Ellinger
OR 115-183, 11.50 Ac.




FOR: SCOTT WALTERS
DATE: JANUARY 31, 2006

TOBIN-McFARLAND SURVEYING INC.

111 West Wheeling Street
Lancaster, Ohio 43130

BY: R. N. McFarland DATE: 1/31/06
Registered Professional Surveyor No. 7492

Ph. 740-687-1710 Fax 740-687-0877



Donald Taylor Jr. & Roseann Warden
OR 89-162, 8.08 Ac.

Larry & Lori Ellinger
OR 115-183, 3.00 Ac.

Larry Gerstner, TR.
OR 191-254
25.53 Ac.

C. Scott & Julie A. Walters
OR 349, Pg. 972
5.087 Ac.

C. Scott & Julie A. Walters
OR 349, Pg. 972, 5.515 Ac.

C. Scott & Julie A. Walters
OR 349, Pg. 972, 11.015 Ac.



TOBIN-McFARLAND SURVEYING, INC.

Professional Land Surveyors

111 West Wheeling Street
Lancaster, Ohio 43130
Phone (740) 687-1710
Fax (740) 687-0877

Description of 5.010 Acres

Situated in the State of Ohio, County of Hocking, Township of Green, Township 13, Range 16, Fractional Lot #4, section 17.

Being part of the 10.939 acre tract described in a deed to C. Scott and Julie A. Walters, recorded in official record 349, page 972, and being more fully described as follows:

Beginning at a point in Jake Tom Road (T. R. 352) and on a northeasterly line of said 10.939 acre tract, said point is located North 00°11'16" East a distance of 558.59 feet and North 39°30'47" West a distance of 235.36 feet from a 5/8 inch rebar found with a 1 1/4 inch identification cap stamped Seymour and Associates at the southeast corner of Fractional Lot #4 and said 10.939 acre tract;

thence South 06°00'00" West, passing a 5/8 inch rebar set with a 1 1/4 inch identification cap stamped Tobin-McFarland at 30.00 feet, a distance of 165.00 feet to a 5/8 inch rebar set with a 1 1/4 inch identification cap stamped Tobin-McFarland;

thence South 03°20'00" East a distance of 363.17 feet to a 5/8 inch rebar set with a 1 1/4 inch identification cap stamped Tobin-McFarland;

thence North 86°36'22" West a distance of 515.30 feet to a 5/8 inch rebar set with a 1 1/4 inch identification cap stamped Tobin-McFarland on the east side of the existing pavement of Scout Road (T. R. 350);

thence North 27°13'00" East a distance of 772.37 feet to a 5/8 inch rebar set with a 1 1/4 inch identification cap stamped Tobin-McFarland in Scout Road (T. R. 350);

thence South 39°30'47" East a distance of 247.20 feet to the point of beginning, containing **5.010 Acres**, and subject to all legal easements, restrictions, and rights-of-way of record.

Bearings are based on the south line of Fractional Lot #4 being North 90°00'00" West by previous surveys. Rebars set are 5/8 inch by 36 inches and have a 1 1/4 inch yellow plastic identification cap stamped "Tobin-McFarland". For additional information see plat of survey made in conjunction with and considered an integral part of this description.

This description is based on a survey made in January of 2006 by Tobin-McFarland Surveying, Inc., and was prepared by Robert N. McFarland, Registered Professional Surveyor No. 7492.



Robert N. McFarland 1/31/06
Robert N. McFarland, P.S.
January 31, 2006 originals are signed in blue ink

b-103 5.010

Approved - Mathematically
Hocking County Engineer's Office

BY WIB DATE 02-03-2006



TOBIN-McFARLAND SURVEYING, INC.

Professional Land Surveyors

111 West Wheeling Street
Lancaster, Ohio 43130
Phone (740) 687-1710
Fax (740) 687-0877

Description of 5.929 Acres

Situated in the State of Ohio, County of Hocking, Township of Green, Township 13, Range 16, Fractional Lot #4, section 17.

Being part of the 10.939 acre tract described in a deed to C. Scott and Julie A. Walters, recorded in official record 349, page 972, and being more fully described as follows:

Beginning at a 5/8 inch rebar found with a 1 1/4 inch identification cap stamped Seymour and Associates at the southeast corner of Fractional Lot #4 and said 10.939 acre tract;

thence South 89°30'33" West a distance of 207.92 feet to a stone found on the south line of Fractional Lot #4;

thence North 90°00'00" West, passing a 5/8 inch rebar found with a 1 1/4 inch identification cap stamped LPG-6344 at 698.41 feet, a distance of 731.94 feet to a point in Scout Road (T. R. 350) and at the southwest corner of said 10.939 acre tract;

thence North 30°21'30" East a distance of 88.82 feet to a 5/8 inch rebar set with a 1 1/4 inch identification cap stamped Tobin-McFarland on the west side of the existing pavement of said road;

thence North 54°25'31" East a distance of 290.78 feet a 5/8 inch rebar set with a 1 1/4 inch identification cap stamped Tobin-McFarland on the east side of the existing pavement of said road;

thence South 86°36'22" East a distance of 515.30 feet to a 5/8 inch rebar set with a 1 1/4 inch identification cap stamped Tobin-McFarland;

thence North 03°20'00" West a distance of 363.17 feet to a 5/8 inch rebar set with a 1 1/4 inch identification cap stamped Tobin-McFarland;

thence North 06°00'00" East, passing a 5/8 inch rebar set with a 1 1/4 inch identification cap stamped Tobin-McFarland at 135.00 feet, a distance of 165.00 feet to a point in Jake Tom Road (T. R. 352);

thence South 39°30'47" East a distance of 235.36 feet to a point on the east line of Fractional Lot #4 and at a corner of said 10.939 acre tract;

thence South 00°11'16" West, passing a 5/8 inch rebar found with a 1 1/4 inch identification cap stamped Seymour and Associates at 34.49 feet, a distance of 558.59 feet to the point of beginning, containing **5.929 Acres**, and subject to all legal easements, restrictions, and rights-of-way of record.

Bearings are based on the south line of Fractional Lot #4 being North 90°00'00" West by previous surveys. Rebars set are 5/8 inch by 36 inches and have a 1 1/4 inch yellow plastic identification cap stamped "Tobin-McFarland". For additional information see plat of survey made in conjunction with and considered an integral part of this description.

This description is based on a survey made in January of 2006 by Tobin-McFarland Surveying, Inc., and was prepared by Robert N. McFarland, Registered Professional Surveyor No. 7492.


b-103 5.929



Robert N. McFarland 1/31/06
Robert N. McFarland, P.S.
January 31, 2006 originals are signed in blue ink

Approved - Mathematically
Hocking County Engineer's Office

BY WIB DATE 02-03-2006



Approved Mathematically
 Hocking County Engineer's Office
 Date 6-1-00

CONDITIONAL APPROVAL/
 TRANSFER Not to be used as
 separate building site or
 transferred as an independent
 parcel in the future without
 Planning Commission and/or
 Health Department approval
*Both Tract Must Stay
 Together*

BEARINGS ARE BASED IN THE EAST LINE OF SECTION 17
 S 0° 05' 01" E.

IRON PINS SET ARE 5/8 INCH REBAR, 30 INCHES LONG,
 WITH PLASTIC IDENTIFICATION CAPS SET FLUSH WITH THE
 GROUND.




<p><i>The JW Company</i> 1218 St. Rt. 93 NE New Lexington, Ohio 43764 (614) 342-5131</p>	
<p>SURVEY FOR: <u>M. RENICK</u></p>	
<ul style="list-style-type: none"> ● IRON PIN SET ○ IRON PIN FOUND ⊕ POST ▲ RAILROAD SPIKE SET △ RR SPIKE FOUND ○ STONE FOUND *- FENCE ○ POINT 	<p>DATE: <u>9/28/92</u></p> <p>RANGE: <u>16W</u></p> <p>TOWNSHIP: <u>13N</u></p> <p>SECTION: <u>17</u></p> <p>POL. TWP: <u>GREEN</u></p> <p>COUNTY: <u>HOCKING</u></p> <p>SCALE: <u>1" = 100'</u></p> <p>STATE OF <u>OHIO</u></p>
<p>RONALD M. MERCKLE OHIO REG. SURVEYOR NO. 6473</p>	<p><i>Thomas C. Wilson</i> THOMAS C. WILSON OHIO REG. SURVEYOR NO. 6465</p>



GREEN 17
 2.99 Ac.
 2.63 Ac.

The T.C.W. Company



Engineering • Surveying
Resource Development

1218 State Route 93 NE • New Lexington, Ohio 43764 • 614-342-5131 • FAX: 614-342-4832

Approved - Mathematically
Hocking County Engineer's Office

T.C.W. DATE 6-1-00

DEED DESCRIPTION

M. Renick
~~Tract 8B~~


CONDITIONAL APPROVAL/
TRANSFER Not to be used as
separate building site or
transferred as an independent
parcel in the future without
Planning Commission and/or
Health Department approval
*with 2.99 Ac. Tract
To the West*

Being a part of the Northeast Quarter of Section 17 and Part Lot No. 6, Township 13 North, Range 16 West, Green Township, Hocking County, Ohio and being more particularly described as follows:

Beginning, for reference, at an iron pin found at the northeast corner of Section 17 and Part Lot No. 6; thence South $00^{\circ} 05' 01''$ East 560.384 feet along the east line of Section 17 to a point in the centerline of Township Road 16 and the principal place of beginning of the tract herein to be described; thence South $42^{\circ} 17' 19''$ West 330.913 feet to an iron pin found, passing an iron pin found at 25.000 feet; thence North $88^{\circ} 59' 31''$ West 290.825 feet to an iron pin set; passing an iron pin found at 180.943 feet; thence North $21^{\circ} 15' 11''$ East 378.224 feet to a point in the centerline of Township Road 16, passing an iron pin set at 353.224 feet; thence South $77^{\circ} 22' 47''$ East 204.455 feet along the centerline of Township Road 16 to a point; thence South $76^{\circ} 54' 57''$ East 81.669 feet along the centerline of Township Road 16 to a point; thence South $71^{\circ} 52' 23''$ East 41.465 feet along the centerline of Township Road 16 to a point; thence South $57^{\circ} 34' 30''$ East 68.554 feet along the centerline of Township Road 16 to the principal place of beginning. The tract as surveyed contains 2.63 acres, more or less, subject to all highways and easements of record.

Bearings in the above description are based on the east line of Section 17 bearing South $00^{\circ} 05' 01''$ East.

Iron pins set are 5/8 inch rebar, 30 inches long, with plastic identification caps set flush with the ground.




T.C. Wilson

T. Chris Wilson
Ohio Reg. Surveyor No. 6465

Date: September 25, 1992

The T&W Company



Engineering • Surveying
Resource Development

1218 State Route 93 NE • New Lexington, Ohio 43764 • 614-342-5131 • FAX: 614-342-4832

Approved - Mathematically
Hocking County Engineer's Office

DEED DESCRIPTION

T. C. Wilson DATE 6-1-00

M. Renick
~~Tract 8A~~


CONDITIONAL APPROVAL/
TRANSFER Not to be used as
separate building site or
transferred as an independent
parcel in the future without
Planning Commission and/or
Health Department approval
*with 2.63 Ac. Tract To
THE EAST*

Being a part of the Northeast Quarter of Section 17 and Part Lot No. 6, Township 13 North, Range 16 West, Green Township, Hocking County, Ohio and being more particularly described as follows:

Beginning, for reference, at an iron pin found at the northeast corner of Section 17 and Part Lot No. 6; thence South $61^{\circ} 10' 41''$ West 771.565 feet to a point in the centerline of Township Road 16 and the principal place of beginning of the tract herein to be described; thence South $73^{\circ} 45' 33''$ East 137.658 feet along the centerline of Township Road 16 to a point; thence South $77^{\circ} 50' 29''$ East 70.306 feet along the centerline of Township Road 16 to a point; thence South $77^{\circ} 22' 47''$ East 102.036 feet along the centerline of Township Road 16 to a point; thence South $21^{\circ} 15' 11''$ West 378.224 feet to an iron pin set, passing an iron pin set at 25.000 feet; thence North $88^{\circ} 59' 31''$ West 300.118 feet to an iron pin found; thence North $00^{\circ} 22' 24''$ West 130.000 feet to an iron pin found; thence North $25^{\circ} 09' 43''$ East 323.524 feet to the principal place of beginning, passing an iron pin found at 320.976 feet. The tract as surveyed contains 2.99 acres, more or less, subject to all highways and easements of record.

Bearings in the above description are based on the east line of Section 17 bearing South $00^{\circ} 05' 01''$ East.

Iron pins set are 5/8 inch rebar, 30 inches long with plastic identification caps set flush with the ground.



T. Chris Wilson
Ohio Reg. Surveyor No. 6465

Date: September 25, 1992

Seymour & Associates



830 West Hunter Street
Logan, Ohio 43138
740-385-4349
FAX: 740-385-6954

**SURVEYING
MAPPING**

email: seysurv@hocking.net



PLAT OF SURVEY

0.0106 Ac. / 0.0282 Ac.

SITUATED IN THE STATE OF OHIO,
COUNTY OF HOCKING
TOWNSHIP OF GREEN, AND
BEING PART OF THE NORTHEAST
QUARTER OF SECTION 17,
T-13-N, R-16-W




FOR: Shelby Brooks

JOB #:
G17081

DRAWN BY:
GFS

I HEREBY CERTIFY THAT THIS PLAT WAS PREPARED FROM AN ACTUAL FIELD SURVEY OF THE PREMISES IN OCTOBER OF 2008 AND FROM EXISTING PUBLIC RECORDS AND THAT SAID PLAT CORRECTLY SHOWS THE LIMITS OF THE PARCEL TO BE CONVEYED.

THIS CERTIFICATION WAS MADE BY ME ON THIS 9th DAY OF OCTOBER, 2008.



George F. Seymour

GEORGE F. SEYMOUR
OHIO PROFESSIONAL SURVEYOR NO. 6044

©2008 SEYMOUR & ASSOCIATES

EXHIBIT A
(Continued from page 1)

Tract 2: 0.0106 Acre

Being a part of the tract of land that is now or formerly in the name of Christopher Goss & Carol Bush as recorded in Official Record 12 at page 759, Hocking County Recorder's Office, said tract being part of the Northeast quarter of Section 17, T13N, R16W, Green Township, Hocking County, State of Ohio and being more particularly described as follows:

Beginning, for reference, at a point on the northwest corner of the Northeast quarter of Section 17 by the survey recorded in O.R. 236 at page 729;

Thence following said survey, North 90 degrees 00 minutes 00 seconds West a distance of 511.50 feet to a point;

Thence following said survey, South 30 degrees 50 minutes 16 seconds East a distance of 1247.98 feet to a 5/8" iron pin with a 1-1/4" plastic identification cap stamped "LPG-6344" found;

Thence along the west line of the tract as recorded in O.R. 236 at page 729, South 27 degrees 10 minutes 44 seconds East a distance of 128.65 feet to a 3/4" iron pin found on the southwest corner of the tract recorded in O.R. 236 at page 729, said corner being the principal point of beginning of the tract here in described;

Thence along the south line of the tract as recorded in O.R. 236 at page 729, North 62 degrees 31 minutes 51 seconds East a distance of 180.07 feet to a 3/4" iron pin found on the southeast corner of said tract;

Thence South 02 degrees 50 minutes 23 seconds West a distance of 2.32 feet to a 5/8" iron pin set;

Thence South 62 degrees 01 minutes 00 second West a distance of 128.07 feet to a 5/8" iron pin set;

Thence South 63 degrees 49 minutes 32 seconds West a distance of 50.85 feet to aa 5/8" iron pin set;


Thence North 27 degrees 10 minutes 44 seconds West a distance of 2.00 feet to the principal point of beginning, containing 0.0106 acre, more or less.


The bearings used in this survey of Tracts 1 & 2 were derived from monumentation found on the South line of the tract as recorded in O.R. 236 at page 729 as bearing, North 62 degrees 31 minutes 51 seconds East and are for the determination of angles only.

The iron pins set in this survey are 5/8" X 30" iron pins with a 1-1/4" plastic identification cap stamped "Seymour & Assoc".

Tracts 1 & 2 are to be held in continuous and contiguous ownership with the tract as recorded in O.R. 236 at page 729

This description was prepared from a survey by George F. Seymour, Ohio Professional Surveyor No. 6044, in October of 2008.


George F. Seymour, P.S. 6044



10-9-08
Date

APPROVED MATHEMATICALLY
Hocking County Engineer's Office
By: WJ Date: M.10 D.10 Y. 2008

EXHIBIT "A"

TRACT 1: 0.0282 Acre

Being a part of the tract of land that is now or formerly in the name of Christopher Goss & Carol Bush as recorded in Official Record 12 at page 759, Hocking County Recorder's Office, said tract being part of the Northeast quarter of Section 17, T13N, R16W, Green Township, Hocking County, State of Ohio and being more particularly described as follows:

Beginning, for reference, at a point on the northwest corner of the Northeast quarter of Section 17 by the survey recorded in O.R. 236 at page 729;

Thence following said survey, North 90 degrees 00 minutes 00 seconds West a distance of 511.50 feet to a point;

Thence following said survey, South 30 degrees 50 minutes 16 seconds East a distance of 1247.98 feet to a 5/8" iron pin with a 1-1/4" plastic identification cap stamped "LPG-6344" found;

Thence along the north line of the tract as recorded in O.R. 236 at page 729, North 60 degrees 11 minutes 11 seconds East, passing through a 3/4" iron pin found at 159.38 feet, going a total distance of 175.55 feet to a 5/8" iron pin set in the center of Township Road #350(Scout Road) on the northeast corner of the tract as recorded in O.R. 236 at page 729 and the principal point of beginning of the tract herein described;

Thence along the center of Scout Road the following three courses:

1. South 37 degrees 25 minutes 15 seconds East a distance of 26.79 feet to a point,
2. South 34 degrees 41 minutes 23 seconds East a distance of 33.40 feet to a point,
3. South 49 degrees 56 minutes 53 seconds East a distance of 43.12 feet to a 5/8" iron pin set;

Thence leaving said road, South 02 degrees 50 minutes 23 seconds West a distance of 42.23 feet to a 3/4" iron pin found on the southeast corner of the tract as recorded in O.R. 236 at page 729;


Thence along the east line of the tract as recorded in O.R. 236 at page 729, North 29 degrees 09 minutes 28 seconds West a distance of 135.89 feet to the principal point of beginning, containing 0.0282 acre, more or less, and subject to the right of way of Scout Road and all easements of record.

APPROVED MATHEMATICALLY
Hocking County Engineer's Office
By: WB Date: M.10.D.10.Y.2008

PLAT OF A 1.905 ACRE TRACT FOR DOROTHY THRUSH

Green Twp., Sec. 17
1.905 Ac.

Situated in Green Township, Hocking County, Ohio; being part of Fractional Lot 6 of Section 17, Township 13, Range 16.



CONDITIONAL APPROVAL/
TRANSFER Not to be used as
separate building site or
transferred as an independent
parcel in the future without
Planning Commission and/or
Health Department approval
remaining portions of
the 2.25 acre tract
and the 1.9757 acre
tract recorded in
Official Record Volume 300,
Page 948

Approved - Mathematically
Hocking County Engineer's Office

BY CW DATE 01-24-08


LEGEND

- Point
- 5/8"x30" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 found
- 5/8"x30" iron pin with 1-1/4" plastic ID cap stamped SVE-8127 set
- ▲ 3/4" iron pin found
- Railroad spike found
- ⊗ 2" iron pipe found



REFERENCES:

- Tax maps
- Deed descriptions
- Previous surveys
- Existing monumentation
- Existing public road



REFERENCE BEARING:

The North line of Section 17 as North 90 degrees 00 minutes 00 seconds East. Bearings are based upon an assumed meridian and are to denote angles only.

CERTIFICATION:

I hereby certify that an actual survey was made under my supervision of the premises shown hereon on the 16th day of January, 2008 and that the plat is a correct representation of the premises as described by said survey.

S. Vince Evans
Registered Surveyor No. 8127

Survey by: S. Vince Evans Surveying - S. Vince Evans P.S. 8127
64103 Woodgeard Road, Creola, Ohio 45622
Phone (740) 380-3884
FAX (740) 596-5831

SURVEY DESCRIPTION OF A 1.905 ACRE TRACT FOR DOROTHY THRUSH

Situated in Green Township, Hocking County, Ohio; being part of Fractional Lot 6 of Section 17, Township 13, Range 16; and being more particularly described as follows:

Being part of a 2.25 acre tract and part of a 4 acre tract as described in deed book Volume OR300, Page 948 to Dorothy Thrush.

Commencing at a 2" iron pipe found at the Northwest corner of the Northeast quarter of Section 17; Thence with the north line of Section 17, North 90 degrees 00 minutes 00 seconds East a distance of 744.29 feet to a Point in the north lane of County Road 16 (Maysville Greendale Road) and being the point of **Beginning** of the tract of land to be described;

Thence with the north line of Section 17 and the north lane of County Road 16 (Maysville Greendale Road), North 90 degrees 00 minutes 00 seconds East a distance of 326.23 feet to a Point;

Thence leaving the north line of Section 17 and the north lane of County Road 16 (Maysville Greendale Road), South 12 degrees 26 minutes 38 seconds East a distance of 62.43 feet to a 3/4" iron pin found, passing a Railroad spike found at a distance of 3.60 feet and a 5/8" iron pin set at a distance of 30.00 feet;

Thence South 00 degrees 27 minutes 18 seconds East a distance of 202.66 feet to a 5/8" iron pin set;

Thence South 89 degrees 32 minutes 42 seconds West a distance of 285.51 feet to a 5/8" iron pin set;


Thence North 12 degrees 54 minutes 45 seconds West a distance of 250.00 feet to a 5/8" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 found;

Thence North 00 degrees 11 minutes 02 seconds East a distance of 22.21 feet to the point of beginning and containing 1.905 acres, more or less, subject to the public easement of said County Road 16 (Maysville Greendale Road) and any other public or private easements of record.

The above 1.905 acre survey was based upon information obtained from tax maps, deed descriptions, previous surveys, existing monumentation, and an existing public road. The reference bearing for this survey is the North line of Section 17 as North 90 degrees 00 minutes 00 seconds East. Bearings are based upon an assumed meridian and are to denote angles only.

All iron pins set by this survey are 5/8" by 30" and are capped by a 1-1/4" plastic identification cap stamped "SVE-8127".

The above described property was surveyed by S. Vince Evans, Ohio Registered Surveyor No. 8127, on January 17, 2008.


S. Vince Evans, P. S. 8127

Survey by: S. Vince Evans Surveying
S. Vince Evans, P. S. 8127
64103 Woodgeard Road
Creola, Ohio 45622
Phone (740) 380-3884
FAX (740) 596-5831



Approved - Mathematically
Hocking County Engineer's Office


BY CW DATE 01-24-08

CONDITIONAL APPROVAL/
TRANSFER Not to be used as
separate building site or
transferred as an independent
parcel in the future without
Planning Commission and/or
Health Department approval
remaining portions of
the 2.25 acre tract
and the 1.9757 acre
tract recorded in Official
Record Volume 300, Page 948

PLAT OF A 1.840 ACRE TRACT, A 1.000 ACRE LEASE TRACT AND A 0.021 ACRE EASEMENT OF INGRESS AND EGRESS FOR BEVAN BARNETT

Green Twp.
Sec. 17
1.840 Ac.

Situated in Green Township, Hocking County, Ohio; being part of Fractional Lot 5 of Section 17, Township 13, Range 16.



LEGEND

- Point
- 5/8"x30" iron pin with 1-1/4" plastic ID cap stamped SVE-8127 previously set
- 5/8"x30" iron pin with 1-1/4" plastic ID cap stamped SVE-8127 set
- ▲ 3/4" iron pin found
- Railroad spike found
- ⊗ 2" iron pipe found

REFERENCES:

- Tax maps
- Deed descriptions
- Previous surveys
- Existing monumentation
- Existing public road

APPROVED MATHEMATICALLY
Hocking County Engineer's Office
By: CW Date: M. 1. D. 21. Y. 09.



REFERENCE BEARING:

The North line of Section 17 as North 90 degrees 00 minutes 00 seconds East. Bearings are based upon an assumed meridian and are to denote angles only.

CERTIFICATION:

I hereby certify that an actual survey was made under my supervision of the premises shown hereon on the 13th day of January, 2009 and that the plat is a correct representation of the premises as described by said survey.

S. Vince Evans
Registered Surveyor No. 8127

Survey by: S. Vince Evans Surveying - S. Vince Evans P.S. 8127
64103 Woodgeard Road, Creola, Ohio 45622
Phone (740) 380-3884
FAX (740) 596-5831

SURVEY DESCRIPTION OF A 1.840 ACRE TRACT FOR BEVAN BARNETT

Situated in Green Township, Hocking County, Ohio; being part of Fractional Lot 5 of Section 17, Township 13, Range 16; and being more particularly described as follows:

Being part of a 11.8273 acre tract as described in deed book Volume OR350, Page 154 to Bevan and Jacqueline Barnett.

Commencing at a 2" iron pipe found at the Northwest corner of the Northeast quarter of Section 17; Thence with the north line of Section 17, North 90 degrees 00 minutes 00 seconds East a distance of 1070.52 feet to a Point in the north lane of County Road 16 (Maysville Greendale Road); Thence leaving the north line of Section 17 and the north lane of County Road 16 (Maysville Greendale Road), South 12 degrees 26 minutes 38 seconds East a distance of 3.60 feet to a Railroad spike found in the centerline of said County Road 16 (Maysville Greendale Road) and being the point of **Beginning** of the tract of land to be described;

Thence with the centerline of said County Road 16 (Maysville Greendale Road), South 89 degrees 55 minutes 38 seconds East a distance of 167.23 feet to a Point;

Thence leaving the centerline of said County Road 16 (Maysville Greendale Road), South 00 degrees 27 minutes 18 seconds East a distance of 514.12 feet to a 5/8" iron pin set, passing a 5/8" iron pin set at a distance of 16.04 feet and 233.09 feet;

Thence South 89 degrees 32 minutes 42 seconds West a distance of 155.00 feet to a 5/8" iron pin set;


Thence North 00 degrees 27 minutes 18 seconds West a distance of 458.11 feet to a 3/4" iron pin found, passing a 5/8" iron pin previously set at a distance of 255.45 feet and passing a 5/8" iron pin set at a distance of 281.03 feet;

Thence North 12 degrees 26 minutes 38 seconds West a distance of 58.83 feet, passing a 5/8" iron pin previously set at a distance of 32.43 feet, to the point of beginning and containing 1.840 acres, more or less, subject to the public easement of said County Road 16 (Maysville Greendale Road) and any other public or private easements of record.

The above 1.840 acre survey was based upon information obtained from tax maps, deed descriptions, previous surveys, existing monumentation, and an existing public road. The reference bearing for this survey is the North line of Section 17 as North 90 degrees 00 minutes 00 seconds East. Bearings are based upon an assumed meridian and are to denote angles only.

All iron pins set or previously set by this survey are 5/8" by 30" and are capped by a 1-1/4" plastic identification cap stamped "SVE-8127".

The above described property was surveyed by S. Vince Evans, Ohio Registered Surveyor No. 8127, on January 13, 2009.



S. Vince Evans, P. S. 8127

Survey by: S. Vince Evans Surveying
S. Vince Evans, P. S. 8127
64103 Woodgeard Road
Creola, Ohio 45622
Phone (740) 380-3884
FAX (740) 596-5831



APPROVED MATHEMATICALLY
Hocking County Engineer's Office
By: CW Date: M. 1 D. 21 Y. 09

SURVEY DESCRIPTION OF A 1.000 ACRE LEASE TRACT FOR BEVAN BARNETT

Situated in Green Township, Hocking County, Ohio; being part of Fractional Lot 5 of Section 17, Township 13, Range 16; and being more particularly described as follows:

Being part of a 11.8273 acre tract as described in deed book Volume OR350, Page 154 to Bevan and Jacqueline Barnett.

Commencing at a 2" iron pipe found at the Northwest corner of the Northeast quarter of Section 17; Thence with the north line of Section 17, North 90 degrees 00 minutes 00 seconds East a distance of 1070.52 feet to a Point in the north lane of County Road 16 (Maysville Greendale Road); Thence leaving the north line of Section 17 and the north lane of County Road 16 (Maysville Greendale Road), South 12 degrees 26 minutes 38 seconds East a distance of 3.60 feet to a Railroad spike found in the centerline of said County Road 16 (Maysville Greendale Road); Thence South 12 degrees 26 minutes 38 seconds East a distance of 58.83 feet to a 3/4" iron pin found, passing a 5/8" iron pin previously set at a distance of 26.40 feet; Thence South 00 degrees 27 minutes 18 seconds East a distance of 177.08 feet to a 5/8" iron pin set, and being the point of **Beginning** of the tract of land to be described;

Thence North 89 degrees 32 minutes 42 seconds East a distance of 155.00 feet to a 5/8" iron pin set;

Thence South 00 degrees 27 minutes 18 seconds East a distance of 281.03 feet to a 5/8" iron pin set;

Thence South 89 degrees 32 minutes 42 seconds West a distance of 155.00 feet to a 5/8" iron pin set;

Thence North 00 degrees 27 minutes 18 seconds West a distance of 281.03 feet, passing a 5/8" iron pin previously set at a distance of 255.45 feet, to the point of beginning and containing 1.000 acres, more or less, subject to the public easement of said County Road 16 (Maysville Greendale Road) and any other public or private easements of record.

The above 1.000 acre survey was based upon information obtained from tax maps, deed descriptions, previous surveys, existing monumentation, and an existing public road. The reference bearing for this survey is the North line of Section 17 as North 90 degrees 00 minutes 00 seconds East. Bearings are based upon an assumed meridian and are to denote angles only.

All iron pins set or previously set by this survey are 5/8" by 30" and are capped by a 1-1/4" plastic identification cap stamped "SVE-8127".

The above described property was surveyed by S. Vince Evans, Ohio Registered Surveyor No. 8127, on January 13, 2009.

S. Vince Evans, P. S. 8127

Survey by: S. Vince Evans Surveying
S. Vince Evans, P. S. 8127
64103 Woodgeard Road
Creola, Ohio 45622
Phone (740) 380-3884
FAX (740) 596-5831



APPROVED MATHEMATICALLY
Hocking County Engineer's Office
By: CW Date: M. 1. D. 21. Y. 09.

**SURVEY DESCRIPTION OF A 0.021 ACRE EASEMENT
OF INGRESS AND EGRESS FOR BEVAN BARNETT**

Situated in Green Township, Hocking County, Ohio; being part of Fractional Lot 5 of Section 17, Township 13, Range 16; and being more particularly described as follows:

Being part of a 11.8273 acre tract as described in deed book Volume OR350, Page 154 to Bevan and Jacqueline Barnett.

Commencing at a 2" iron pipe found at the Northwest corner of the Northeast quarter of Section 17; Thence with the north line of Section 17, North 90 degrees 00 minutes 00 seconds East a distance of 1070.52 feet to a Point in the north lane of County Road 16 (Maysville Greendale Road); Thence leaving the north line of Section 17 and the north lane of County Road 16 (Maysville Greendale Road), South 12 degrees 26 minutes 38 seconds East a distance of 3.60 feet to a Railroad spike found in the centerline of said County Road 16 (Maysville Greendale Road); Thence with the centerline of said County Road 16 (Maysville Greendale Road), South 89 degrees 55 minutes 38 seconds East a distance of 167.23 feet to a Point and being the point of **Beginning** of the easement to be described;

Thence with the centerline of said County Road 16 (Maysville Greendale Road), South 89 degrees 55 minutes 38 seconds East a distance of 12.83 feet to a Point;

Thence with the centerline of said County Road 16 (Maysville Greendale Road), South 88 degrees 52 minutes 38 seconds East a distance of 7.17 feet to a Point;

Thence leaving the centerline of said County Road 16 (Maysville Greendale Road), South 00 degrees 27 minutes 18 seconds East a distance of 45.72 feet to a Point;


Thence South 89 degrees 32 minutes 42 seconds West a distance of 20.00 feet to a Point;

Thence North 00 degrees 27 minutes 18 seconds West a distance of 46.04 feet, passing a 5/8" iron pin set at a distance of 30.00 feet, to the point of beginning and containing 0.021 acres, more or less, subject to the public easement of said County Road 16 (Maysville Greendale Road) and any other public or private easements of record.

The above 0.021 acre easement survey was based upon information obtained from tax maps, deed descriptions, previous surveys, existing monumentation, and an existing public road. The reference bearing for this survey is the North line of Section 17 as North 90 degrees 00 minutes 00 seconds East. Bearings are based upon an assumed meridian and are to denote angles only.

All iron pins set or previously set by this survey are 5/8" by 30" and are capped by a 1-1/4" plastic identification cap stamped "SVE-8127".

The above described property was surveyed by S. Vince Evans, Ohio Registered Surveyor No. 8127, on January 13, 2009.




S. Vince Evans, P. S. 8127


Survey by: S. Vince Evans Surveying
S. Vince Evans, P. S. 8127
64103 Woodgeard Road
Creola, Ohio 45622
Phone (740) 380-3884
FAX (740) 596-5831



APPROVED MATHEMATICALLY
Hocking County Engineer's Office
By: CW Date: M. 1. D. 21. Y. 09



NOTE: BEARINGS WERE DERIVED FROM A PREVIOUS SURVEY RECORDED IN O.R. V. 40 AT PG 501. BASED ON MONUMENTATION FOUND ON THE EAST LINE OF SECTION 17 AS BEARING S 0° 02' 52" E AND ARE FOR THE DETERMINATION OF ANGLES ONLY.



- LEGEND**
- △ - 5/8" IRON PIN W/I.D. CAP SET
 - ▲ - EXISTING IRON PIN
 - - POINT
 - ▣ - EXISTING IRON PIN IN CONCRETE

REFERENCES

CURRENT TAX PLATS
 U.S.G.S. TOPO MAPS
 AERIAL PHOTOGRAPHS
 PREVIOUS SURVEYS
 DEEDS: AS NOTED ON PLAT

Approved - Mathematically
 Hocking County Engineer's Office
 BY *JAW* DATE 5-20-98

PLAT PREPARED FROM AN ACTUAL SURVEY MADE ON THE 13TH DAY OF MAY, 1998 BY,

George F. Seymour
 OHIO PROFESSIONAL SURVEYOR

No 6044



© SEYMOUR AND ASSOCIATES

SURVEYED AND PLATED AT THE REQUEST OF: JASON ALLISON
 BEING A PART OF SECTIONS 11 AND 17, TOWNSHIP-13-NORTH, RANGE-16-WEST
 GREEN TOWNSHIP, HOCKING COUNTY, STATE OF OHIO.

seymour and associates consultants
 830 west hunter street
 logan, ohio 43138
 (614) 588-4849

NO	DATE
617981	5-13-98

EXHIBIT "A"

Being a part of the tract of land that is now or formerly in the name of Ruth Renick as recorded in Deed Book 200 at page 516, Deed Book 200 at page 518 and Official Record 97 at page 730, Hocking County Recorder's Office, said tract being part of the Section 11 and part of Section 17, T13N, R16W, Green Township, Hocking County, State of Ohio, and being more particularly described as follows:

Beginning at a point within the right-of-way of Township Road 16, the west line of Section 11 and the east line of Section 17 from which an iron pin found in concrete on the northeast corner of Section 17 bears North 00 degrees 02 minutes 52 seconds West a distance of 560.34 feet;

Thence leaving the east line of Section 17 and the west line of Section 11 and within the right-of-way of said road and a grantor's line the following four courses:

1. South 57 degrees 34 minutes 30 seconds East a distance of 6.88 feet to a point;
2. South 43 degrees 36 minutes 04 seconds East a distance of 390.85 feet to a point;
3. South 43 degrees 37 minutes 02 seconds East a distance of 284.45 feet to an iron pin found in concrete, and;
4. South 09 degrees 52 minutes 10 seconds West a distance of 294.00 feet to a point;

Thence leaving said road and with a new line through the grantor's land the following five courses:

1. North 50 degrees 46 minutes 00 seconds West, passing through a 5/8" X 30" iron pin with a plastic identification cap set at 25.00 feet, going a total distance of 543.60 feet to a 5/8" X 30" iron pin with a plastic identification cap set;
2. South 65 degrees 17 minutes 42 seconds West a distance of 442.20 feet to a 5/8" X 30" iron pin with a plastic identification cap set;
3. North 00 degrees 22 minutes 36 seconds West a distance of 382.08 feet to an iron pin found;
4. South 88 degrees 56 minutes 43 seconds East a distance of 181.00 feet to an iron pin found, and;
5. North 42 degrees 17 minutes 25 seconds East, passing through an iron pin found at 305.88 feet, going a total distance of 330.72 feet to a point within the right-of-way of Township Road 16;

Thence continuing with a new line within said right-of-way, South 57 degrees 34 minutes 30 seconds East a distance of 0.58 feet to the point of beginning, containing 3.288 acres in Section 17 and 3.982 acres in Section 11, for a total of 7.270 acres, more or less, and subject to the right-of-way of Township Road 16 and all easements of record.

All 5/8" X 30" iron pins with plastic identification caps set are stamped "Seymour & Associates".

The bearings used in the above described tract were based on a previous survey as recorded in Official Record 40 at page 501 and the east line of Section 17 as bearing South 00 degrees 02 minutes 52 seconds East and are for the determination of angles only.

The above described tract was surveyed by George F. Seymour, Ohio Professional Surveyor No. 6044, May 13, 1998.

Approved - Mathematically
Hocking County Engineer's Office

BY JA AW DATE 5-20-98




EXHIBIT "A"

Being a part of the tract of land that is now or formerly in the name of Ruth Renick as recorded in Deed Book 200 at page 518 and Official Record 97 at page 730, Hocking County Recorder's Office, said tract being part of the Section 11 and part of Section 17, T13N, R16W, Green Township, Hocking County, State of Ohio, and being more particularly described as follows:

Beginning, for reference, at an iron pin found in concrete on the northeast corner of Section 17;

Thence along the east line of Section 17, South 00 degrees 02 minutes 52 seconds East a distance of 560.34 feet to a point within the right-of-way of Township Road 16;

Thence leaving the east line of Section 17 and within the right-of-way of said road the following four courses:

1. South 57 degrees 34 minutes 30 seconds East a distance of 6.88 feet to a point;
2. South 43 degrees 36 minutes 04 seconds East a distance of 390.85 feet to a point;
3. South 43 degrees 37 minutes 02 seconds East a distance of 284.45 feet to an iron pin found in concrete, and;
4. South 09 degrees 52 minutes 10 seconds West a distance of 294.00 feet to a point on the grantor's easterly line and the principal place of beginning for the tract herein described;

Thence continuing along the right-of-way of said road and the grantor's line the following nine courses:

1. South 09 degrees 52 minutes 10 seconds West a distance of 104.35 feet to a point;
2. South 04 degrees 34 minutes 54 seconds East a distance of 63.51 feet to a point;
3. South 24 degrees 33 minutes 41 seconds East a distance of 51.17 feet to a point;
4. South 34 degrees 15 minutes 29 seconds East a distance of 177.81 feet to a point;
5. South 37 degrees 18 minutes 47 seconds East a distance of 125.07 feet to a point;
6. South 46 degrees 09 minutes 37 seconds East a distance of 84.96 feet to a point;
7. South 53 degrees 57 minutes 37 seconds East a distance of 56.82 feet to a point;
8. South 59 degrees 37 minutes 55 seconds East a distance of 136.47 feet to a point, and;
9. South 63 degrees 15 minutes 32 seconds East a distance of 196.06 feet to a point being a grantor's corner;

Thence leaving said road and along a grantor's line the following two courses:

1. South 56 degrees 28 minutes 57 seconds West, passing through an iron pin found at 24.77 feet, going a total distance of 284.67 feet to an iron pin found, and;
2. South 89 degrees 47 minutes 57 seconds West a distance of 767.10 feet to an iron pin found;


Thence with a new line through the grantor's land the following two courses:

1. North 00 degrees 01 minutes 47 seconds West a distance of 502.32 feet to an iron pin found, and;
2. North 66 degrees 00 minutes 35 seconds West a distance of 283.68 feet to a 5/8" X 30" iron pin with a plastic identification cap set on a grantor's corner;

Thence along a grantor's line, North 50 degrees 09 minutes 01 second West a distance of 376.78 feet to an iron pin found;

Thence with a new line through the grantor's land the following four courses:

1. North 64 degrees 53 minutes 01 second East a distance of 161.97 feet to an iron pin found;
2. North 00 degrees 22 minutes 36 seconds West a distance of 99.91 feet to a 5/8" X 30" iron pin with a plastic identification cap set;



[continued on page 2]

EXHIBIT "A"

3. North 65 degrees 17 minutes 42 seconds East a distance of 442.20 feet to a 5/8" X 30" iron pin with a plastic identification cap set, and;
4. South 50 degrees 46 minutes 00 seconds East, passing through a 5/8" X 30" iron pin with a plastic identification cap set at 518.60 feet, going a total distance of 543.60 feet to the principal point of beginning, containing 5.103 acres in Section 17 and 14.261 acres in Section 11, for a total of 19.364 acres, more or less, and subject to the right-of-way of Township Road 16 and all easements of record.


All 5/8" X 30" iron pins with plastic identification caps set are stamped "Seymour & Associates".

The bearings used in the above described tract were based on a previous survey as recorded in Official Record 40 at page 501 and the east line of Section 17 as bearing South 00 degrees 02 minutes 52 seconds East and are for the determination of angles only.

The above described tract was surveyed by George F. Seymour, Ohio Professional Surveyor No. 6044, May 13, 1998.

Approved - Mathematically
Hocking County Engineer's Office

BY GAW DATE 5-20-98



THIS PAGE
LEFT BLANK
INTENTIONALLY

PLAT NUMBER: 100

I HEREBY CERTIFY THAT AN ACTUAL SURVEY WAS MADE UNDER MY DIRECT SUPERVISION OF THE PREMISES SHOWN HEREON ON THE 13 DAY OF NOV. 1993 AND THAT THE PLAT IS A CORRECT REPRESENTATION OF THE PREMISES AS DETERMINED BY SAID SURVEY. I FURTHER CERTIFY THAT THERE ARE NO ENCUMBRANCES OF ANY KIND WHICH CROSS ANY BOUNDARY EXCEPT AS SHOWN HEREON.



George F. Seymour
PROFESSIONAL SURVEYOR NO. 5034

LEGEND

△ - 5/8" IRON PIN SET W/ I.D. CAP STAMPED "SEYMOUR & ASSOC."

○ - POINT

NOTE:
BEARINGS DERIVED FROM PREVIOUS SURVEYS AND ARE FOR ORIENTATION OF ANGLES ONLY AND ARE BASED ON THE WEST LINE OF FR. LOT 1 AS BEARING N04°36'29"E



REFERENCES:
DEEDS AS NOTED
COUNTY TAX MAPS
PREVIOUS SURVEYS
EXISTING MONUMENTS

DONALD W. & DOROTHY D. TAYLOR
(128/166) (ALLEGED TO CONTAIN 7 AC. BY EXCEPTIONS)
AREA = 8.0813 ACRES
(BY SURVEY)


ABANDONED TOWNSHIP ROAD
(AS CITED IN DB 128/166)
215.59'
N76°16'30"W
579°34'15"W ~ 44.82'
534°30'02"W ~ 33.19'
520°11'12"W ~ 185.64'

AREA = 7.7647 ACRES
(BY SURVEY)

ROBERT BEOUGHNER (85/177)
(1ST TRACT ALLEGED TO CONTAIN 3 ACRES)

ROBERT BEOUGHNER (85/177)
(11.5 AC. TRACT - DEED)
(2ND TRACT)

Approved - Mathematically
Hocking County Engineer's Office
E. J. W. Date: 11-19-93



PLAT OF SURVEY

BEING PART OF FR. LOT NO. 1 SITUATE IN SECTION 17 - TOWN 13 NORTH - RANGE 16 WEST - GREEN TOWNSHIP - HOCKING COUNTY - STATE OF OHIO.

LOG No: G17931 DATE: 11/18/93 DRAWN: GFB SURVEYED D.W. & D.D. TAYLOR & FOR: ROBERT BEOUGHNER

seymour & assoc. consultants

(614) - 385 - 4349

69 s. market

logan, ohio 43138



EXHIBIT "A"

Being all of the tract of land that is now or formerly in the name of Donald W. and Dorothy D. Taylor and intended to be conveyed as recorded in Deed Book 128 at page 766, Hocking County Recorder's Office, said tract being part of Fractional Lot 1 situated in Section 17, T13N, R16W, Green Township, Hocking County, State of Ohio and being more particularly described as follows:

Beginning at a 5/8" iron pin with a plastic identification cap set on the grantor's northwest corner and on the west line of Fractional Lot 1 from which the northwest corner of said fractional lot bears North 04 degrees 36 minutes 29 seconds East a distance of 86.00 feet;

Thence leaving the west line of Fractional Lot 1 and along the grantor's north line, South 85 degrees 22 minutes 47 seconds East a distance of 198.46 feet to a 5/8" iron pin with a plastic identification cap set on a northeasterly corner to the grantor;

Thence along an old fence line of occupation being the easterly line to the grantor, South 31 degrees 32 minutes 26 seconds East, passing through 5/8" iron pins with plastic identification caps set at 702.36 feet and 831.19 feet, going a total distance of 844.34 feet to a 5/8" iron pin with a plastic identification cap set in the center of an abandoned Township Road as cited in Deed Book 128 at page 766 and on the most easterly corner to the grantor;

Thence along the center of said abandoned road and the grantor's southeasterly line the following six courses:

- [1] North 76 degrees 16 minutes 36 seconds West a distance of 215.59 feet to a point;
- [2] North 85 degrees 26 minutes 06 seconds West a distance of 93.45 feet to a point;
- [3] South 79 degrees 34 minutes 15 seconds West a distance of 44.82 feet to a point;
- [4] South 34 degrees 39 minutes 02 seconds West a distance of 38.19 feet to a point;
- [5] South 20 degrees 11 minutes 12 seconds West a distance of 185.64 feet to a point, and;
- [6] South 26 degrees 08 minutes 50 seconds West a distance of 43.21 feet to a 5/8" iron pin with a plastic identification cap set in the center of Township Road No. 352 and on a southeasterly corner to the grantor;

Thence leaving the center of said abandoned road and along the center of Township Road No. 352 and the grantor's south line the following three courses:

- [1] North 64 degrees 55 minutes 12 seconds West a distance of 208.55 feet to a point;
- [2] North 54 degrees 20 minutes 17 seconds West a distance of 50.98 feet to a point, and;
- [3] North 43 degrees 04 minutes 13 seconds West a distance of 31.15 feet to a point being the grantor's southwest corner and on the West line of Fractional Lot 1;

[continued on page 2]

EXHIBIT "A"

Thence leaving the center of said road and along the grantor's west line and the west line of Fractional Lot 1, North 04 degrees 36 minutes 29 seconds East, passing through a 5/8" iron pin with a plastic identification cap set at 30.00 feet, going a total distance of 791.24 feet to the place of beginning, containing 8.0813 acres, more or less, and subject to the right of way of Township Road No. 352 and all easements of record.

All 5/8" iron pins with plastic identification caps set are stamped "Seymour & Associates".

The bearings used in the above described tract were based on the west line of Fractional Lot 1 as bearing North 04 degrees 36 minutes 29 seconds East and are for the determination of angles only.

The above described tract was surveyed by George F. Seymour, Ohio Professional Surveyor No. 6044, November 18, 1993.

Approved - Mathematically
Hocking County Engineer's office
By *M.A.W.* Date *11-19-93*

EXHIBIT "A"

Being part of the tract of land that is now or formerly in the name of Robert Beougher and being all of the tract intended to be conveyed and referred to as the FIRST TRACT as recorded in Deed Book 85 at page 177, Hocking County Recorder's Office, said tract being part of Fractional Lot 1 situated in Section 17, T13N, R16W, Green Township, Hocking County, State of Ohio and being more particularly described as follows:

Beginning at a 5/8" iron pin with a plastic identification cap set on the southwest corner of Fractional Lot 1 and a corner to the grantor;

Thence along the west line of Fractional Lot 1, a westerly line to the grantor and also known as the east line of the old Poling Farm, North 04 degrees 36 minutes 29 seconds East, passing through a 5/8" iron pin with a plastic identification cap set at 524.15 feet, going a total distance of 554.15 feet to a point in the center of Township Road No. 352 and on the grantor's northwest corner;

Thence leaving the west line of Fractional Lot 1 and along the grantor's northeasterly line and the center of said road the following ten courses:

- [1] South 43 degrees 04 minutes 13 seconds East a distance of 31.15 feet to a point;
- [2] South 54 degrees 20 minutes 17 seconds East a distance of 50.98 feet to a point;
- [3] South 64 degrees 55 minutes 12 seconds East a distance of 208.55 feet to a 5/8" iron pin with a plastic identification cap set;
- [4] South 66 degrees 12 minutes 13 seconds East a distance of 452.90 feet to a point;
- [5] South 65 degrees 55 minutes 19 seconds East a distance of 104.88 feet to a point;
- [6] South 60 degrees 42 minutes 51 seconds East a distance of 73.93 feet to a point;
- [7] South 46 degrees 51 minutes 50 seconds East a distance of 54.15 feet to a point;
- [8] South 35 degrees 41 minutes 28 seconds East a distance of 94.80 feet to a point;
- [9] South 27 degrees 17 minutes 28 seconds East a distance of 108.86 feet to a point, and;
- [10] South 11 degrees 15 minutes 15 seconds East a distance of 8.28 feet to a point being the grantor's southeast corner and on the south line of Fractional Lot 1 and the south line of Section 17;

[continued on page 2]

EXHIBIT "A"

Thence leaving the center of said road and along the grantor's south line, the south line of Fractional Lot 1 and the south line of Section 17, North 86 degrees 06 minutes 47 seconds West, passing through a 5/8" iron pin with a plastic identification cap set at 30.00 feet, going a total distance of 1019.44 feet to the place of beginning, containing 7.7647 acres, more or less and subject to the right of way of Township Road No. 352 and all easements of record.

All 5/8" iron pins with plastic identification caps set are stamped "Seymour & Associates".


The bearings used in the above described tract were based on the west line of Fractional Lot 1 as bearing North 04 degrees 36 minutes 29 seconds East and are for the determination of angles only.

The above described tract was surveyed by George F. Seymour, Ohio Professional Surveyor No. 6044, November 18, 1993.

Approved - Mathematically
Hocking County Engineer's office
Date. 11-19-93
PJ

BEING A PART OF THE NW/4 AND FRAC. LOT NO. 6 OF SEC. 17, TOWNSHIP T-13N, R-16W, HOCKING CO., OHIO

NOTE: CITED BEARINGS ARE BASED ON THE BEARING SYSTEM OF THE 7.4369 AC. TRACT DESCRIBED IN O.R. VOL. 39, PG. 749.



C.E.C. GOSS O.R. 12, PG. 759


R. B. BENTON O.R. 97, PG. 230

10.0341 Ac.
(PT. OF O.R. VOL. 12, PG. 759)

REFERENCES:
COUNTY TAX PLATS
SURVEYS OF RECORD
RECORDED PLAT OF
"MAYLOR'S CROSS" SUBD.
1880 PLAT RECORDS
DEEDS (AS NOTED)

M. BOWMAN
O.R. 246, PG. 807
O.R. 94, PG. 719

Approved - Mathematically
Hocking County Engineer's Office
BY WJB DATE 06-21-05



- = 7/8" x 30" IRON PEGS (W/1/4" HD CAP STAMPED "MFB 5-6003")
- ⊕ = 1/2" x 30" IRON PEG (STEU. SET) W/1" HD CAP STAMPED "MFB 5-6003"
- = 7/8" IRON PEG (PS) W/1/4" HD CAP STAMPED "5-6004"

PLAT DERIVED FROM SURVEY MADE
JULY 14, 2005, BY:
[Signature] (6-21-05)
OHIO REGISTERED SURVEYOR NO. 2803



DESCRIPTION OF SURVEY FOR MR. & MRS. CHRISTOPHER GOSS

Being a part of the tract of land described in Vol. 12 Pg. 759, Hocking Co. Official Records, situated in the NW ¼ and in part of Frac. Lot No. 6 of Sec. 17, Green Twp., T-13N, R-16W, Hocking Co., Ohio, and being more particularly described as follows:

Beginning at an iron pin previously set on the SW corner of the 7.4369 Ac. tract described in O.R. Vol. 39, Pg. 749;

Thence, with the south line of said tract, S 88 degrees 08' 30" E, passing an iron pin previously set at 1263.60 ft., going a total distance of 1283.56 ft. to a point in the center of Twp. Rd. 350;

Thence with the centerline of said Twp. road the following four (4) courses:

- 1) S 2 degrees 10' 02" W a distance of 16.94 ft. to a point;
- 2) S 11 degrees 27' 32" E a distance of 69.74 ft. to a point;
- 3) S 21 degrees 48' 50" E a distance of 125.46 ft. to a point;
- 4) S 28 degrees 01' 50" E a distance of 118.76 ft. to a point;

Thence, leaving Twp. Rd. No. 350 and with the south line of Frac. Lot No. 6 and an extension thereof, S 89 degrees 47' 59" W, passing an iron pin found at 30.00 ft., going a total distance of 1397.30 ft. to an iron pin set;

Thence, with a new line, N 0 degrees 12' 01" W a distance of 353.09 ft. to the place of beginning, containing 10.0341 acres, more or less, and being subject to the right-of-way of Twp. Rd. No. 350 and all valid easements.

Cited bearings are based on the bearing system of the 7.4369 Ac. tract described in O.R. Vol. 39, Pg. 749;

All iron pins described as being set are 5/8" X 30" with an attached 1 ¼" I.D. cap stamped "M.P.B. S-6803".

All iron pins described as being previously set are ½" X 30" with a 1" I.D. cap stamped "M.P.B. S-6803".

All iron pins described as being found are 5/8" with a 1 ¼ I.D. cap stamped "S-6044".

The above description is the result of an actual survey made by Michael P. Berry, Ohio Registered Surveyor No. 6803, on June 14, 2005

Approved - Mathematically
Hocking County Engineer's Office

BY WJB DATE 06-21-05


Michael P. Berry #6803





TOBIN-McFARLAND SURVEYING, INC.

Professional Land Surveyors

111 West Wheeling Street
Lancaster, Ohio 43130
Phone (740) 687-1710
Fax. (740) 687-0877

Description of 5.515 Acres

Situated in the State of Ohio, County of Hocking, Township of Green, Township 13, Range 16, Fractional Lot #4, section 17.

Being part of the 42.5 acre tract described in a deed to Clark R. Truax, recorded in official record 221, page 364, and being more fully described as follows:

Beginning at a 5/8 inch rebar set with a 1 1/4 inch identification cap stamped Tobin-McFarland on the west line of Fractional Lot #4, said point is located South 00°06'32" West a distance of 129.41 feet from a 5/8 inch rebar set with a 1 1/4 inch identification cap stamped Tobin-McFarland at the northwest corner of said fractional lot;

thence North 88°36'59" East, passing a 5/8 inch rebar set with a 1 1/4 inch identification cap stamped Tobin-McFarland at 1171.01 feet, a distance of 1201.01 feet to a point in Scout Road (T. R. 350);

thence South 12°26'48" East a distance of 215.55 feet to a 5/8 inch rebar set with a 1 1/4 inch identification cap stamped Tobin-McFarland in said road;

thence North 90°00'00" West, passing a 5/8 inch rebar set with a 1 1/4 inch identification cap stamped Tobin-McFarland at 30.00 feet, a distance of 1247.46 feet to a 5/8 inch rebar set with a 1 1/4 inch identification cap stamped Tobin-McFarland on the west line of Fractional Lot #4;

thence North 00°06'32" East a distance of 181.49 feet to the point of beginning, containing **5.515 Acres**, and subject to all legal easements, restrictions, and rights-of-way of record.

Bearings are based on the south line of Fractional Lot #4 being North 90°00'00" West by previous surveys. Rebars set are 5/8 inch by 36 inches and have a 1 1/4 inch yellow plastic identification cap stamped "Tobin-McFarland". For additional information see plat of survey made in conjunction with and considered an integral part of this description.

This description is based on a survey made in October of 2005 by Tobin-McFarland Surveying, Inc., and was prepared by Robert N. McFarland, Registered Professional Surveyor No. 7492.



Robert N. McFarland 10 25 05
Robert N. McFarland, P.S.
October 25, 2005 originals are signed in blue ink

b-97

Approved - Mathematically
Hocking County Engineer's Office

BY W13, CW DATE 11-04-2005

TOBIN-McFARLAND SURVEYING, INC.



Professional Land Surveyors

111 West Wheeling Street
Lancaster, Ohio 43130
Phone (740) 687-1710
Fax (740) 687-0877

Description of 11.015 Acres

Situated in the State of Ohio, County of Hocking, Township of Green, Township 13, Range 16, Fractional Lot #4, section 17.

Being part of the 42.5 acre tract described in a deed to Clark R. Truax, recorded in official record 221, page 364, and being more fully described as follows:

Beginning at a 5/8 inch rebar set with a 1 1/4 inch identification cap stamped Tobin-McFarland on the west line of Fractional Lot #4, said point is located North 00°06'32" East a distance of 511.62 feet from a 5/8 inch rebar found with a 1 1/4 inch identification cap stamped LPG-6344 at the southwest corner of said fractional lot;

thence North 00°06'32" East a distance of 421.04 feet to a 5/8 inch rebar set with a 1 1/4 inch identification cap stamped Tobin-McFarland on the west line of Fractional Lot #4;

thence South 90°00'00" East, passing a 5/8 inch rebar set with a 1 1/4 inch identification cap stamped Tobin-McFarland at 1217.46 feet, a distance of 1247.46 feet to a 5/8 inch rebar set in Scout Road (T. R. 350);

thence South 27°13'00" West a distance of 473.46 feet to a point in said road;

thence North 90°00'00" West, passing a 5/8 rebar set with a 1 1/4 inch identification cap stamped Tobin-McFarland at 30.00 feet, a distance of 1031.72 feet to the point of beginning, containing **11.015 Acres**, and subject to all legal easements, restrictions, and rights-of-way of record.

Bearings are based on the south line of Fractional Lot #4 being North 90°00'00" West by previous surveys. Rebars set are 5/8 inch by 36 inches and have a 1 1/4 inch yellow plastic identification cap stamped "Tobin-McFarland". For additional information see plat of survey made in conjunction with and considered an integral part of this description.

This description is based on a survey made in October of 2005 by Tobin-McFarland Surveying, Inc., and was prepared by Robert N. McFarland, Registered Professional Surveyor No. 7492.




Robert N. McFarland 10 | 25 | 05
Robert N. McFarland, P.S.
October 25, 2005 originals are signed in blue ink

b-97

Approved - Mathematically
Hocking County Engineer's Office

BY WJB, CW DATE 11-04-2005



TOBIN-McFARLAND SURVEYING, INC.

Professional Land Surveyors

111 West Wheeling Street
Lancaster, Ohio 43130
Phone (740) 687-1710
Fax (740) 687-0877

Description of 10.020 Acres

Situated in the State of Ohio, County of Hocking, Township of Green, Township 13, Range 16, Fractional Lot #4, section 17.

Being part of the 42.5 acre tract described in a deed to Clark R. Truax, recorded in official record 221, page 364, and being more fully described as follows:

Beginning at a 5/8 inch rebar found with a 1 1/4 inch identification cap stamped LPG-6344 at the southwest corner of Fractional Lot #4;

thence North 00°06'32" East a distance of 511.62 feet to a 5/8 inch rebar set with a 1 1/4 plastic identification cap stamped Tobin-McFarland on the west line of Fractional Lot #4;

thence South 90°00'00" East, passing a 5/8 inch rebar set with a 1 1/4 identification cap stamped Tobin-McFarland at 1001.72 feet, a distance of 1031.72 feet to a point in Scout Road (T. R. 350);

thence South 27°13'00" West a distance of 298.91 feet to a 5/8 inch rebar set with a 1 1/4 identification cap stamped Tobin-McFarland on the east side of the existing pavement of said road;

thence South 54°25'31" West a distance of 290.78 feet to a 5/8 inch rebar set with a 1 1/4 identification cap stamped Tobin-McFarland on the west side of the existing pavement of said road;

thence South 30°21'30" West a distance of 88.82 feet to a point in said road and on the south line of Fractional Lot #4;

thence North 90°00'00" West, passing 5/8 rebars found with a 1 1/4 inch plastic identification caps stamped LPG-6344 at 30.00 feet and 398.32 feet, a distance of 614.59 feet to the point of beginning, containing *10.020 Acres*, and subject to all legal easements, restrictions, and rights-of-way of record.

Bearings are based on the south line of Fractional Lot #4 being North 90°00'00" West by previous surveys. Rebars set are 5/8 inch by 36 inches and have a 1 1/4 inch yellow plastic identification cap stamped "Tobin-McFarland". For additional information see plat of survey made in conjunction with and considered an integral part of this description.

This description is based on a survey made in October of 2005 by Tobin-McFarland Surveying, Inc., and was prepared by Robert N. McFarland, Registered Professional Surveyor No. 7492.

b-97



Robert N. McFarland 10/25/05
Robert N. McFarland, P.S.
October 25, 2005 originals are signed in blue ink

Approved - Mathematically
Hocking County Engineer's Office
BY *W.B. CW* DATE *11-04-2005*



TOBIN-McFARLAND SURVEYING, INC.

Professional Land Surveyors

111 West Wheeling Street
Lancaster, Ohio 43130
Phone (740) 687-1710
Fax. (740) 687-0877

Description of 5.010 Acres

Situated in the State of Ohio, County of Hocking, Township of Green, Township 13, Range 16, Fractional Lot #4, section 17.

Being part of the 42.5 acre tract described in a deed to Clark R. Truax, recorded in official record 221, page 364, and being more fully described as follows:

Beginning at a 5/8 inch rebar set with a 1 1/4 inch identification cap stamped Tobin-McFarland at the northwest corner of Fractional Lot #4;

thence North 83°33'57" East, passing a 5/8 inch rebar found with a 1 1/4 inch identification cap stamped Seymour and Associates at 1174.77 feet, a distance of 1199.77 feet to a point in Scout Road (T. R. 350);

thence South 02°00'00" East a distance of 235.00 feet to a point in said road;

thence South 88°36'59" West, passing a 5/8 inch rebar set with a 1 1/4 inch identification cap stamped Tobin-McFarland at 30.00 feet, a distance of 1201.01 feet to a 5/8 inch rebar set with a 1 1/4 inch identification cap stamped Tobin-McFarland on the west line of Fractional Lot #4;

thence North 00°06'32" East a distance of 129.41 feet to the point of beginning, containing **5.010 Acres**, and subject to all legal easements, restrictions, and rights-of-way of record.

Bearings are based on the south line of Fractional Lot #4 being North 90°00'00" West by previous surveys. Rebars set are 5/8 inch by 36 inches and have a 1 1/4 inch yellow plastic identification cap stamped "Tobin-McFarland". For additional information see plat of survey made in conjunction with and considered an integral part of this description.

This description is based on a survey made in October of 2005 by Tobin-McFarland Surveying, Inc., and was prepared by Robert N. McFarland, Registered Professional Surveyor No. 7492.

b-100



Robert N. McFarland 10/25/05
Robert N. McFarland, P.S.
October 25, 2005 originals are signed in blue ink

Approved - Mathematically
Hocking County Engineer's Office

BY WB, CW DATE 11-04-2005



TOBIN-McFARLAND SURVEYING, INC.

Professional Land Surveyors

111 West Wheeling Street
Lancaster, Ohio 43130
Phone (740) 687-1710
Fax (740) 687-0877

Description of 10.939 Acres

Situated in the State of Ohio, County of Hocking, Township of Green, Township 13, Range 16, Fractional Lot #4, section 17.

Being part of the 42.5 acre tract described in a deed to Clark R. Truax, recorded in official record 221, page 364, and being more fully described as follows:

Beginning at a 5/8 inch rebar found with a 1 1/4 inch identification cap stamped LPG-6344 at the southeast corner of Fractional Lot #4;

thence South 89°30'33" West a distance of 207.92 feet to a stone found on the south line of Fractional Lot #4;

thence North 90°00'00" West, passing a 5/8 inch rebar found with a 1 1/4 inch identification cap stamped LPG-6344 at 698.41 feet, a distance of 731.94 feet to a point in Scout Road (T. R. 350);

thence North 30°21'30" East a distance of 88.82 feet to a 5/8 inch rebar set with a 1 1/4 inch identification cap stamped Tobin-McFarland on the west side of the existing pavement of said road;

thence North 54°25'31" East a distance of 290.78 feet a 5/8 inch rebar set with a 1 1/4 inch identification cap stamped Tobin-McFarland on the east side of the existing pavement of said road;

thence North 27°13'00" East a distance of 772.37 feet to a 5/8 inch rebar set with a 1 1/4 inch identification cap stamped Tobin-McFarland in said road;

thence South 39°30'47" East a distance of 482.56 feet to a point in Jake Tom Road (T. R. 352) and on the east line of Fractional Lot #4;

thence South 00°11'16" West, passing a 5/8 inch rebar found with a 1 1/4 inch identification cap stamped Seymour and Associates at 34.49 feet, a distance of 558.59 feet to the point of beginning, containing *10.939 Acres*, and subject to all legal easements, restrictions, and rights-of-way of record.

Bearings are based on the south line of Fractional Lot #4 being North 90°00'00" West by previous surveys. Rebars set are 5/8 inch by 36 inches and have a 1 1/4 inch yellow plastic identification cap stamped "Tobin-McFarland". For additional information see plat of survey made in conjunction with and considered an integral part of this description.

This description is based on a survey made in October of 2005 by Tobin-McFarland Surveying, Inc., and was prepared by Robert N. McFarland, Registered Professional Surveyor No. 7492.



Robert N. McFarland 10/25/05
Robert N. McFarland, P.S.
October 25, 2005 originals are signed in blue ink

b-100

Approved - Mathematically
Hocking County Engineer's Office
BY *W.P. C.W.* DATE *11-04-2005*



Description of 5.087 Acres

Situated in the State of Ohio, County of Hocking, Township of Green, Township 13, Range 16, Fractional Lot #4, section 17.

Being part of the 42.5 acre tract described in a deed to Clark R. Truax, recorded in official record 221, page 364, and being more fully described as follows:

Beginning at a 5/8 inch rebar found with a 1 1/4 inch identification cap stamped LPG-6344 at the northeast corner of Fractional Lot #4;

thence South 00°11'16" West, passing a 5/8 inch rebar found with a 1 1/4 inch identification cap stamped LPG-6344 at 85.01 feet, and passing a 5/8 inch rebar set with a 1 1/4 inch identification cap stamped Tobin-McFarland at 841.62 feet, a distance of 871.62 feet to a point in Jake Tom Road (T. R. 352);

thence with said road North 39°30'47" West a distance of 482.56 feet to a 5/8 inch rebar set with a 1 1/4 inch identification cap stamped Tobin-McFarland in Scout Road (T. R. 350);

thence North 12°26'48" West a distance of 215.55 feet to a point in Scout Road (T. R. 350), said point is located North 88°36'59" East a distance of 30.00 feet from a 5/8 inch rebar set with a 1 1/4 inch identification cap stamped Tobin-McFarland;

thence North 02°00'00" West a distance of 235.00 feet a point in Scout Road (T. R. 350);

thence North 81°34'34" East, passing a 5/8 inch rebar found (uncapped) at 27.05 feet, a distance of 368.52 feet to the point of beginning, containing *5.087 Acres*, and subject to all legal easements, restrictions, and rights-of-way of record.

Bearings are based on the south line of Fractional Lot #4 being North 90°00'00" West by previous surveys. Rebars set are 5/8 inch by 36 inches and have a 1 1/4 inch yellow plastic identification cap stamped "Tobin-McFarland". For additional information see plat of survey made in conjunction with and considered an integral part of this description.

This description is based on a survey made in October of 2005 by Tobin-McFarland Surveying, Inc., and was prepared by Robert N. McFarland, Registered Professional Surveyor No. 7492.




Robert N. McFarland 10/25/05
Robert N. McFarland, P.S.
October 25, 2005 originals are signed in blue ink

b-100


Approved - Mathematically
Hocking County Engineer's Office

BY WB, CW DATE 11-04-2005



S. & A. WERT
VOL. 143, PG. 838

D. THURSH
VOL. 170, PG. 744



SEE
REVISED
SURVEY
BY SEYMOUR
1998

Need
Description

BOY SCOUTS OF AMERICA
CENTRAL OHIO COUNCIL
VOL. 104, PG. 380

Approved - Mechanically
Hocking County Engineer's Office
By: *[Signature]* Date: 5-21-10

BEARINGS ARE BASED ON THE EAST LINE
OF SECTION 17 BEARING S 0° 05' 01" E.

MONUMENTS SET ARE IRON
PINS ONE (1) INCH DIAMETER
SET IN CONCRETE THAT IS
SIX (6) INCHES IN DIAMETER




THE TCW COMPANY	
28 S.R. 92 NE, NEW LEXINGTON, OHIO 41764 (614) 442-3100	
T.C.W.	
SURVEY FOR: M. BENICK	
REVISED: 10/13/94	DATE: 12/6/99
IRON PIN SET W/D. CORR.	RANGE: 18
IRON PIN FOUND	TOWNSHIP: 13
POST	SECTION: 17 LOT 8 & 11 LOT 11
RAILROAD SPIKE SET	POL. TOWNSHIP: GREEN
R.R. SPIKE FOUND	COUNTY: HOCKING
SCALE: 1" = 100'	
POINT	MONUMENT SET
STATE OF OHIO	
RONALD M. MERRICKLE OHIO REG. SURVEYOR NO. 8473	
THOMAS G. WILSON OHIO REG. SURVEYOR	

18 12
17 11

1" = 400'

NORTH




SEE PLAT
THIS FOLDER

- 5.89 Ac.
- 6.55 Ac.
- 7.86 Ac.
- 8.93 Ac.
- 5.97 Ac.
- 21.62 Ac.
- 16.04 Ac.
- 7.27 Ac.
- 5.62 Ac.
- 19.36 Ac.
- NE PTS.

GREEN 17+11

1725
1125

The T C W Company



Engineering • Surveying
Resource Development

1218 State Route 93 NE • New Lexington, Ohio 43764 • 614-342-5131 • FAX: 614-342-4832

DEED DESCRIPTION

Renick
~~Tract 3~~

Being a part of the Northeast Quarter of Section 17 and Part Lot No. 6, Township 13 North, Range 16 West, Green Township, Hocking County, Ohio and more particularly described as follows:


Beginning, for reference, at an iron pin set at the northeast corner of Section 17 and Part Lot No. 5; thence South $59^{\circ} 30' 47''$ West 1323.451 feet to an iron pin set and the principal place of beginning; thence North $88^{\circ} 50' 01''$ East 327.002 feet to an iron pin set; thence South $00^{\circ} 22' 24''$ East 646.412 feet to an iron pin set, passing an iron pin set at 130.000 feet; thence South $64^{\circ} 48' 16''$ West 1038.906 feet to a point on the centerline of Township Road 350, passing an iron pin set at 1013.906 feet; thence North $24^{\circ} 32' 11''$ West 150.000 feet along the centerline of Township Road 350 to a point; thence North $64^{\circ} 48' 16''$ East 746.303 feet to an iron pin set, passing an iron pin set at 25.000 feet; thence North $00^{\circ} 22' 24''$ West 627.865 feet to the principal place of beginning.

The tract as surveyed contains 7.86 acres, more or less, subject to all highways and easements of record.

The bearings in the tract described are based on the east line of Section 17 bearing South $00^{\circ} 05' 01''$ East.

Iron pins set are 5/8 inch rebar, 30 inches long with plastic identification caps set flush with the ground.

Approved - Mathematically
Hocking County Engineer's office
By M. A. [Signature] Date 1-3-94




[Signature]

T. Chris Wilson
Ohio Reg. Surveyor No. 6465

Date: December 30, 1993

The T.C.W. Company



Engineering • Surveying
Resource Development

So. Main St. • P.O. Box 648 • New Lexington, Ohio 43764 • 614-342-5131

DEED DESCRIPTION

Renick
~~Tract-2~~

Being a part of the Northeast Quarter of Section 17 and Part Lot No. 6, Township 13 North, Range 16 West, Green Township, Hocking County, Ohio and more particularly described as follows:

Beginning, for reference, at an iron pin set⁵ at the northeast corner of Section 17 and Part Lot No. 6; thence South 59° 30' 47" West 1323.451 feet to an iron pin set and the principal place of beginning; thence South 88° 50' 01" West 315.320 feet to an iron pin set; thence South 00° 22' 24" East 604.077 feet to an iron pin set; thence South 64° 48' 16" West 466.570 feet to a point on the centerline of Township Road 350, passing an iron pin set at 441.570 feet; thence South 24° 32' 11" East 150.000 feet along the centerline of Township Road 350 to a point; thence North 64° 48' 16" East 746.303 feet to an iron pin set, passing an iron pin set at 25.000 feet; thence North 00° 22' 24" West 627.865 feet to the principal place of beginning.

The tract as surveyed contains 6.55 acres, more or less, subject to all highways and easements of record.

The bearings in the tract described are based on the east line of Section 17 bearing South 00° 05' 01" East.

Iron pins set are 5/8 inch rebar, 30 inches long with plastic identification caps set flush with the ground.



T. Chris Wilson


T. Chris Wilson
Ohio Reg. Surveyor No. 6465

Date: December 6, 1989

Approved - Mathematically
Hocking County Engineer's office
By *J. A. W.* Date *5-7-90*

THIS PAGE
LEFT BLANK
INTENTIONALLY

The T.C.W. Company



Engineering • Surveying
Resource Development

1218 State Route 93 NE • New Lexington, Ohio 43764 • 614-342-5131 • FAX: 614-342-4832

DEED DESCRIPTION

Renick
~~Tract 5~~


Being a part of the Northeast Quarter of Section 17 and Part Lot No. 6, Township 13 North, Range 16 West, Green Township, Hocking County, Ohio and more particularly described as follows:

Beginning, for reference, at an iron pin set at the northeast corner of Section 17 and Part Lot No. 6; thence South 00° 05' 01" East 560.384 feet along the east line of Section 17 and Part Lot #6 to a point in the centerline of Township Road 16; thence South 42° 17' 19" West 330.913 feet to an iron pin set, passing an iron pin set at 25.000 feet; thence North 88° 59' 31" West 180.943 feet to an iron pin set; thence South 00° 22' 24" East 481.935 feet to an iron pin set; thence South 64° 48' 16" West 162.000 feet to an iron pin set and the principal place of beginning for the tract herein to be described; thence South 50° 12' 37" East 376.641 feet to an iron pin set; thence South 79° 24' 57" West 696.857 feet to an iron pin set; thence South 65° 44' 46" West 499.049 feet to an iron pin set; thence South 74° 38' 25" West 288.276 feet to a point in the centerline of Township Road 350, passing an iron pin set at 263.276 feet; thence North 00° 32' 49" East 22.949 feet to a point in the centerline of Township Road 350; thence North 08° 55' 06" West 91.051 feet to a point in the centerline of Township Road 350; thence North 64° 48' 16" East 1262.589 feet to the place of beginning, passing an iron pin set at 25.000 feet.

The tract as surveyed contains 5.97 acres, more or less, subject to all highways and easements of record.

The bearings in the tract described are based on the east line of Section 17 bearing South 00° 05' 01" East.

Iron pins set are 5/8 inch rebar, 30 inches long with plastic identification caps set flush with the ground.




Approved: _____
Hocking County Engineer's Office
By: *J.C.W.* Date: 6-27-94

T.C. Wilson

T. Chris Wilson
Ohio Reg. Surveyor No. 6465

Date: June 15, 1994

The T.C.W. Company



Engineering • Surveying
Resource Development

1218 State Route 93 NE • New Lexington, Ohio 43764 • 614-342-5131 • FAX: 614-342-4832

DEED DESCRIPTION

Renick ~~Tract 6~~

Being a part of the Northeast Quarter of Section 17 and Part Lot No. 6, Township 13 North, Range 16 West, Green Township, Hocking County, Ohio and more particularly described as follows:

Beginning, for reference, at an iron pin set in concrete at the northeast corner of Section 17 and Part Lot No. 5; thence South $00^{\circ} 05' 01''$ East 1728.61 feet along the east line of Section 17 and Part Lot No. 6 to an iron pin set and the principal place of beginning; thence South $00^{\circ} 05' 01''$ East 502.000 feet along the east line of Section 17 and Part Lot No. 6 to an iron pin set; thence South $83^{\circ} 08' 52''$ West 1710.680 feet to a point on the centerline of Township Road 350, passing an iron pin set at 1685.680 feet; thence North $01^{\circ} 56' 42''$ West 45.835 feet along the centerline of Township Road 350 to a point; thence North $04^{\circ} 30' 39''$ East 267.795 feet along the centerline of Township Road 350 to a point; thence North $00^{\circ} 32' 49''$ East 99.157 feet along the centerline of Township Road 350 to a point; thence North $74^{\circ} 38' 25''$ East 288.276 feet to an iron pin set, passing an iron pin set at 25.000 feet; thence North $65^{\circ} 44' 46''$ East 499.049 feet to an iron pin set; thence North $79^{\circ} 24' 57''$ East 696.857 feet to an iron pin set; thence South $66^{\circ} 02' 50''$ East 283.719 feet to the principal place of beginning.

The tract as surveyed contains 21.62 acres, more or less, subject to all highways and easements of record.

The above property was deeded to Milton and Ruth Renick by deed reference Volume 200, Page 518, Hocking County Recorder's Office.

The bearings in the tract described are based on the east line of Section 17 bearing South $00^{\circ} 05' 01''$ East.

Iron pins set are 5/8 inch rebar, 30 inches long with plastic identification caps set flush with the ground.




T. C. Wilson

T. Chris Wilson
Ohio Reg. Surveyor No. 6465

Date: December 6, 1989
Revised: October 3, 1994

Hocking County Engineers Office
By *M. And. Date* 10-18-94

The T.C.W. Company



Engineering • Surveying
Resource Development

1218 State Route 93 NE • New Lexington, Ohio 43764 • 614-342-5131 • FAX: 614-342-4832

DEED DESCRIPTION

Renick
~~Tract 7~~

Being a part of the east half of Section 17 and Part Lot No. 6, Township 13 North, Range 16 West, Green Township, Hocking County, Ohio and more particularly described as follows:

Beginning, for reference, at an iron pin set in concrete at the northeast corner of Section 17 and Part Lot No. 5; thence South 00° 05' 01" East 2230.619 feet along the east line of Section 17 and Part Lot No. 6 to an iron pin set and the principal place of beginning; thence South 00° 05' 01" East 521.590 feet along the east line of Section 17 and Part Lot No. 6 to an iron pin set; thence South 89° 59' 35" West 1581.983 feet to a point on the centerline of Township Road 350, passing an iron pin set at 1556.983 feet; thence North 28° 01' 50" West 118.764 feet along the centerline of Township Road 350 to a point; thence North 21° 48' 50" West 125.460 feet along the centerline of Township Road 350 to a point; thence North 11° 27' 32" West 69.737 feet along the centerline of Township Road 350 to a point; thence North 01° 56' 42" West 28.039 feet along the centerline of Township Road 350 to a point; thence North 83° 08' 52" East 1710.680 feet to the principal place of beginning, passing an iron pin set at 25.000 feet.

The tract as surveyed contains 16.04 acres, more or less, subject to all highways and easements of record.

The above property was deeded to Milton and Ruth Renick by deed reference Volume 200, Page 518, Hocking County Recorder's Office.

The bearings in the tract described are based on the east line of Section 17 bearing South 00° 05' 01" East.

Iron pins set are 5/8 inch rebar, 30 inches long with plastic identification caps set flush with the ground.




T. Chris Wilson

T. Chris Wilson
Ohio Reg. Surveyor No. 6465

Date: December 6, 1989
Revised: October 3, 1994

Approved: *[Signature]*
Hocking County Engineer's Office
Date: 10-18-94

The T&W Company



Engineering • Surveying
Resource Development

1218 State Route 93 NE • New Lexington, Ohio 43764 • 614-342-5131 • FAX: 614-342-4832

DEED DESCRIPTION

Renick
~~Tract 9~~

Being a part of the Northeast Quarter of Section 17 and Part Lot No. 5 and Part Lot No. 6 and the Northwest Quarter of Section 11 and Part Lot No. 11, Township 13 North, Range 16 West, Green Township, Hocking County, Ohio and more particularly described as follows:

Beginning, for reference, at an iron pin set in concrete at the northeast corner of Section 17 and Part Lot No. 5; thence South
00° 05' 01" East 560.384 feet along the east line of Section 17 and Part Lot No. 6 to a point in the center of Township Road 16 and the principal place of beginning; thence South 57° 34' 30" East 7.431 feet along the centerline of Township Road 16 to a pin set; thence South 43° 36' 04" East 275.000 feet along the centerline of Township Road 16 to a point; thence South 39° 39' 15" West 306.012 feet to an iron pin set on the west line of Section 11 and Part Lot No. 11, passing an iron pin set at 25.000 feet; thence South 23° 28' 08" West 648.458 feet to an iron pin set; thence North 50° 12' 37" West 376.641 feet to an iron pin set; thence North 64° 48' 16" East 162.000 feet to an iron pin set; thence North 00° 22' 24" West 481.935 feet to an iron pin set; thence South 88° 59' 31" East 180.943 feet to an iron pin set; thence North 42° 17' 19" East 330.913 feet to the principal place of beginning, passing an iron pin set at 305.913 feet.

The tract as surveyed contains 7.27 acres, more or less, subject to all highways and easements of record with 6.28 acres in Section 17 and 0.99 acres in Section 11.

The above property was deeded to Milton and Ruth Renick by deed reference Volume 200, Pages 516 and 518, Hocking County Recorder's Office.

The bearings in the tract described are based on the east line of Section 17 bearing South 00° 05' 01" East.

Iron pins set are 5/8 inch rebar, 30 inches long with plastic identification caps set flush with the ground.




T. C. Wilson

T. Chris Wilson
Ohio Reg. Surveyor No. 6465

Date: December 6, 1989
Revised: October 3, 1994

Approved - Mathematically
Hocking County Engineer's office
By *Jytlw* Date 10-18-94

The T C W Company



Engineering • Surveying
Resource Development

1218 State Route 93 NE • New Lexington, Ohio 43764 • 614-342-5131 • FAX: 614-342-4832

DEED DESCRIPTION

Renick
~~Tract 10~~

Being a part of the Northeast Quarter of Section 17 and Part Lot No. 6 and the Northwest Quarter of Section 11 and Part Lot No. 11, Township 13 North, Range 16 West, Green Township, Hocking County, Ohio and more particularly described as follows:

Beginning, for reference, at an iron pin set in concrete at the northeast corner of Section 17 and Part Lot No. 5; thence South
00° 05' 01" East 1018.618 feet along the east line of Section 17 and Part Lot No. 6 to an iron pin set and the principal place of beginning; thence North 39° 39' 15" East 306.012 feet to a point on the centerline of Township Road 16, passing an iron pin set at 281.012 feet; thence South 43° 36' 04" East 115.847 feet along the centerline of Township Road 16 to a point; thence South 43° 37' 02" East 284.450 feet to an iron pin found; thence South 09° 52' 10" West 398.352 feet to a point on the centerline of Township Road 16; thence South 04° 34' 54" East 63.511 feet along the centerline of Township Road 16 to a point; thence South 24° 33' 20" East 51.162 feet along the centerline of Township Road 16 to a point; thence South 34° 15' 29" East 177.811 feet along the centerline of Township Road 16 to a point; thence South 37° 18' 47" East 125.065 feet along the centerline of Township Road 16 to a point; thence South 46° 09' 37" East 84.963 feet along the centerline of Township Road 16 to a point; thence South 53° 57' 37" East 56.815 feet along the centerline of Township Road 16 to a point; thence South 59° 37' 55" East 136.472 feet along the centerline of Township Road 16 to a point; thence South 63° 15' 32" East 196.334 feet along the centerline of Township Road 16 to a point; thence South 56° 28' 57" West 285.000 feet to an iron pin set, passing an iron pin set at 25.000 feet; thence South 89° 50' 48" West 766.300 feet to an iron pin set on the west line of Section 11 and Part Lot No. 11; thence North 00° 05' 01" West 502.000 feet to an iron pin set; thence North 66° 02' 50" West 283.719 feet to an iron pin set; thence North 23° 28' 08" East 648.458 feet to the principal place of beginning.

The tract as surveyed contains 19.36 acres, more or less, subject to all highways and easements of record with 2.11 acres

in Section 17 and 17.25 acres in Section 11.

The above property was deeded to Milton and Ruth Renick by deed reference Volume 200, Page 518, Hocking County Recorder's Office.

The bearings in the tract described are based on the east line of Section 17 bearing South 00° 05' 01" East.

Iron pins set are 5/8 inch rebar, 30 inches long with plastic identification caps set flush with the ground.




T. C. Wilson

T. Chris Wilson
Ohio Reg. Surveyor No. 6465

Date: December 6, 1989
Revised: October 3, 1994

Approved - Mathematically
Hocking County Engineer's office
by *J. A. W.* Date *10-18-94*

The T&W Company



Engineering • Surveying
Resource Development

So. Main St. • P.O. Box 648 • New Lexington, Ohio 43764 • 614-342-5131

DEED DESCRIPTION

Renick
~~Tract~~

Being a part of the Northeast Quarter of Section 17 and Part Lot No. 6, Township 13 North, Range 16 West, Green Township, Hocking County, Ohio and more particularly described as follows:

Beginning, for reference, at an iron pin set at the northeast corner of Section 17 and Part Lot No. 6; thence South $65^{\circ} 01' 51''$ West 1605.817 feet to an iron pin set and the principal place of beginning; thence South $88^{\circ} 50' 01''$ West 118.485 feet to an iron pin found; thence North $84^{\circ} 01' 07''$ West 140.245 feet to a post; thence South $00^{\circ} 20' 44''$ West 451.781 feet to an iron pin set; thence South $89^{\circ} 33' 03''$ West 338.739 feet to a point on the centerline of Township Road 350, passing an iron pin set at 313.739 feet; thence South $37^{\circ} 56' 56''$ East 68.168 feet along the centerline of Township Road 350 to a point; thence South $24^{\circ} 18' 04''$ East 172.218 feet along the centerline of Township Road 350 to a point; thence South $24^{\circ} 32' 11''$ East 164.614 feet along the centerline of Township Road 350 to a point; thence North $64^{\circ} 48' 16''$ East 466.570 feet to an iron pin set, passing an iron pin set at 25.000 feet; thence North $00^{\circ} 22' 24''$ West 604.077 feet to the principal place of beginning.

The tract as surveyed contains 5.89 acres, more or less, subject to all highways and easements of record.

The bearings in the tract described are based on the east line of Section 17 bearing South $00^{\circ} 05' 01''$ East.

Iron pins set are 5/8 inch rebar, 30 inches long with plastic identification caps set flush with the ground.



T. Chris Wilson
Ohio Reg. Surveyor No. 6465

Date: December 6, 1989

Approved - Mathematically
Hocking County Engineer's Office

DATE 11-29-89

BEING A PART OF FRAC. LOTS 7 & 8
 SEC. 17 GREEN TWP., T-13N, R-16W
 HOCKING CO., OHIO

F. LEMON
 VOL. 95 PG. 631

NE COR. FRAC. LOT 8
 SEC. 17, T-13N, R-16W

C. WOLFE
 VOL. 176 PG. 229

TRACT 1
 5.3963 ACRES

LOT 6
 LOT 9
 365.0' (PLAT)

SEC. 17
 SEC. 11

159.20
 N 77° 33' 06" E
 176.23

1183.03
 S 88° 36' 05" W

TRACT 2
 3.4037 ACRES

1170.77
 N 89° 48' 09" W

141.52'
 194.40'

74.42'

816.61'

742.19'

816.61'

742.19'

816.61'

742.19'

816.61'

742.19'

816.61'

742.19'

816.61'

C.O.B.S.C.
 VOL. 104 PG. 380



SCALE: 1" = 100'
 O = IRON PIN(S)
 ● = IRON PIPE (F)

NOTE: BEARINGS WERE ARBITRARILY ASSIGNED AND ARE FOR DETERMINATION OF ANGLES ONLY

REFERENCES:
 COUNTY TAX MAPS
 1880 PLAT RECORDS

DEEDS:
 174-973
 176-227
 154-723
 176-229
 104-380
 95-631

SE COR. OF FRAC. LOTS 8
 SEC. 17, T-13N, R-16W
 IRON PIN BEARS S 01° 00' 46" W
 7.02'

W.C. ADAIR, CO.
 VOL. 154 PG. 723

TRACT 4
 2.00 ACRES

TRACT 3
 21.6154 ACRES

N 88° 34' 17" E
 217.80'

435.60'

200.00'
 S 01° 25' 43" E

S 88° 34' 17" W
 435.60'

217.80'

C.O.B.S.C.
 VOL. 116 PG. 58

1114.67'

S 82° 29' 44" W

1141.93'

SUBDIVISION REGULATIONS WAIVED *
 PENDING HEALTH DEPT. APPROVAL

BY *AW* DATE 2-25-81

* FOR TRACTS 2 & 4
 See Attached

Approved - Mathematically
 Hocking County Engineer's Office
AW FN Date 9-30-80

Revised: *AW* 2-25-81
 Revised: *AW DW* 6-10-81

I hereby certify that an actual survey was made under my supervision of the premises shown hereon on the 4TH day of SEPTEMBER, 1980; and that the plat is a correct representation of the premises as determined by said survey. I further certify that there are no encroachments either way across any boundary line except as shown hereon.

Howard Seymour
 REGISTERED SURVEYOR NO. 6044

Seymour-Shaw & Associates, Inc.
 Consulting Engineers & Surveyors
 615 Walthonding Ave. (814) 385-4349
 LOGAN, OHIO 43138

Green Twp.
Sec. 17

Seymour-Shaw & Associates, Inc.

Consulting Engineers & Surveyors

WILLIAM R. SHAW, P.E., P.S.
GEORGE F. SEYMOUR, P.S.

PHONE
614 - 385-4349

615 WALHONDING AVE.
LOGAN, OHIO 43138

Description of Survey for Curtis Wolfe

Tract 1:

Being a part of Fractional Lots 7 and 8 situate in Section 17, T13N, R16W, Green Township, Hocking County, State of Ohio, and more particularly described as follows:

Beginning at a 5/8" iron pin set on the northeast corner of Fractional Lot 8 situate in Section 17, T13N, R16W;

Thence with the east line of Fractional Lot 8, South 1° 00' 46" West a distance of 141.52 feet to a 5/8" iron pin set;

Thence leaving the east line of Fractional Lot 8, South 83° 36' 05" West a distance of 1183.03 feet to a 5/8" iron pin set in the center of Township Road 350;

Thence with the center of said road, North 1° 25' 43" West a distance of 120.85 feet to a point;

Thence leaving the center of said road and with the south line of a .71 acre tract as recorded in Deed Book 176 at page 229, Hocking County Recorder's Office, North 77° 33' 06" East, passing through an iron pipe found at 17.03 feet, going a total distance of 176.23 feet to the southeast corner of said .71 acre tract;

Thence with the east line of said .71 acre tract, North 12° 49' 10" West a distance of 141.00 feet to a point on the south line of Fractional Lot 6;

Thence with the south line of Fractional Lot 6, South 88° 44' 12" East a distance of 1040.63 feet to the place of beginning, containing 5.3963 acres, more or less, subject to the right of way of Township Road 352.

The above described tract was surveyed by George F. Seymour, Ohio Registered Surveyor No. 6044, September 4, 1980.

George F. Seymour

Approved - Mathematically
Hocking County Engineer's Office
By W. W. W. Date 2-25-81
7/11

Seymour-Shaw & Associates, Inc.

Consulting Engineers & Surveyors

WILLIAM R. SHAW, P.E., P.S.
GEORGE F. SEYMOUR, P.S.

PHONE
614-385-4349

515 WALHONDING AVE.
LOGAN, OHIO 43138

Description of Survey for Connie Scarberry

Tract 2:

Being a part of Fractional Lots 7 and 8 situate in Section 17, T13N, R16W, Green Township, Hocking County, State of Ohio, and more particularly described as follows:

Beginning at a 5/8" iron pin set on the east line of Fractional Lot 8 in Section 17, T13N, R16W, from which a 5/8" iron pin set on the northeast corner of Fractional Lot 8 bears North 1° 00' 46" East a distance of 141.52 feet;

Thence with the east line of Fractional Lot 8, South 1° 00' 46" West a distance of 194.40 feet to a point from which a 5/8" iron pin bears South 1° 00' 46" West a distance of 74.42 feet;

Thence leaving the east line of Fractional Lot 8, North 89° 48' 09" West a distance of 1170.77 feet to a 5/8" iron pin set in the center of Township Road 350;

Thence with the center of said road, North 1° 25' 43" West a distance of 58.51 feet to a 5/8" iron pin set;

Thence leaving the center of said road, North 83° 36' 05" East a distance of 1183.03 feet to the place of beginning, containing 3.4037 acres, more or less, subject to the right of way of Township Road 350.

The above described tract was surveyed by George F. Seymour, Ohio Registered Surveyor No. 6044, September 4, 1980.

George F. Seymour

Approved - Mathematically
Hocking County Engineer's Office
By Ben Daw Date 6-10-81

SUBMISSION REGULATIONS WAIVED
PENDING HEALTH DEPT. APPROVAL
BY Ben DATE 6-10-81

Sec Attached

Seymour-Shaw & Associates, Inc.

Consulting Engineers & Surveyors

WILLIAM R. SHAW, P.E., P.S.
GEORGE F. SEYMOUR, P.S.

PHONE
614 - 385-4349

615 WALHONDING AVE.
LOGAN, OHIO 43138

Description of Survey for
Paul and Kathryn Francis
and
Paula and Richard Mowery

Tract 3:

Being a part of Fractional Lots 7 and 8 situate in Section 17, T13N, R16W, Green Township, Hocking County, State of Ohio, and more particularly described as follows:

Beginning at the southeast corner of Fractional Lot 8 situate in Section 17, T13N, R16W, said corner being referenced by a 5/8" iron pin set which bears South 1° 00' 46" West a distance of 7.02 feet;

Thence with the south line of Fractional Lot 8, South 82° 29' 44" West, passing through a 5/8" iron pin set at 1114.67 feet, going a total distance of 1141.93 feet to a point in the center of Township Road 350;

Thence with the center of said road, North 1° 25' 43" West a distance of 489.64 feet to a 5/8" iron pin set;

Thence leaving the center of said road, North 88° 34' 17" East, passing through a 5/8" iron pin set at 217.80 feet, going a total distance of 435.60 feet to a 5/8" iron pin set;

Thence North 1° 25' 43" West a distance of 200.00 feet to a 5/8" iron pin set;


Thence South 88° 34' 17" West, passing through a 5/8" iron pin set at 217.80 feet, going a total distance of 435.60 feet to a 5/8" iron pin set in the center of Township Road 350;


Thence with the center of said road, North 1° 25' 43" West a distance of 280.31 feet to a 5/8" iron pin set;

Thence leaving the center of said road, South 89° 48' 09" East a distance of 1170.77 feet to a point on the east line of Fractional Lot 8;

Thence with the east line of Fractional Lot 8, South 1° 00' 46" West, passing through a 5/8" iron pin set at 74.42 feet, going a total distance of 816.61 feet to the place of beginning, containing 21.6184 acres, more or less, subject to the right of way of Township Road 350.

The above described tract was surveyed by George F. Seymour, Ohio Registered Surveyor No. 6044, September 4, 1980.



Approved - Mathematically
Hocking County Engineer's Office
By  Date 6-10-81

Seymour-Shaw & Associates, Inc.

Consulting Engineers & Surveyors

WILLIAM R. SHAW, P.E., P.S.
GEORGE F. SEYMOUR, P.S.

PHONE
614-385-4349

615 WALHONDING AVE
LOGAN, OHIO 43138

Description of Survey for Connie Scarberry

Tract 4:

Being a part of Fractional Lots 7 and 8 situate in Section 17, T13N, R16W, Green Township, Hocking County, State of Ohio, and more particularly described as follows:

Beginning, for reference, at the southeast corner of Fractional Lot 8 situate in Section 17, T13N, R16W, said corner being referenced by a 1/8" iron pin set which bears South 1° 00' 46" West a distance of 7.02 feet;

Thence with the south line of Fractional Lot 8, South 82° 29' 44" West, passing through a 5/8" iron pin set at 1114.67 feet, going a total distance of 1141.93 feet to a point in the center of Township Road 350;

Thence with the center of said road, North 1° 25' 43" West a distance of 489.64 feet to a 5/8" iron pin set for the principal place of beginning of the tract herein described;

Thence continuing with the center of said road, North 1° 25' 43" West a distance of 200.00 feet to a 5/8" iron pin set;

Thence leaving the center of said road, North 88° 34' 17" East, passing through a 5/8" iron pin set at 217.80 feet, going a total distance of 435.60 feet to a 5/8" iron pin set;

Thence South 1° 25' 43" East a distance of 200.00 feet to a 5/8" iron pin set;

Thence South 88° 34' 17" West, passing through a 5/8" iron pin set at 217.80 feet, going a total distance of 435.60 feet to the principal place of beginning, containing 2.00 acres, more or less, subject to the right of way of Township Road 350.

The above described tract was surveyed by George F. Seymour, Ohio Registered Surveyor No. 6044, September 4, 1980.

George F. Seymour

Approved - Mathematically
Hocking County Engineer's Office
By *John Dew* Date *6/10/81*

SUED BY _____
FEE _____
BY *John Dew* Date *6-10-81*

See Attached

TRACT 2
3.4037 ACRES

09° W

194.40

742.19'

876.61'

876.61'

1018'

1018'

1018'

1018'

1018'

1018'

1018'

1018'

C.O.S.C.
VOL. 104 / PG. 380



SCALE: 1" = 100'
O = IRON PIN (8)
● = IRON PIPE (8)

NOTES: BEARINGS AND DISTANCES ARE ARBITRARY FOR IRON PINS AND ANGLES ONLY

REFERENCES:
COUNTY TAX MAPS
1880 PLAT RECORDS

DEEDS:
716-513
716-241
754-728
716-201
754-880
95-431

SE COR. OF FRAC. NOTE
SEE INT. TOWN R. 16 W
IRON PIN GEARS BOUNDARY
7.02

Lot 8
Lot 1
A W 1141.93'

I hereby certify that an actual survey was made under the supervision of the premises shown hereon on the 4th day of SEPTEMBER, 1980, and that the plat is a correct representation of the premises as determined by said survey. I further certify that there are no encroachments or other ways across any boundary line except as shown hereon.

James W. Schuman
REGISTERED SURVEYOR NO. 11044

APPROVED
3-26-82
LOGAN-HOCKING COUNTY
HEALTH DEPT.

James W. Schuman, Inc.
Professional Engineers & Surveyors
618 Washington Ave., Logan, Ohio 43138
LOGAN, OHIO 43138

GREEN 17
2.043 AC.

PLAT OF A 2.043 ACRE TRACT FOR PAUL POSTON



Situated in Green Township, Hocking County, Ohio; being part of Fractional Lot 6 of Section 17, Township 13, Range 16.

REFERENCES:

- Tax maps
- Deed descriptions
- Previous surveys
- Existing monumentation
- Existing public road

Larry Lemon
 213-339,
 OR104-731

Center of Township
 Road 16;
 Maysville Greendale Road



Christopher Goss &
 Carol Bush
 OR12-759

Dorothy Thrush
 170-744
 2.043 acres

LEGEND

- 5/8" x 30" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 set
- ▲ PK nail set
- Railroad spike found
- ⊙ 2" OD iron pipe found
- ⊙ 2-1/2" OD iron pipe found

Approved: - Mathematically
 Hocking County Engineer's Office

SUBDIVISION REGULATIONS WAIVED
 PENDING HEALTH DEPT. APPROVAL
 BY Larry P. Gerstner DATE 2-18-99

REFERENCE BEARING:

The North line of Section 17 as South 90 degrees 00 minutes 00 seconds East. Bearings are based upon an assumed meridian and are to denote angles only.

CERTIFICATION:

I hereby certify that an actual survey was made under my supervision of the premises shown hereon on the 18th day of February, 1999 and that the plat is a correct representation of the premises as described by said survey.

Larry P. Gerstner
 Registered Surveyor No. 6344

Survey by:

Larry P. Gerstner - Engineering and Surveying
 9 East Second Street, Suite A, Logan, Ohio 43138
 (740) 385-4260

SURVEY DESCRIPTION OF A 2.043 ACRE TRACT FOR PAUL POSTON

Situated in Green Township, Hocking County, Ohio; being part of Fractional Lot 6 of Section 17, Township 13, Range 16; and being more particularly described as follows:

Commencing for reference at a 2" OD iron pipe found in the center of Township Road 350, Scout Road, at the Northwest corner of the Northeast quarter of Section 17; thence with the North line of Section 17 and the surface of Township Road 16, Maysville Greendale Road, South 90 degrees 00 minutes 00 seconds East a distance of 543.05 feet to a 5/8" iron pin set and being the point of **Beginning** of the tract of land to be described;

thence continuing with the North line of Section 17 and the surface of said Township Road 16 South 90 degrees 00 minutes 00 seconds East a distance of 201.24 feet to a PK nail set, from which a railroad spike found bears South 90 degrees 00 minutes 00 seconds East at a distance of 331.08 feet;

thence leaving the North line of Section 17 and the surface of said Township Road 16 South 0 degrees 11 minutes 02 seconds West a distance of 442.96 feet to a 5/8" iron pin set, passing a 5/8" iron pin set at a distance of 22.21 feet, and from which a 2" OD iron pipe found bears South 89 degrees 36 minutes 58 seconds East at a distance of 205.05 feet;

thence North 89 degrees 36 minutes 58 seconds West a distance of 201.24 feet to a 2-1/2" OD iron pipe found;

thence North 0 degrees 11 minutes 02 seconds East a distance of 441.62 feet to the point of beginning, passing a 5/8" iron pin set at a distance of 421.62 feet, containing 2.043 acres more or less, and subject to the public easement of said Township Road 16 and any other public or private easements of record.

The above 2.043 acre survey is intended to describe part of the 4 acre tract as deeded to Dorothy Thrush, deed reference Volume 170, Page 744, Hocking County Recorder's Office. This survey was based upon information obtained from tax maps, deed descriptions, previous surveys, existing monumentation, and an existing public road. The reference bearing for this survey is the North line of Section 17 as South 90 degrees 00 minutes 00 seconds East. Bearings are based upon an assumed meridian and are to denote angles only. All iron pins set by this survey are 5/8" by 30" and are capped by a 1-1/4" plastic identification cap stamped LPG-6344. The above described property was surveyed by Larry P. Gerstner, Ohio Registered Surveyor No. 6344, on February 18, 1999.



Approved - Mathematically
Hocking County Engineer's Office

BY [Signature] DATE 2-18-99

[Signature]

SUBDIVISION REGULATIONS WAIVED
PENDING HEALTH DEPT. APPROVAL

BY [Signature] DATE 2-18-99

APPROVED
LOGAN-HOCKING COUNTY
HEALTH DEPT.


Date 3-17-99 [Signature]

Survey by:

Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138 385-4260

PLAT OF A 33.539 ACRE TRACT

Situated in Green Township, Hocking County, Ohio; being part of the south half of the Southwest quarter of Section 17 and part of the Northwest quarter of Section 16, both of Township 13, Range 16.



LEGEND:

- Point
- 5/8"x30" iron pin with 1-1/4" plastic ID cap stamped SVE-8127 set
- 5/8" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 found
- Boundary Line
- - - Adjacent Boundary Line
- - - Road Right of Way

REFERENCES:

- Tax maps
- Deed descriptions
- Previous surveys
- Existing monumentation
- Existing public road

REFERENCE BEARING:



The north line of Section 16 as North 00 degrees 00 minutes 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only.

CERTIFICATION:

I hereby certify that an actual survey was made under my supervision of the premises shown hereon on the 16th day of August, 2021 and that the plat is a correct representation of the premises as described by said survey.

APPROVED MATHEMATICALLY
 Hocking County Engineer's Office
 By: *[Signature]* Date: M. 9 D. 21 21

[Signature]
 Registered Surveyor No. 8127



Survey by: S. Vince Evans Surveying – S. Vince Evans P.S. 8127
 64103 Woodgeard Road, Creola, Ohio 45622
 Phone (740) 380-3884
 FAX (740) 596-5831

SURVEY DESCRIPTION OF A 33.539 ACRE TRACT

Situated in Green Township, Hocking County, Ohio; being part of the south half of the Southwest quarter of Section 17 and part of the Northwest quarter of Section 16, both of Township 13, Range 16; and being more particularly described as follows:

Being part of a 32.177 acre tract as described in Volume OR569, Page 36 to Sandra K. Thrasher and Alycia Ryan; being part of a 37.648 acre tract as described in Volume OR351, Page 649 to Sandra K. Thrasher and Alycia Ryan.

Commencing at a 5/8" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 found at the Northeast corner of the Northwest quarter of Section 16;

Thence with the north line of Section 16, South 90 degrees 00 minutes 00 seconds West a distance of 583.71 feet to a Point, and being the point of **Beginning** of the tract of land to be described;

Thence leaving the north line of Section 16, South 24 degrees 02 minutes 21 seconds East a distance of 356.33 feet to a 5/8" iron pin set;

Thence South 53 degrees 24 minutes 29 seconds West a distance of 169.12 feet to a 5/8" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 found;

Thence South 53 degrees 24 minutes 29 seconds West a distance of 340.77 feet to a 5/8" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 found;

Thence South 36 degrees 45 minutes 36 seconds East a distance of 259.96 feet to a 5/8" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 found;

Thence South 81 degrees 03 minutes 02 seconds East a distance of 540.83 feet to a Point in the centerline of Township Road 350 (Scout Road)(60' R/W), passing 5/8" iron pins with 1-1/4" plastic ID caps stamped LPG-6344 found at distances of 329.61 feet and 523.71 feet;

Thence with the centerline of Township Road 350 (Scout Road), the following 11 bearings and distances:

1) South 31 degrees 05 minutes 04 seconds West a distance of 115.82 feet to a 5/8" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 found;

2) South 51 degrees 54 minutes 41 seconds West a distance of 397.52 feet to a 5/8" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 found;

3) South 54 degrees 34 minutes 02 seconds West a distance of 324.74 feet to a 5/8" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 found;

4) South 46 degrees 40 minutes 27 seconds West a distance of 109.28 feet to a 5/8" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 found at the end of Township Road 351 (Davis-Chapel Road)(60' R/W);

5) South 50 degrees 37 minutes 04 seconds West a distance of 57.95 feet to a Point;

6) North 82 degrees 43 minutes 05 seconds West a distance of 272.76 feet to a Point;

7) North 67 degrees 37 minutes 51 seconds West a distance of 67.79 feet to a Point;

8) North 41 degrees 36 minutes 42 seconds West a distance of 80.98 feet to a Point;

9) North 36 degrees 09 minutes 09 seconds West a distance of 128.36 feet to a Point;

10) North 48 degrees 54 minutes 17 seconds West a distance of 92.89 feet to a Point;

11) North 52 degrees 02 minutes 58 seconds West a distance of 318.61 feet to a Point;

Thence leaving the centerline of Township Road 350 (Scout Road), North 37 degrees 57 minutes 02 seconds East a distance of 654.82 feet to a 5/8" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 found, passing 5/8" iron pins with 1-1/4" plastic ID caps stamped LPG-6344 found at distances of 13.23 feet and 287.35 feet;

Thence North 00 degrees 00 minutes 00 seconds West a distance of 800.12 feet to a 5/8" iron pin set, passing 5/8" iron pins with 1-1/4" plastic ID caps stamped LPG-6344 found at distances of 121.61 feet, 463.48 feet and 535.88 feet, and passing a Point on the north line of Section 16 at a distance of 568.26 feet;

Thence North 90 degrees 00 minutes 00 seconds East a distance of 613.80 feet to a 5/8" iron pin set;


Thence South 24 degrees 02 minutes 21 seconds East a distance of 253.88 feet to the point of beginning and containing 33.539 acres (29.997 acres in section 16 and 3.542 acres in section 17), more or less, subject to any public or private easements of record.

The above 33.539 acre survey was based upon information obtained from tax maps, deed descriptions, previous surveys, existing monumentation, and an existing public road. The reference bearing for this survey is the north line of Section 16 as South 90 degrees 00

minutes 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only.


All iron pins set by this survey are 5/8" by 30" and are capped by a 1-1/4" plastic identification cap stamped "SVE-8127".

The above described property was surveyed by S. Vince Evans, Ohio Registered Surveyor No. 8127, on August 16, 2021.



S. Vince Evans, P. S. 8127



Survey by: S. Vince Evans Surveying
S. Vince Evans, P. S. 8127
64103 Woodgeard Road
Creola, Ohio 45622
Phone (740) 380-3884
FAX (740) 596-5831



APPROVED MATHEMATICALLY
Hocking County Engineer's Office
By:  Date: M. 10 D. 21 Y. 21

SITUATED IN FRACTIONAL LOT No. 6 OF SECTION 17, GREEN TOWNSHIP,
T-13N, R-16W, HOCKING COUNTY, STATE OF OHIO.

New Line Courses
 1. N 60°08'50" E 22.39'
 2. N 78°41'22" E 59.80'
 3. S 84°27'10" E 85.00'
 4. S 60°22'36" E 67.18'



- LEGEND
- ▲ 5/8" X 30" iron pin w/ 1 1/4" plastic ID cap stamped "M.P.B. S-6803" set
 - ⊕ 5/8" iron pin w/ 1 1/4" plastic ID cap stamped "T.C.W. 6455" found
 - point
- _____ boundary line
 - - - - - centerline Twp. Rd. 350- 60'R/W
 - - - - - right of way line
 - - - - - adjacent / political subdivision line
 x x x x x wire fence line

Note: Current and previous tax plats and previous surveys taken from Hocking County Drafting Department's website
 Deeds: as noted on plat

Note: Cited bearings are based on the south line of the 21.62 acre tract described in O.R. Vol.386, Pg.463 as running S 83°11'07" W.

Surveyed and platted by
MICHAEL P. BERRY
 OHIO PROFESSIONAL SURVEYOR #6803
 P.O. BOX 1127
 LOGAN, OHIO 43138
 740-385-3279

RECEIVED
 JUL 05 2022
 HOCKING COUNTY
 ENGINEERS OFFICE

APPROVED MATHEMATICALLY
 Hocking County Engineer's Office
 By: *[Signature]* Date: *MOR 15 DAY Y. 2022*

Filed Hocking County Auditor's Office
 Frank Nelson July 15, 2022

Plat prepared from an actual survey made on the 25th day of March, 2022 by,
[Signature]
 Michael P. Berry Ohio Professional Surveyor No. 6803



DESCRIPTION OF SURVEY FOR MR. & MRS. CHAD ARMSTRONG

Being a part of the 21.62 acre tract described in Vol. 386, Pg. 463, Hocking County Official Records, situated in Fractional Lot No. 6 of Section 17, Green Twp., T-13N, R-16W, Hocking County, Ohio, and being more particularly described as follows:

Beginning at a 5/8" T.C.W. pin found with 1 1/4" plastic I.D. cap stamped "T.C.W. 6455" on the SE corner of said 21.62 acre tract from which a 5/8" T.C.W. pin with a 5/8" plastic I.D. cap stamped "T.C.W. 6544" found on the SE corner of said Fractional Lot No. 6 bears S 0 degrees 02' 44" E a distance of 521.59 ft.;

Thence, with the south line of said 21.62 acre tract, S 83 degrees 11' 07" W, passing a 5/8" T.C.W. pin with a 5/8" plastic I.D. cap stamped "T.C.W. 6455" found at 1684.81 ft., going a total distance of 1709.81 ft. to a point in the center of Twp. Rd. No. 350 (Scout Rd.);

Thence with the centerline of said Twp. road the following two (2) courses:

- 1) N 1 degrees 56' 42" W a distance of 45.83 ft. to a point;
- 2) N 4 degrees 30' 39" E a distance of 267.80 ft. to a point;

Thence leaving Twp. Rd. 350 and with new lines the following five (5) courses:


- 1) N 60 degrees 08' 50" E a distance of 22.39 ft. to an iron pin set;
- 2) N 78 degrees 41' 22" E a distance of 59.80 ft. to an iron pin set;
- 3) S 84 degrees 27' 10" E a distance of 85.00 ft. to an iron pin set;
- 4) S 60 degrees 22' 36" E a distance of 67.18 ft. to an iron pin set;
- 5) N 79 degrees 25' 30" E, passing an iron pin set in an existing fence at 1478.15 ft., going a total distance of 1482.06 ft. to an iron pin set on the east line of Section 17;

Thence, with said east section line, S 0 degrees 02' 44" E a distance of 363.33 ft. to the Place of Beginning, containing 12.1700 acres, more or less, and being subject to the right-of-way of 60 ft. wide Twp. Rd. 350 and all valid easements.

Cited bearings are based on the south line of the 21.62 acre tract described in O.R 386, Pg. 463, as running S 83 degrees 11' 07" W.

All iron pins described as being set are 5/8" X 30" with a 1 1/4" plastic I.D. cap stamped "M.P.B. S-6803".

The above description is the result of an actual survey made by Michael P. Berry, Ohio Registered Surveyor No. 6803, on March 25, 2022.

 (7-1-22)
Michael P. Berry #6803



APPROVED MATHEMATICALLY
Hocking County Engineer's Office
By: AB Date: M. 07. 06. Y. 2022

Filed Hocking County Auditor's Office
Frank Nelson July 15, 2022

RECEIVED
JUL 05 2022
HOCKING COUNTY
ENGINEERS OFFICE

Plat of Survey


Township of Green, County of Hocking, State of Ohio, part Fractional Lot 6 in Section 17, Township 13N, Range 16W.

PROPERTY LOCATION:

Being a Survey of a part of an 8.2777 Acre parcel conveyed to Sarah M. Harkless, as recorded in O.R. Book 449, Page 161, in the Hocking County Deed Records, and being part of Auditor's P.P.N. 060002560200.

BASIS OF BEARING

~~The bearings of this plat are based on the Plat of Heron Bay Amended, as recorded in Plat Book 5, Pages 131-132 & Plat Cabinet Slots 289A & 289B, in the Perry County Plat Records.~~




P.O.C.: Northwest Corner
Northeast Quarter
Section 17

LEGEND

- △ - Railroad Spike Found
- Mag Nail Set
- - 5/8" o.d. Iron Pin Found
w/ 1.25" dia. yellow cap labeled "LPG-6344"
- ⊕ - Iron Pin Set
5/8" Rebar 30" long w/ 1.25" dia. red cap Labeled S.A. England #7452
- ⊕ - 2.5" o.d. Iron Pipe Found
- ▲ - 3/4" o.d. Iron Pin Found (NO CAP)
- - Property line
- - - - - Road R/W Line

RELATED DOCUMENTS


- 1) 1999 Survey of 2.043 Acres by Larry P. Gerstner, P.S. 6344
- 2) 1989 Survey of 5.89 Acres by T. Chris Wilson, P.S. 6465
- 3) 1953 Survey of 5.9757 Acres by A.W. Seabright, P.E., P.S.




Filed Hocking County Auditor's Office
Frank Nelson February 03, 2023

APPROVED MATHEMATICALLY
Hocking County Engineer's Office
By: *[Signature]* Date: M 02 D 01 Y 2023

I hereby certify that an actual survey of the premises was made on December 23, 2022, and that this plat is correct to the best of my knowledge.
Dated 1/31/23
[Signature]
Scott A. England, P.S.
Ohio Registered Surveyor #7452



PREPARED BY:
S.A. ENGLAND SURVEYING
Professional Land Surveying
P.O. Box 1770
Buckeye Lake, Ohio 43008
PHONE: 740-323-0644
email: saengland@surveyohio.com



S.A. ENGLAND SURVEYING

Professional Land Surveying
P.O. Box 1770
Buckeye Lake, Ohio 43008



E-mail: www.surveyohio.com

Phone: 740-323-0644

Fax: 740-323-0272

Ohio Phone: 1-800-551-5844

Legal Description

5.555 Acres

Part Sarah M. Harkless Parcel: O.R. 449, Page 161

166

Situated in the Township of Green, County of Hocking, State of Ohio, and being a part of Fractional Lot 6 in Section 17, Township 13N, Range 16W, and being more particularly described as follows;

Being a Survey of a part of an 8.2777 Acre parcel conveyed to Sarah M. Harkless, as recorded in O.R. 449, Page 161, in the Hocking in the Hocking County Deed Records, being part of Auditor's P.P.N. 060002560200, and further described as follows;

166

Commencing at a railroad spike found marking the Northwest corner of the Northeast Quarter of Section 17;

166

Thence, S 86°16'59" E 543.05 feet with the North line of Section 17, the same being the South line of Section 18, to a 5/8" o.d. iron pin found w/1.25" yellow cap stamped "LPG-6344" marking the Northwest corner of a 2.043 Acre parcel conveyed to Sarah M. Harkless, as recorded in O.R. 449, Page 161, and being the Northeast corner of a 94.9802 Acre parcel conveyed to Christopher Goss & Carol Bush, as recorded in O.R. 12, Page 759;

Thence, S 03°38'52" W 441.62 feet with the West line of said 2.043 Acre parcel conveyed to Harkless, the same being the East line of said parcel conveyed to Goss & Bush, to a 2.5" o.d. iron pipe found, being the **PRINCIPLE PLACE OF BEGINNING** of the 5.555 Acre parcel herein to be described, and passing over a 5/8" o.d. iron pin found w/1.25" yellow cap stamped "LPG-6344 at 20.00 feet;

SEE REVISED

Thence, S 85°54'57" E 201.24 feet with the South line of said 2.043 Acre parcel conveyed to Harkless, to an iron pin set on the boundary of said 8.2777 Acre parcel of which this description is a part;

Thence, S 41°33'29" E 286.47 feet with a line across said 8.2777 Acre parcel, of which this description is a part, to an iron pin set on the East line thereof, and being the Northwest corner of a 5.89 Acre parcel conveyed to Alan R. Holley & Stewart C. Holley, as recorded in O.R. 544, Page 121;

Thence with the boundary of said parcel conveyed to Holley & Holley, with the following two (2) courses and distances:

- 1) S 04°06'15" W 451.22 feet to a 5/8" o.d. iron pin found (no cap);
- 2) N 86°26'07" W 336.33 feet, to a 3/4" o.d. iron pin found (no cap) found in the centerline of Scout Road (Twp. Road 350)(40' Wide);

Thence, N 58°17'00" W 73.20 feet with the East line of said parcel conveyed to Goss & Bush, to a 3/4" o.d. iron pin found (no cap) in the centerline of Scout Road;

Thence, N 03°38'52" E 620.62 feet leaving Scout Road with the East line of said parcel conveyed to Goss & Bush, to the **PRINCIPLE PLACE OF BEGINNING**, containing 5.555 Acres, more or less, and is subject to the 40 foot Right of Way of Scout Road (Twp. Road 350), and all legal easements, right of ways, restrictions, and zoning ordinances of record.

The bearings of the above description are based on the North line of Section 17, as being S 86°16'59" E, and is based using the O.D.O.T. CORS Network System, Ohio State Plane Coordinates South Zone. 2011(NAD83)

All iron pins set are 5/8" reinforcing bars 30" long with red 1.25" dia. plastic caps labeled "S.A. ENGLAND #7452".

The above description was prepared by S.A. England Surveying, under the direct supervision of Scott A. England, Ohio Registered Surveyor #S-7452 in December of 2022.

Dated 1/31/23

Scott A. England P.S.
Ohio Registered Surveyor #7452

Job No. 4065-22HO

APPROVED MATHEMATICALLY
Hocking County Engineer's Office
By: Date: 02/01/2023



Filed Hocking County Auditor's Office

Frank Nelson February 03, 2023

Plat of Survey

Township of Green, County of Hocking, State of Ohio, part Fractional Lot 6 in Section 17, Township 13N, Range 16W.

PROPERTY LOCATION:

Being a Survey of a part of an 8.2777 Acre parcel conveyed to Sarah M. Harkless, as recorded in O.R. Book 449, Page 166, in the Hocking County Deed Records, and being part of Auditor's P.P.N. 060002560200.

BASIS OF BEARING

The bearings of this plat are based on the North line of Section 17, as being S 86°16'59" E, and is based on the O.D.O.T. CORS Network System, Ohio State Plane Coordinates South Zone, 2011(NAD83).

Prepared For:
Sarah Harkless



P.O.C.: Northwest Corner
Northeast Quarter
Section 17

LEGEND

- △ - Railroad Spike Found
- Mag Nail Set
- - 5/8" o.d. Iron Pin Found
w/ 1.25" dia. yellow cap labeled "LPG-6344"
- ⊕ - Iron Pin Set
5/8" Rebar 30" long w/ 1.25" dia. red cap Labeled S.A. England #7452
- ⊕ - 2.5" o.d. Iron Pipe Found
- ▲ - 3/4" o.d. Iron Pin Found (NO CAP)

- - Property line
- - Road R/W Line

RELATED DOCUMENTS

- 1) 1999 Survey of 2.043 Acres by Larry P. Gerstner, P.S. 6344
- 2) 1989 Survey of 5.89 Acres by T. Chris Wilson, P.S. 6465
- 3) 1953 Survey of 5.9757 Acres by A.W. Seabright, P.E., P.S.

5.555 Acres Surveyed


APPROVED MATHEMATICALLY
Hocking County Engineer's Office
By SAE Date: MO. 02.15.2023

**As Revised*

I hereby certify that an actual survey of the premises was made on December 23, 2022, and that this plat is correct to the best of my knowledge.

Dated 2/18/23

Scott A. England, P.S.
Ohio Registered Surveyor #7452



PREPARED BY:
S.A. ENGLAND SURVEYING
Professional Land Surveying
P.O. Box 1770
Buckeye Lake, Ohio 43008
PHONE: 740-323-0644
email: saengland@surveyohio.com



S.A. ENGLAND SURVEYING

Professional Land Surveying
P.O. Box 1770
Buckeye Lake, Ohio 43008



E-mail: www.surveyohio.com

Phone: 740-323-0644

Fax: 740-323-0272

Ohio Phone: 1-800-551-5844

Legal Description

5.555 Acres

Part Sarah M. Harkless Parcel: O.R. 449, Page 166

Situated in the Township of Green, County of Hocking, State of Ohio, and being a part of Fractional Lot 6 in Section 17, Township 13N, Range 16W, and being more particularly described as follows;

Being a Survey of a part of an 8.2777 Acre parcel conveyed to Sarah M. Harkless, as recorded in O.R. 449, Page 166, in the Hocking in the Hocking County Deed Records, being part of Auditor's P.P.N. 060002560200, and further described as follows;

Commencing at a railroad spike found marking the Northwest corner of the Northeast Quarter of Section 17;

Thence, S 86°16'59" E 543.05 feet with the North line of Section 17, the same being the South line of Section 18, to a 5/8" o.d. iron pin found w/1.25" yellow cap stamped "LPG-6344" marking the Northwest corner of a 2.043 Acre parcel conveyed to Sarah M. Harkless, as recorded in O.R. 449, Page 166, and being the Northeast corner of a 94.9802 Acre parcel conveyed to Christopher Goss & Carol Bush, as recorded in O.R. 12, Page 759;

Thence, S 03°38'52" W 441.62 feet with the West line of said 2.043 Acre parcel conveyed to Harkless, the same being the East line of said parcel conveyed to Goss & Bush, to a 2.5" o.d. iron pipe found, being the **PRINCIPLE PLACE OF BEGINNING** of the 5.555 Acre parcel herein to be described, and passing over a 5/8" o.d. iron pin found w/1.25" yellow cap stamped "LPG-6344 at 20.00 feet;

Thence, S 85°54'57" E 201.24 feet with the South line of said 2.043 Acre parcel conveyed to Harkless, to an iron pin set on the boundary of said 8.2777 Acre parcel of which this description is a part;

Thence, S 41°33'29" E 286.47 feet with a line across said 8.2777 Acre parcel, of which this description is a part, to an iron pin set on the East line thereof, and being the Northwest corner of a 5.89 Acre parcel conveyed to Alan R. Holley & Stewart C. Holley, as recorded in O.R. 544, Page 121;

Thence with the boundary of said parcel conveyed to Holley & Holley, with the following two (2) courses and distances:

- 1) S 04°06'15" W 451.22 feet to a 5/8" o.d. iron pin found (no cap);
- 2) N 86°26'07" W 336.33 feet, to a 3/4" o.d. iron pin found (no cap) found in the centerline of Scout Road (Twp. Road 350)(40' Wide);

Thence, N 58°17'00" W 73.20 feet with the East line of said parcel conveyed to Goss & Bush, to a 3/4" o.d. iron pin found (no cap) in the centerline of Scout Road;

Thence, N 03°38'52" E 620.62 feet leaving Scout Road with the East line of said parcel conveyed to Goss & Bush, to the **PRINCIPLE PLACE OF BEGINNING**, containing 5.555 Acres, more or less, and is subject to the 40 foot Right of Way of Scout Road (Twp. Road 350), and all legal easements, right of ways, restrictions, and zoning ordinances of record.

The bearings of the above description are based on the North line of Section 17, as being S 86°16'59" E, and is based using the O.D.O.T. CORS Network System, Ohio State Plane Coordinates South Zone. 2011(NAD83)

All iron pins set are 5/8" reinforcing bars 30" long with red 1.25" dia. plastic caps labeled "S.A. ENGLAND #7452".

The above description was prepared by S.A. England Surveying, under the direct supervision of Scott A. England, Ohio Registered Surveyor #S-7452 in December of 2022.

Dated 2/8/23
Job No. 4066-22HO


Scott A. England P.S.
Ohio Registered Surveyor #7452

APPROVED MATHEMATICALLY
Hocking County Engineer's Office
By  Date: MO2.D.15.Y.2023

** As Revised*



Plat of Survey

Township of Green, County of Hocking, State of Ohio, part Fractional Lot 6 in Section 17, Township 13N, Range 16W, Ohio Company Purchase.

LEGEND

- △ - Railroad Spike Found
- ▲ - 3/4" o.d. Iron Pipe Found (no cap)
- - 5/8" o.d. Iron Pin Found w/ 1.25" dia. yellow cap labeled "Seymore Assoc"
- ⊕ - Iron Pin Set 5/8" Rebar 30" long w/ 1.25" dia. red cap Labeled S.A. England #7452
- ⊕ - 5/8" o.d. Iron Pin Found (NO CAP)
- - point

— Property line
 - - - - - Road R/W Line

LINE TABLE

No.	Bearing	Distance
L1	S 22°51'10" E	130.64'
L2	N 68°00'04" E	50.64'
L3	N 66°19'09" E	127.86'
L4	N 07°08'32" E	44.55'
L5	S 76°11'32" E	50.07'
L6	N 83°48'05" E	52.39'
L7	N 86°42'58" E	60.21'
L8	S 77°46'43" E	43.65'
L9	S 58°17'00" E	73.20'
L10	S 37°02'03" E	46.31'

Filed Hocking County Auditor's Office
Frank Nelson **May 23, 2023**



APPROVED MATHEMATICALLY
 Hocking County Engineer's Office
 By: [Signature] Date: 05/18/2023



I hereby certify that an actual survey of the premises was made on February 1, 2023, and that this plat is correct to the best of my knowledge.

Dated 5/17/23

[Signature]
 Scott A. England, P.S.
 Ohio Registered Surveyor #7452

12.433 Acres Surveyed
 (11.967 Acres excluding road R/W)
 Christopher Goss & Carol Bush
 94.9802 Acres
 O.R. 12, Page 759
 P.P.N. 060002540000
 Property is currently vacant

- #### RELATED DOCUMENTS
- 1) 1999 Survey of 2.043 Acres by Larry P. Gerstner, P.S. 6344
 - 2) 1989 Survey of 5.89 Acres by T. Chris Wilson, P.S. 6465
 - 3) 1953 Survey of 5.9757 Acres by A.W. Seabright, P.E., P.S.
 - 4) 2023 Survey of 5.555 Acres by Scott A. England, P.S. 7452



PROPERTY LOCATION:
 Being a Survey of a part of a 94.97 Acre parcel conveyed to Christopher Goss & Carol Bush, as recorded in O.R. 12, Page 759, in the Hocking County Deed Records, and being part of Auditor's P.P.N. 060002540000.

BASIS OF BEARING
 The bearings of this plat are based on the North line of Section 17, as being S 86°16'59" E, and is based on the O.D.O.T. CORS Network System, Ohio State Plane Coordinates South Zone, 2011(NAD83).

Fenceline and occupation generally agrees with boundary lines shown hereon unless otherwise shown.
 ** (60' Wide R/W)(Com. Jrnl. Bk A-206

Dale F. & Angela S. Bowman
 2.000 Acres
 O.R. 681, Page 979
 T.O.D.: O.R. 684, Page 91


William M. Lemon
 36 Acres
 O.R. 720, Page 278
 O.R. 434, Page 196

Donald & Kathleen Keeney
 6.55 Acres
 O.R. 214, Page 444

Jacqueline Hunter
 7.86 Acres
 O.R. 53, Page 329

David & Claudette Roush
 8.93 Acres
 O.R. 508, Page 397

PREPARED BY:
S.A. ENGLAND SURVEYING
 Professional Land Surveying
 P.O. Box 1770
 Buckeye Lake, Ohio 43008
 PHONE: 740-323-0644
 email: saengland@surveyohio.com



S.A. ENGLAND SURVEYING

Professional Land Surveying
P.O. Box 1770
Buckeye Lake, Ohio 43008



E-mail: www.surveyohio.com

Phone: 740-323-0644

Fax: 740-323-0272

Ohio Phone: 1-800-551-5844

Legal Description 12.433 Acres

Situated in the Township of Green, County of Hocking, State of Ohio, and being a part of Fractional Lot 6 in Section 17, Township 13N, Range 16W, of the Ohio Company Purchase, and being more particularly described as follows;

Being a Survey of a part of a 94.9802 Acre parcel conveyed to Christopher Goss & Carol Bush, as recorded in O.R. 12, Page 759, in the Hocking in the Hocking County Deed Records, being part of Auditor's P.P.N. 060002540000, and further described as follows;

Commencing at a railroad spike found marking the Northwest corner of the Northeast Quarter of Section 17, and in Maysville-Greendale Road (60' Wide R/W)(Commissioners Journal Book A, Page 206);

Thence, S 86°16'59" E 543.05 feet with the North line of Section 17, the same being the South line of Section 18, to a 5/8" o.d. iron pin found marking the Northwest corner of a 2.043 Acre parcel conveyed to Sarah M. Harkless, as recorded in O.R. 449, Page 166, and being the Northeast corner of said parcel conveyed to Goss & Bush, of which this description is a part;

Thence, S 03°38'52" W 1062.24 feet with the West line of said parcel conveyed to Harkless, the same being the East line of said parcel conveyed to Goss & Bush, to a 3/4" o.d. iron pipe found in the centerline of Scout Road (Twp. Road 350)(40' Wide R/W), and being the **PRINCIPLE PLACE OF BEGINNING** of the **12.433 Acre** parcel herein to be described;

Thence with the centerline of Scout Road, with the following four (4) courses and distances:

- 1) S 58°17'00" E 73.20 feet to a 3/4" o.d. iron pin found (no cap);
- 2) S 37°02'03" E 46.31 feet to a point;
- 3) S 20°07'11" E 172.22 feet to a point;
- 4) S 20°21'21" E 516.82 feet to a point;

Thence leaving Scout Road with a line across said parcel conveyed to Goss & Bush, with the following three (3) courses and distances:

- 5) N 80°19'11" W 1027.75 feet to an iron pin set, and passing over an iron pin set at 25.00 feet;
- 6) N 09°28'59" W 442.80 feet to an iron pin set;
- 7) N 68°40'06" E 357.60 feet to a 5/8" o.d. iron pin found w/1.25" dia. yellow cap stamped "Seymore-Assoc" marking the Northwest corner of a parcel conveyed to Dean Lindsay Sutton, Jr., as recorded in O.R. 544, Page 121;

Thence with the boundary of said parcel conveyed to Sutton, with the following four (4) courses and distances:

- 8) S 22°51'10" E 130.64 feet to a 5/8" o.d. iron pin found w/1.25" dia. yellow cap stamped "Seymore-Assoc";
- 9) N 68°00'04" E 50.64 feet to a 5/8" o.d. iron pin found w/1.25" dia. yellow cap stamped "Seymore-Assoc";
- 10) N 66°19'09" E 127.86 feet to a 5/8" o.d. iron pin found w/1.25" dia. yellow cap stamped "Seymore-Assoc";
- 11) N 07°08'32" E 44.55 feet to a railroad spike found in the centerline of Scout Road;

Thence with the centerline of Scout Road, with the following four (4) courses and distances:

- 12) S 76°11'32" E 50.07 feet to a point;
- 13) N 83°48'05" E 52.39 feet to a point;
- 14) N 86°42'58" E 60.21 feet to a point;
- 15) S 77°46'43" E 43.65 feet to the **PRINCIPLE PLACE OF BEGINNING.**

Said parcel as surveyed contains **12.433 Acres**, more or less, and is subject to the 40 foot Right of Way of Scout Road (Twp. Road 350), and all legal easements, right of ways, restrictions, and zoning ordinances of record.


The bearings of the above description are based on the North line of Section 17, as being S 86°16'59" E, and is based using the O.D.O.T. CORS Network System, Ohio State Plane Coordinates South Zone. 2011(NAD83)

All iron pins set are 5/8" reinforcing bars 30" long with red 1.25" dia. plastic caps labeled "S.A. ENGLAND #7452".

The above description was prepared by S.A. England Surveying, under the direct supervision of Scott A. England, Ohio Registered Surveyor #S-7452 in December of 2022.

Dated 5/17/23

Job No. 4089-23 HO


Scott A. England P.S.
Ohio Registered Surveyor #7452



Filed Hocking County Auditor's Office
Frank Nelson **May 23, 2023**

APPROVED MATHEMATICALLY
Hocking County Engineer's Office
By  Date: MAY 18 2023