

14

DESCRIPTION
LUTZ - 2.014 ACRES

Situated in the Township of Laurel, County of Hocking, State of Ohio and being a part of the southwest quarter of Section 14, Town 12, Range 18, bounded and described as follows:

Commencing at a stone in the south line of Section 14, said stone being South $86^{\circ}03'31''$ East 1475.86 feet from the Southwest corner of Section 14; thence North $2^{\circ}05'30''$ East 1337.01 feet to an iron pin, said iron pin being the place of beginning for the tract of land herein described; thence North $86^{\circ}29'$ West 312.25 feet to an iron pin; thence North $20^{\circ}25'$ East 430.93 feet to a point in Township Road 232, passing an iron pin at 397.18 feet; thence with said Township Road South $47^{\circ}07'$ E 233.34 feet to an iron pin; thence leaving said Township Road South $2^{\circ}05'30''$ West 264.40 feet to the place of beginning and containing 2.014 acres more or less subject to the right of way of Township Road 232.

Prepared by: William M. Watkins
Registered Surveyor #5216

APPROVED
HOCKING COUNTY
ENGINEERS OFFICE
LOGAN, OHIO 43138

DEC 26 1973

J.E.

Laurel 14

DESCRIPTION OF A 0.56 ACRE PARCEL OF LAND SITUATED IN THE SOUTHEAST QUARTER OF THE SOUTH WEST QUARTER OF SECTION 14, TOWNSHIP 12, RANGE 18, LAUREL TOWNSHIP, HOCKING COUNTY, OHIO AND BEING MORE ACCURATELY DESCRIBED AS FOLLOWS:

BEGINNING AT A STONE IN THE SOUTHWEST CORNER OF THE SOUTHEAST QUARTER OF THE SOUTHWEST QUARTER OF SECTION 14; THENCE NORTH 4-57 EAST A DISTANCE OF 1329.25^b FEET TO A POINT; THENCE SOUTH 84-00 EAST A DISTANCE OF 303.81 FEET TO A SPIKE IN THE CENTERLINE OF TOWNSHIP ROAD 232; ^{THE TRUE PLACE OF BEGINNING OF THE TRAIL HEREIN OCCUPIED} THENCE SOUTH 84-00 EAST A DISTANCE OF 385.52 FEET TO AN IRON PIN; THENCE SOUTH 49-45 WEST A DISTANCE OF 51.48 FEET TO A SPIKE IN THE CENTERLINE OF TOWNSHIP ROAD 232; THENCE WITH THE CENTERLINE OF SAID ROAD THE FOLLOWING FOUR (4) COURSES AND DISTANCES :

- (1) THENCE SOUTH 50-48 WEST A DISTANCE OF 92.28 FEET TO A SPIKE,
- (2) THENCE SOUTH 79-13 WEST A DISTANCE OF 39.50 FEET TO A SPIKE,
- (3) THENCE NORTH 66-32 WEST A DISTANCE OF 58.58 FEET TO A SPIKE,
- (4) THENCE NORTH 57-13 WEST A DISTANCE OF 214.19 FEET TO A SPIKE, THE TRUE PLACE OF BEGINNING AND CONTAINING 0.56 ACRES OF LAND SUBJECT TO ALL EASEMENTS AND RIGHT-OF-WAYS OF RECORD.

APPROVED
HOCKING COUNTY ENGINEER'S OFFICE
DATE 10-13-76
BY [Signature]

Prepared 10-08-76
W. Wayne Porter
P.S. - 5465

14

DESCRIPTION - LUTZ TO WILKINS

Situated in the Township of Laurel, County of Hocking,
State of Ohio and being a part of the Southwest quarter of Section
14, Township 12, Range 18 bounded and described as follows:

Beginning at a point in County Road 9, said point being
in the West line of Section 14, North $3^{\circ}40'$ East 334.60 feet from the
southwest corner of Section 14; thence with said road and West line
of the Section North $3^{\circ}40'$ East 30.00 feet to a point; thence leaving
said road South $87^{\circ}19'$ East 103.20 feet to an iron pin; thence South
 $0^{\circ}30'$ West 30.00 feet to an iron pin; thence North $87^{\circ}19'$ West 104.84
feet to the place of beginning, passing an iron pin at 88.84 feet and
containing 0.0716 acres more or less, subject to the right of way of
County Road 9.

Description by: William M. Wilkins
Registered Surveyor #5216

APPROVED
HOCKING COUNTY
ENGINEERS OFFICE
LOGAN, OHIO 43138

DEC 26 1973

J.E

LAUREL 14

PLAT OF A 20.000 ACRE TRACT FOR MARTIN AND GAIL LOHN

20.00 AC.


Situated in Laurel Township, Hocking County, Ohio; being part of the Northeast quarter of the Southwest quarter of Section 14, Township 12, Range 18.

Hocking County Engineer's Office

Chloe Heller
145-369 & 151-467

DATE 12-22-00

Northwest corner of
the Northeast quarter
of the Southwest
quarter of Section 14
Point of Beginning



SCALE:
1" = 300'

James II & Linda Lutz
OR95-814

S88°57'48"E- 720.77'

N0°29'03"W- 1065.45' TOTAL

1034.40'

Martin R. and Gail
Lohn
OR8-925
20.000 Acres

S1°30'44"W- 1057.11'

REFERENCES:

- Tax maps
- Deed descriptions
- Previous surveys
- Existing monumentation
- Existing public road

Center of
Township Road 232,
Rocky Fork Road

LEGEND

- 5/8" iron pin with 1-1/4" plastic ID cap stamped 6803 found
- 5/8"x 30" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 set
- ▲ MAG nail set
- ⊙ 1" OD iron pipe found (damaged)
- ⊗ 1/4" iron pin found
- ⊙ 1/2" iron pin found

Ronald & Darla Murdock
153-85


N0°05'40"W
264.29' TOTAL

31.05'
16.11'

248.18'
260.07'

S88°53'01"W
289.43' TOTAL

459.31'
S57°09'32"W
468.88' TOTAL



Center of
Township Road 232,
Rocky Fork Road

Paul Beach
159-658 & OR96-133

REFERENCE BEARING:

East line of the Northeast quarter of the Southwest quarter of Section 14 as South 0 degrees 00 minutes 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only.

CERTIFICATION:

I hereby certify that an actual survey was made under my supervision of the premises shown hereon on the 18th day of December, 2000 and that the plat is a correct representation of the premises as described by said survey.

Larry P. Gerstner
Registered Surveyor No. 6344

Survey by:

Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138
(740) 385-4260

SURVEY DESCRIPTION OF A 20.000 ACRE TRACT FOR MARTIN AND GAIL LOHN

Situated in Laurel Township, Hocking County, Ohio; being part of the Northeast quarter of the Southwest quarter of Section 14, Township 12, Range 18; and being more particularly described as follows:

Beginning at a 5/8" iron pin with 1-1/4" plastic ID cap stamped 6803 found at the Northwest corner of the Northeast quarter of the Southwest quarter of Section 14; thence South 88 degrees 57 minutes 48 seconds East a distance of 720.77 feet to a damaged 1" OD iron pipe found;

thence South 1 degree 30 minutes 44 seconds West a distance of 1057.11 feet to a 5/8" iron pin set;

thence South 57 degrees 09 minutes 32 seconds West a distance of 468.88 feet to a MAG nail set in the edge of Township Road 232, Rocky Fork Road, and passing a 5/8" iron pin set at a distance of 459.31 feet;

thence leaving the center of said Township Road 232 South 88 degrees 53 minutes 01 second West a distance of 289.43 feet to a 1/2" iron pin found and passing a 5/8" iron pin set at a distance of 29.36 feet;

thence North 0 degrees 05 minutes 40 seconds West a distance of 264.29 feet to a 1/4" iron pin found in the center of said Township Road 232 and passing a 5/8" iron pin set at a distance of 248.18 feet;

thence leaving the center of said Township Road 232 North 0 degrees 29 minutes 03 seconds West a distance of 1065.45 feet to the point of beginning, passing a 5/8" iron pin set at a distance of 31.05 feet, containing 20.000 acres more or less, and subject to the public easement of said Township Road 232 and any other public or private easements of record.

The above 20.000 acre survey is intended to describe part of the 40 acre Tract One as deeded to Martin R. And Gail Lohn, deed reference Volume OR8, Page 925, Hocking County Recorder's Office. This survey was based upon information obtained from tax maps, deed descriptions, previous surveys, existing monumentation, and an existing public road. The reference bearing for this survey is the East line of the Northeast quarter of the Southwest quarter of Section 14 as South 0 degrees 00 minutes 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only. All iron pins set by this survey are 5/8" by 30" and are capped by a 1-1/4" plastic identification cap stamped LPG-6344. The above described property was surveyed by Larry P. Gerstner, Ohio Registered Surveyor No. 6344, on December 18, 2000.

Surveyed - Mathematically
Hocking County Engineer's Office

LP Gerstner DATE 12-22-00

Larry P. Gerstner



Survey by:


Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138 385-4260

LAUREL 14

CENTERLINE SURVEY PLAT OF A 60 FEET WIDE BY 445.08 FEET LONG
SHARED EASEMENT OF INGRESS AND EGRESS FOR MARTIN AND GAIL LOHN

Situated in Laurel Township, Hocking County, Ohio; being part of the Northeast quarter of the Southwest quarter of Section 14, Township 12, Range 18; being a 60 feet wide by 445.08 feet long centerline shared easement of ingress and egress.

EASEMENT
NE 3/4 PT



Northwest corner of the Northeast quarter of the Southwest quarter of Section 14

Martin R. and Gail Lohn
OR8-925

- REFERENCES:
- Tax maps
 - Deed descriptions
 - Previous surveys
 - Existing monumentation
 - Existing public road


LEGEND

- 5/8" iron pin with 1-1/4" plastic ID cap stamped 6803 found
- ▲ MAG nail set
- ⊗ 1/4" iron pin found
- 5/8" iron pin previously set

Center of Township Road 232, Rocky Fork Road

60' x 445.08' centerline shared easement of ingress and egress
Point of Beginning

Prepared Mathematically - Easement Only
Hocking County Engineer's Office



Center of Township Road 232, Rocky Fork Road

REFERENCE BEARING:

East line of the Northeast quarter of the Southwest quarter of Section 14 as South 0 degrees 00 minutes 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only.


CERTIFICATION:

I hereby certify that an actual survey was made under my supervision of the premises shown hereon on the 25th day of January, 2001 and that the plat is a correct representation of the premises as described by said survey.

Larry P. Gerstner
Registered Surveyor No. 6344

Survey by:

Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138
(740) 385-4260



CENTERLINE SURVEY DESCRIPTION OF A 60 FEET WIDE BY 445.08 FEET LONG

SHARED EASEMENT OF INGRESS AND EGRESS FOR MARTIN AND GAIL LOHN

Situated in Laurel Township, Hocking County, Ohio; being part of the Northeast quarter of the Southwest quarter of Section 14, Township 12, Range 18; being a 60 feet wide by 445.08 feet long centerline shared easement of ingress and egress; and being more particularly described as follows:

Commencing for reference at a 5/8" iron pin with 1-1/4" plastic ID cap stamped 6803 found at the Northwest corner of the Northeast quarter of the Southwest quarter of Section 14; thence South 0 degrees 29 minutes 03 seconds East a distance of 1065.45 feet to a 1/4" iron pin found in the center of Township Road 232, Rocky Fork Road, and passing a 5/8" iron pin previously set at a distance of 1034.40 feet;

thence with the center of said Township Road 232 South 43 degrees 14 minutes 55 second East a distance of 102.24 feet to a MAG nail set in the intersection of a private driveway and being the point of **Beginning** of the centerline easement of ingress and egress to be described;

thence leaving the center of said Township Road 232 and with the center of an existing private driveway the following eight bearings and distances:

- 1) North 2 degrees 59 minutes 17 seconds West a distance of 98.30 feet to a MAG nail set;
- 2) North 11 degrees 32 minutes 27 seconds West a distance of 81.08 feet to a MAG nail set;
- 3) North 8 degrees 23 minutes 57 seconds East a distance of 39.34 feet to a MAG nail set;
- 4) North 24 degrees 49 minutes 45 seconds East a distance of 47.96 feet to a MAG nails et;
- 5) North 50 degrees 17 minutes 11 seconds East a distance of 52.99 feet to a MAG nail set;
- 6) North 85 degrees 45 minutes 52 seconds East a distance of 38.45 feet to a MAG nail set;
- 7) North 66 degrees 33 minutes 36 seconds East a distance of 62.43 feet to a MAG nail set;
- 8) North 82 degrees 24 minutes 56 seconds East a distance of 24.53 feet to a MAG nail set and being the end of a 60 feet wide by 445.08 feet long centerline shared easement of ingress an egress, and subject to the public easement of said Township Road 232 and any other public or private easements of record.

The above surveyed centerline shared easement of ingress and egress is intended to describe part of the 40 acre Tract One as deeded to Martin R. and Gail Lohn, deed reference Volume OR8, Page 925, Hocking County Recorder's Office. This survey was based upon information obtained from tax maps, deed descriptions, previous surveys, existing monumentation, and an existing public road. The reference bearing for this survey is the East line of the Northeast quarter of the Southwest quarter of Section 14 as South 0 degrees 00 minutes 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only. All iron pins set by this survey or previously set are 5/8" by 30" and are capped by a 1-1/4" plastic identification cap stamped LPG-6344. The above described property was surveyed by Larry P. Gerstner, Ohio Registered Surveyor No. 6344, on January 25, 2001.



Easement only
Hocking County Engineer's Office.

Jy Ger DATE 2-5-01

Larry P. Gerstner

Survey by:

Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138 385-4260

Approved - Mathematically
Hocking County Engineer's Office

BY JA DATE 2-19-99

SUBDIVISION REGULATIONS WAIVED
PENDING HEALTH DEPT. APPROVAL

BY JA DATE 2-19-99

APPROVED
LOGAN-HOCKING COUNTY
HEALTH DEPT.

Date 11 Mar 99 mjm

REAL ESTATE DESCRIPTION WORKSHEET

FROM: RALPH COKONOUGH

TO: DANNY AND AMELIA CALHOUN

The following real estate situated in the County of Hocking in the State of Ohio, and in the Township of Laurel and bounded and described as follows:

Being part of a 24.83 acre tract, D.V. 215, page 594 and O.R. 132, page 792 in the East half of the Northeast quarter of Section 14, T12, R18, Congress Lands, and being more particularly described as follows;

Beginning for reference at an iron pipe found, said iron pipe marking the Northwest corner of the East half of the Northeast quarter of Section 14;

thence South 84 degrees 58 minutes 00 seconds East 300.77 feet in the North line of said Section 14 to an iron pipe found;

thence South 07 degrees 02 minutes 48 seconds West 755.99 feet leaving said Section 14 line To a 5/8" rebar set with plastic I.D. cap, said rebar marking the principal place of beginning of the Tract herein to be described;

thence continuing South 07 degrees 02 minutes 48 seconds West 571.31 feet to a P.K. nail set in the centerline of County Road 4, passing an iron pipe found at 544.50 feet;

thence North 59 degrees 08 minutes 00 seconds East 355.00 feet in the centerline of said County Road 4 to a P.K. nail set;

thence North 31 degrees 22 minutes 06 seconds West 450.75 feet leaving the centerline of said County Road 4 to the principal place of beginning, passing a 5/8" rebar set with plastic I.D. cap at 37.00 feet, containing 1.836 acres.

Bearings used for this survey were from a previous survey by J. A. Mathias, May 1980.

This description was prepared by from an actual survey performed by James R. Cartwright, Ohio Registered Surveyor No. 7486.

James R. Cartwright 2-3-99
JAMES R. CARTWRIGHT DATE
OHIO REGISTERED SURVEYOR #7486

Seymour-Shaw & Associates, Inc.

Consulting Engineers & Surveyors



WILLIAM R. SHAW, P.E., P.S.
GEORGE F. SEYMOUR, P.S.

PHONE
614 - 385-4349

615 WALHONDING AVE.
LOGAN, OHIO 43138

ECTOR WERNET 177-348
GARY & SARA GAHM 141-023

BEING A PART OF SECTIONS 14 & 15,
T-12, R-18, LAUREL TOWNSHIP,
HOCKING COUNTY, OHIO



- = IRON PIN FROM PREVIOUS SURVEY
- = 5/8" IRON PIN W/I.D. CAP SET

BEARINGS MEASURED FROM PREVIOUS SURVEY AND ARE FOR THE DETERMINATION OF ANGLES ONLY.

REFERENCES:
PREVIOUS SURVEYS
TAX MAPS
DEEDS AS NOTED

Approved - Mathematically
Hocking County Engineer's office
By R. J. [Signature] Date 1-28-83

22.64 ACRES SEC. 15
0.24 ACRES SEC. 14

22.88 ACRES TOTAL

HALF SECTION LINE
WEST
SE CORNER OF
NE QUARTER OF
SECTION 15, T-12, R-18



I hereby certify that an actual survey was made under my supervision of the premises shown hereon on the 24 day of JANUARY, 1983; and that the plat is a correct representation of the premises as determined by said survey. I further certify that there are no encroachments either way across any boundary line except as shown hereon.

George F. Seymour

Seymour-Shaw & Associates, Inc.

Consulting Engineers & Surveyors

WILLIAM R. SHAW, P.E., P.S.
GEORGE F. SEYMOUR, P.S.

PHONE
614 - 385-4349

615 WALHONDING AVE.
LOGAN, OHIO 43138

Description of Survey for Ronald McGrady

Being a part of the tract of land transferred to Ronald McGrady as recorded in Deed Book 164 at page 637, Hocking County Recorder's Office, said tract being situated in Section 15 and the northwest quarter of Section 14, T12N, R18W, Laurel Township, Hocking County, State of Ohio, and more particularly described as follows:

Beginning at an iron pin found on the southeast corner of the northeast quarter of Section 15, T12N, R18W;

Thence using bearings derived from previous surveys with the east line of Section 15, South $1^{\circ} 14'$ West a distance of ~~584.83~~^{584.83} feet to a point from which an iron pin found on the southeast corner of the 44.6258 acre tract recorded in Deed Book 164 at page 637 bears South $1^{\circ} 14'$ West a distance of 70.88 feet;

Thence leaving the east line of Section 15, North $53^{\circ} 27' 43''$ West, passing through a $5/8$ " iron pin with a 2" aluminum identification cap set at 1837.40 feet, going a total distance of 1888.64 feet to a point in the center of County Road 4;

Thence with the center of said road, North $12^{\circ} 08'$ East a distance of 24.98 feet to a point;

Thence continuing with the center of said road, North $55^{\circ} 02'$ East a distance of 283.02 feet to an iron pin found;

Thence leaving the center of said road and with the southwesterly line of a 4.81 acre tract recorded in Deed Book 160 at page 118, South $41^{\circ} 29'$ East a distance of 389.46 feet to an iron pin found;

Thence with the southeasterly line of said 4.81 acre tract, North $50^{\circ} 42' 06''$ East a distance of 719.63 feet to an iron pin found on the southerly line of an 18.38 acre tract recorded in Deed Book 170 at page 557;

Thence with the southerly line of said 18.38 acre tract the following 2 courses:

- (1) South $37^{\circ} 29'$ East a distance of 827.28 feet to an iron pin found,
- (2) South $9^{\circ} 36'$ East a distance of 237.21 feet to an iron pin found on the south line of the northwest quarter of Section 14;

Thence with said south line, West a distance of 65.00 feet to the place of beginning, containing .24 acre in Section 14 and 22.64 acres in Section 15 making a total of 22.88 acres, more or less, subject to the right of way of County Road 4.

The above description was prepared from a survey made under my supervision, George F. Seymour, Ohio Registered Surveyor No. 6044, January 24, 1983, and from previous surveys of record.

Approved - Mathematically
Hocking County Engineer's office
By R. H. J. J. Date 1-28-83

George F. Seymour

SURVEY DESCRIPTION OF A 12.815 ACRE TRACT FOR MARTIN AND GAIL LOHN

Situated in Laurel Township, Hocking County, Ohio; being part of the Northeast quarter of the Southwest quarter of Section 14, Township 12, Range 18; and being more particularly described as follows:

Beginning at a 5/8" iron pin with 1-1/4" plastic ID cap stamped 6803 found at the Northwest corner of the Northeast quarter of the Southwest quarter of Section 14; thence South 88 degrees 57 minutes 48 seconds East a distance of 720.77 feet to a damaged 1" OD iron pipe found;

thence South 1 degree 30 minutes 44 seconds West a distance of 345.86 feet to a 5/8" iron pin previously set;

thence South 52 degrees 25 minutes 38 seconds West a distance of 365.58 feet to a 5/8" iron pin set;

thence South 37 degrees 15 minutes 12 seconds West a distance of 302.33 feet to a 5/8" iron pin set and passing a MAG nail set in the center of a private driveway at a distance of 293.19 feet;

thence South 8 degrees 59 minutes 57 seconds West a distance of 411.19 feet to a MAG nail set in the center of Township Road 232, Rocky Fork Road, and passing a 5/8" iron pin set at a distance of 390.46 feet;

thence with the center of said Township Road 232 South 52 degrees 27 minutes 07 seconds East a distance of 156.86 feet to a MAG nail previously set on the North edge of said Township Road 232;

thence leaving said Township Road 232 South 88 degrees 53 minutes 01 second West a distance of 289.43 feet to a 1/2" iron pin found and passing a 5/8" iron pin previously set at a distance of 29.36 feet;

thence North 0 degrees 05 minutes 40 seconds West a distance of 264.29 feet to a 1/4" iron pin found in the center of said Township Road 232 and passing a 5/8" iron pin previously set at a distance of 248.18 feet;

thence leaving the center of said Township Road 232 North 0 degrees 29 minutes 03 seconds West a distance of 1065.45 feet to the point of beginning, passing a 5/8" iron pin previously set at a distance of 31.05 feet, containing 12.815 acres more or less, and subject to the public easement of said Township Road 232 and any other public or private easements of record.

The above 12.815 acre survey is intended to describe part of the 40 acre Tract One as deeded to Martin R. and Gail Lohn, deed reference Volume OR8, Page 925, Hocking County Recorder's Office. This survey was based upon information obtained from tax maps, deed descriptions, previous surveys, existing monumentation, and an existing public road. The reference bearing for this survey is the East line of the Northeast quarter of the Southwest quarter of Section 14 as South 0 degrees 00 minutes 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only. All iron pins set by this survey or previously set are 5/8" by 30" and are capped by a 1-1/4" plastic identification cap stamped LPG-6344. The above described property was surveyed by Larry P. Gerstner, Ohio Registered Surveyor No. 6344, on January 25, 2001.



Surveyor's Office
2-6-01
Larry P. Gerstner

Survey by:

Larry P. Gerstner, + Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138 385-4260

BEING A PART OF THE S¹/₄ OF SEC. 1A,
LAUREL TWP., T-12N, R-18W, HOCKING CO., OHIO

NOTE: GIVEN BEARINGS ARE BASED ON THE BEARING SYSTEM OF THE
11.8452 AC. TRACT DESCRIBED IN O.R. VOL. 90, PG. 610.



C. V. MELLER
VOL. 145, PG. 369

N.E. COR. 11.8452 AC. TRACT,
O.R. VOL. 90, PG. 610

6.0766 ACRES
(PT. OF O.R. VOL. 54, PG. 274,
& O.R. VOL. 56, PG. 178)

M. G. LOMAN
O.R. 8, PG. 925

D. E. NEWBY
O.R. 90, PG. 610



- = 5/8" x 30" IRON PENCILS
W/ 3D CAP
- ⊕ = 5/8" x 30" IRON PEN (SEV.
SET) W/ 3D CAP
- = IRON PEN (FD.)

REFERENCES:
COUNTY TAX PLATS
SURVEYS OF RECORD
DEEDS (AS AWIRED)

A. E. S. WATKINS
O.R. 54, PG. 274
O.R. 56, PG. 178

R. E. D. MURDOCK
VOL. 153, PG. 85

Approved - Mathematically
Hocking County Engineer's office
By A.C.O. Date 2-28-97

PLAT PREPARED FROM SURVEY
MADE FEB. 20, 1997, BY:

M. P. [Signature]
OHIO REGISTERED SURVEYOR NO. 6833



DESCRIPTION OF 6.0766 AC. TRACT

Being a part of a tract of land last transferred in Vol. 56, Pg. 178, Hocking Co. Official Records, situated in the SW 1/4 of Sec. 14, Laurel Twp., T-12N, R-18W, Hocking Co., Ohio, and being more particularly described as follows:

Beginning at an iron pin previously set on the NE corner of the 11.8452 Ac. tract described in O.R. Vol. 90, Pg. 610;

Thence, with the north line of said SW 1/4 and along an existing fence, N 87 degrees 41' 03" E a distance of 602.34 ft. to an iron pin set in an existing fence corner;

Thence, with the east line of the tract of which this survey is a part and along an existing fence, S 1 degree 44' 48" E a distance of 1065.25 ft. to an iron pin found in the center of Twp. Rd. No. 232;

Thence, with the center of said Twp. road, N 48 degrees 32' 21" W a distance of 82.32 ft. to a point;

Thence, with a new line, N 1 degree 44' 48" W, passing an iron pin set at 20.00 ft., going a total distance of 741.35 ft. to an iron pin set;

Thence S 65 degrees 25' 38" W a distance of 420.62 ft. to a point in the center of an existing private lane;

Thence, leaving said lane, West, passing an iron pin set at 20.00 ft., going a total distance of 167.50 ft. to an iron pin set on the east line of the 11.8452 Ac. tract described in O.R. Vol. 90, Pg. 610;


Thence, with said east line, North a distance of 419.82 ft. to the place of beginning, containing 6.0766 acres, more or less, and being subject to the right-of-way of Twp. Rd. No. 232 and all valid easements.

Cited bearings are based on the bearing system of the 11.8452 Ac. tract described in O.R. Vol. 90, Pg. 610;

All iron pins described as being set or previously set are 5/8" X 30" with an attached plastic identification cap.

The above description is the result of an actual survey made by Michael P. Berry, Ohio Registered Surveyor No. 6803, on Feb. 20, 1997.

Approved - Mathematically
Hocking County Engineer's office
By RCO Date 2-20-97


Michael P. Berry #6803

DESCRIPTION OF 30.0 FT. EASEMENT

Being a non-exclusive 30.0 ft. wide easement for the purpose of ingress and egress across part of a tract described in O.R. Vol. 56, Pg. 178, situated in the SW 1/4 of Sec. 14, Laurel Twp., T-12N, R-18W, Hocking Co., Ohio. The centerline of said easement is described as follows:

Beginning at a point in the center of a private lane, said point being referenced by the NE corner of the 11.8452 Ac. tract described in O.R. Vol. 90, Pg. 610, which bears West a distance of 167.50 ft. and North a distance of 419.82 ft.;

Thence with the center of said private lane the following three (3) courses:

1) S 16 degrees 21' 03" E a distance of 187.99 ft. to a point;

2) S 32 degrees 06' 22" E a distance of 95.22 ft. to a point;

3) S 25 degrees 59' 19" E a distance of 152.05 ft. to a point of termination in the center of Twp. Rd. No. 232.

The above description is the result of an actual survey made by Michael P. Berry, Ohio Registered Surveyor No. 6803, on Feb. 20, 1997.

Approved - Mathematically
Hocking County Engineer's office
By RCO Date 2-20-97


Michael P. Berry #6803

Laurel 14-~~22~~23



Parcel 1
31.4 ac.

Exception
10.467 ac.

Parcel 2
0.13 ac.

Exception
0.059 ac.

14

22 23

NW 1/4 NW 1/4

Lot 2

Parcel 3 93.9 ac.

E 1/2 NE 1/4

Parcel 4
133 ac.

Residue Homer Schein Land

Sections 14-22-23

Laurel Twp

Hocking County Ohio

NE 1/4 SE 1/4

Donated, June 1982, by
ALBERT W. SEABRIGHT, P.E., P.S.
COUNTY ENGINEER 1949 - 1964


AW Seabright
June 14 1948

THIS PAGE
LEFT BLANK
INTENTIONALLY

PLAT OF A 0.277 ACRE TRACT FOR JEFF LUTZ

LAUREL 14
.277Ac.

Situated in Laurel Township, Hocking County, Ohio; being part of the Southwest quarter of the Southwest quarter of Section 14, Township 12, Range 18.



REFERENCE BEARING:

The South line of the Southwest quarter of the Southwest quarter of Section 14 as South 90 degrees 00 minutes 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only.

CERTIFICATION:

I hereby certify that an actual survey was made under my supervision of the premises shown hereon on the 11th day of March, 1997 and that the plat is a correct representation of the premises as described by said survey.

Larry P. Gerstner
Registered Surveyor No. 6344

Survey by: Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138
(614) 385-4260

SURVEY DESCRIPTION OF A .277 ACRE TRACT FOR JEFF LUTZ

Situated in Laurel Township, Hocking County, Ohio; being part of the Southwest quarter of the Southwest quarter of Section 14, Township 12, Range 18; and being more particularly described as follows:

Commencing for reference at a railroad spike found at the Southwest corner of Section 14 in the center of County Road 9, Kreashbaum Road; thence with said County Road 9 and the West line of Section 14 North 0 degrees 17 minutes 50 seconds West a distance of 274.60 feet to a PK nail set, passing a PK nail set at a distance of 120.26 feet, and being the point of **Beginning** of the tract of land to be described;

thence continuing with the West line of Section 14 and said County Road 9 North 0 degrees 17 minutes 50 seconds West a distance of 60.01 feet to a PK nail set;

thence leaving said County Road 9 and the West line of Section 14 North 88 degrees 47 minutes 59 seconds East a distance of 104.63 feet to a damaged 3/4" OD iron pipe found and passing a 5/8" iron pin set at a distance of 16.00 feet;

thence North 78 degrees 11 minutes 20 seconds East a distance 120.00 feet to a 5/8" iron pin set;

thence South 36 degrees 51 minutes 35 seconds West a distance of 104.27 feet to a 5/8" iron pin set;

thence South 88 degrees 47 minutes 59 seconds West a distance of 159.24 feet to the point of beginning, passing a 5/8" iron pin set at a distance of 139.24 feet, and containing .277 acres more or less subject to the public easement of County Road 9 and any other public or private easements of record.

The above .277 acre survey is intended to describe part of the 2.254 acre surveyed tract as deeded to Jeffery and Tammy Lutz, deed reference Volume 184, Page 49, Hocking County Recorder's Office. This survey was based upon information obtained from tax maps, deed descriptions, previous surveys, existing monument, and an existing public road. The reference bearing for this survey is the South line of the Southwest quarter of the Southwest quarter of Section 14 as South 90 degrees 00 minutes 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only. All iron pins set by this survey are 5/8" by 30" and are capped by a 1-1/4" plastic identification cap stamped LPG-6344. The above described property was surveyed by Larry P. Gerstner, Ohio Registered Surveyor No. 6344, on March 11, 1997.



A handwritten signature of Larry P. Gerstner in cursive script, positioned above a horizontal line.

* Approved - Mathematically
Hocking County Engineer's office
By John Date 3-12-97
Pending Health Dept Approval
On Remainder of 2.54 Acre Tract

* [Illegible text]
as separate building and
as an independent parcel in
without Planning Commission and
Health Dept. approval.



Survey by:
Larry P. Gerstner - Engineering and Surveying
9 East Second Street - Suite A, Logan, Ohio 43138 385-4260

PLAT OF A 7.185 ACRE TRACT FOR MARTIN AND GAIL LOHN

LAUREL 14

7.185 Ac -

Situated in Laurel Township, Hocking County, Ohio; being part of the Northeast quarter of the Southwest quarter of Section 14, Township 12, Range 18.



REFERENCES:

- Tax maps
- Deed descriptions
- Previous surveys
- Existing monumentation
- Existing public road

LEGEND

- 5/8" iron pin with 1-1/4" plastic ID cap stamped 6803 found
- 5/8"x 30" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 set
- △ MAG nail previously set
- ▲ MAG nail set
- ⊙ 1" OD iron pipe found (damaged)
- 5/8" iron pin previously set

REFERENCE BEARING:

East line of the Northeast quarter of the Southwest quarter of Section 14 as South 0 degrees 00 minutes 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only.

CERTIFICATION:

I hereby certify that an actual survey was made under my supervision of the premises shown hereon on the 25th day of January, 2001 and that the plat is a correct representation of the premises as described by said survey.

Larry P. Gerstner
Registered Surveyor No. 6344

Survey by: Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138
(740) 385-4260

SURVEY DESCRIPTION OF A 7.185 ACRE TRACT FOR MARTIN AND GAIL LOHN

Situated in Laurel Township, Hocking County, Ohio; being part of the Northeast quarter of the Southwest quarter of Section 14, Township 12, Range 18; and being more particularly described as follows:

Commencing for reference at a 5/8" iron pin with 1-1/4" plastic ID cap stamped 6803 found at the Northwest corner of the Northeast quarter of the Southwest quarter of Section 14; thence South 88 degrees 57 minutes 48 seconds East a distance of 720.77 feet to a damaged 1" OD iron pipe found; thence South 1 degree 30 minutes 44 seconds West a distance of 345.86 feet to a 5/8" iron pin previously set and being the point of **Beginning** of the tract of land to be described;

thence continuing South 1 degree 30 minutes 44 seconds West a distance of 711.25 feet to a 5/8" iron pin previously set and passing 5/8" iron pins previously set at distances of 332.49 feet and 660.68 feet;

thence South 57 degrees 09 minutes 32 seconds West a distance of 468.88 feet to a MAG nail previously set in the North edge of Township Road 232, Rocky Fork Road, and passing a 5/8" iron pin previously set at a distance of 459.31 feet;

thence with the center of said Township Road 232 North 52 degrees 27 minutes 07 second West a distance of 156.86 feet to a MAG nail set in the center of said Township Road 232;

thence leaving the center of said Township Road 232 North 8 degrees 59 minutes 57 seconds East a distance of 411.19 feet to a 5/8" iron pin set and passing a 5/8" iron pin set at a distance of 20.73 feet;

thence North 37 degrees 15 minutes 12 seconds East a distance of 302.33 feet to a 5/8" iron pin set and passing a MAG nail set in the center of a private driveway at a distance of 9.14 feet;

thence North 52 degrees 25 minutes 38 seconds East a distance of 365.58 feet to the point of beginning, containing 7.185 acres more or less, and subject to the public easement of said Township Road 232 and any other public or private easements of record.

The above 7.185 acre survey is intended to describe part of the 40 acre Tract One as deeded to Martin R. and Gail Lohn, deed reference Volume OR8, Page 925, Hocking County Recorder's Office. This survey was based upon information obtained from tax maps, deed descriptions, previous surveys, existing monumentation, and an existing public road. The reference bearing for this survey is the East line of the Northeast quarter of the Southwest quarter of Section 14 as South 0 degrees 00 minutes 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only. All iron pins set by this survey or previously set are 5/8" by 30" and are capped by a 1-1/4" plastic identification cap stamped LPG-6344. The above described property was surveyed by Larry P. Gerstner, Ohio Registered Surveyor No. 6344, on January 25, 2001.



Hocking County Engineer's Office
MAV 26-01


A handwritten signature of Larry P. Gerstner in black ink, written over a horizontal line.

Survey by:
Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138 385-4260

LAUREL 14
15.00 Ac.

PLAT OF A 15.000 ACRE TRACT FOR JEFF LUTZ

Situated in Laurel Township, Hocking County, Ohio; being part of the Southwest quarter of the Southwest quarter of Section 14, Township 12, Range 18.



N3°23'20"W
60.65'
Wesley & Gwen Harmon
215-860

DAMAGED
Jeffrey & Tammy Lutz
184-049

LEGEND

- 5/8" iron pin with 1-1/4" plastic ID cap stamped 4027 found
- 5/8" x 30" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 set
- Stone found
- ⊙ 5/8" iron pin found
- ⊗ 3/4" OD iron pipe found

* Approved - Mathematically - Pending Remainder Hocking County Engineer's Office To The Southw. Having Health Pg 3-13-97 Approval
* APPROVAL REMAINS
* as separate building, etc. as an independent parcel to be subject Planning Commission and to pt. approval.

Jesse & Velma Vorhees
204-517

S90°00'00"W - 812.77'

S89°55'49"W
253.09'

N0°37'49"W
279.54'

120.00'
S78°11'20"W
310.21' TOTAL

N74°35'08"E - 1401.18'

Ida Lutz
148-564
15.000 acres

OLD INFO PURPOSES FOR NEW SURVEYS



SCALE:
1" = 200'

NOTE: THIS TRACT IS TO TRANSFER TO Jeffrey + Tammy Lutz (ATAMIN'S OWNERS) THEN LATER THEY PLAN TO KEEP 15 Ac. Tract And -277Ac. Tract (for Road Frontage) AT THAT TIME 15 Ac. Tract And -277Ac. Tract must have Planning Comm. Approval

Southeast corner of the Southwest quarter of the Southwest quarter of Section 14

Point of Beginning

Brian & Teresa Vorhees
OR51-879

Paul & Audni Beach
159-658

N1°53'20"W
213.14'

S1°53'20"E - 770.19'

SECTION 14
SECTION 23

REFERENCES:

- Tax maps
- Deed descriptions
- Previous surveys
- Existing monumentation

REFERENCE BEARING:

The South line of the Southwest quarter of the Southwest quarter of Section 14 as South 90 degrees 00 minutes 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only.

CERTIFICATION:

I hereby certify that an actual survey was made under my supervision of the premises shown hereon on the 11th day of March, 1997 and that the plat is a correct representation of the premises as described by said survey.

Larry P. Gerstner

Registered Surveyor No. 6344

Survey by:
Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138
(614) 385-4260

SURVEY DESCRIPTION OF A 15.000 ACRE TRACT FOR JEFF LUTZ

Situated in Laurel Township, Hocking County, Ohio; being part of the Southwest quarter of the Southwest quarter of Section 14, Township 12, Range 18; and being more particularly described as follows:

Beginning at a stone found at the Southeast corner of the Southwest quarter of the Southwest quarter of Section 14; thence with the South line of Section 14 South 90 degrees 00 minutes 00 seconds West a distance of 812.77 feet to a 5/8" iron pin set;

thence leaving the South line of Section 14 North 0 degrees 00 minutes 00 seconds West a distance of 121.07 feet to a 5/8" iron pin set;

thence South 89 degrees 55 minutes 49 seconds West a distance of 253.09 feet to a 5/8" iron pin with 1-1/4" plastic ID cap stamped 4027 found;

thence North 0 degrees 37 minutes 49 seconds West a distance 279.54 feet to a 5/8" iron pin set;

thence South 78 degrees 11 minutes 20 seconds West a distance of 310.21 feet to a damaged 3/4" OD iron pipe found and passing a 5/8" iron pin set at a distance of 190.21 feet;

thence North 3 degrees 23 minutes 20 seconds West a distance of 60.65 feet to a 5/8" iron pin set;

thence North 74 degrees 35 minutes 08 seconds East a distance of 1401.18 feet to a 5/8" iron pin set, from which a 5/8" iron pin found bears North 1 degree 53 minutes 20 seconds West at a distance of 213.14 feet;

thence South 1 degree 53 minutes 20 seconds East a distance of 770.19 feet to the point of beginning, containing 15.000 acres more or less.

The above 15.000 acre survey is intended to describe part of the remaining 29.853 acre surveyed 44.594 acre tract as deeded to Ida Lutz, deed reference Volume 148, Page 564, Hocking County Recorder's Office. This survey was based upon information obtained from tax maps, deed descriptions, previous surveys, and existing monumentation. The reference bearing for this survey is the South line of the Southwest quarter of the Southwest quarter of Section 14 as South 90 degrees 00 minutes 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only. All iron pins set by this survey are 5/8" by 30" and are capped by a 1-1/4" plastic identification cap stamped LPG-6344. The above described property was surveyed by Larry P. Gerstner, Ohio Registered Surveyor No. 6344, on March 11, 1997.



VOID

A handwritten signature of Larry P. Gerstner in cursive script, written over a horizontal line.

* Approved - Mathematically
Hocking County Engineer's office
By MAW Date 3-13-97
Pay'd Health Dept Approval On Remainder
To The South West
* ADDITIONAL APPROVAL TRANSFERRED
used as separate building
referred as an independent parcel
without Planning Commission or
the Dept. approval.

Survey by:

Larry P. Gerstner - Engineering and Surveying
9 East Second Street - Suite A, Logan, Ohio 43138 385-4260


PLAT OF A 21.625 ACRE TRACT FOR MARTIN AND GAIL LOHN

21.265 Ac.

Situated in Laurel Township, Hocking County, Ohio; being part of the Northeast quarter of the Southwest quarter and part of the Southeast quarter of the Southwest quarter, both of Section 14, Township 12, Range 18.

LEGEND

- 5/8" iron pin with 1-1/4" plastic ID cap stamped SEYMOUR & ASSOC. found
- 5/8"x 30" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 set
- ▲ MAG nail set
- 1" OD iron pipe found




SCALE:
1" = 300'



REFERENCES:

- Tax maps
- Deed descriptions
- Previous surveys
- Existing monumentation
- Existing public roads



REFERENCE BEARING:

East line of the Northeast quarter of the Southwest quarter of Section 14 as South 0 degrees 00 minutes 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only.

CERTIFICATION:

I hereby certify that an actual survey was made under my supervision of the premises shown hereon on the 18th day of December, 2000 and that the plat is a correct representation of the premises as described by said survey.

Larry P. Gerstner
 Registered Surveyor No. 6344

Survey by: Larry P. Gerstner - Engineering and Surveying
 9 East Second Street, Suite A, Logan, Ohio 43138
 (740) 385-4260

Hocking County Engineer's Office
MHW DATE 12-22-00

SURVEY DESCRIPTION OF A 21.625 ACRE TRACT FOR MARTIN AND GAIL LOHN

Situated in Laurel Township, Hocking County, Ohio; being part of the Northeast quarter of the Southwest quarter and part of the Southeast quarter of the Southwest quarter, both of Section 14, Township 12, Range 18; and being more particularly described as follows:

Beginning at a 5/8" iron pin with 1-1/4" plastic ID cap stamped SEYMOUR & ASSOC. found at the Northeast corner of the Northeast quarter of the Southwest quarter of Section 14; thence South 0 degrees 00 minutes 00 seconds West a distance of 1315.08 feet to a 5/8" iron pin with 1-1/4" plastic ID cap stamped SEYMOUR & ASSOC. found;

thence North 88 degrees 39 minutes 47 seconds West a distance of 676.80 feet to a 5/8" iron pin set in the center of Township Road 136, Uckor Road, and passing a 5/8" iron pin set at a distance of 628.00 feet;

thence with the center of said Township Road 136 South 0 degrees 18 minutes 08 seconds West a distance of 48.48 feet to a MAG nail set in the center of Township Road 232, Rocky Fork Road;

thence leaving the center of said Township Road 136 and with the center of said Township Road 232 the following five bearings and distances;

- 1) North 72 degrees 14 minutes 43 seconds West a distance of 39.09 feet to a MAG nail set;
- 2) South 45 degrees 24 minutes 17 seconds West a distance of 92.28 feet to a MAG nail set;
- 3) South 73 degrees 49 minutes 17 seconds West a distance of 39.50 feet to a MAG nail set;
- 4) North 71 degrees 55 minutes 43 seconds West a distance of 58.58 feet to a MAG nail set;
- 5) North 62 degrees 40 minutes 43 seconds West a distance of 214.19 feet to a MAG nail set in the edge of said Township Road 232;

thence leaving said Township Road 232 North 57 degrees 09 minutes 32 second East a distance of 468.88 feet to a 5/8" iron pin set and passing a 5/8" iron pin set at a distance of 9.57 feet;

thence North 1 degree 30 minutes 44 seconds East a distance of 1057.11 feet to a damaged 1" OD iron pipe found;


thence South 88 degrees 14 minutes 34 seconds East a distance of 323.43 feet to a 1" OD iron pipe found;

thence South 88 degrees 55 minutes 56 seconds East a distance of 318.68 feet to the point of beginning, containing 21.625 acres more or less, and subject to the public easements of said Township Roads 136 and 232 and any other public or private easements of record.

The above 21.625 acre survey is intended to describe part of the 40 acre Tract One and all of the .56 acre Tract Two both as deeded to Martin R. and Gail Lohn, deed reference Volume OR8, Page 925, Hocking County Recorder's Office. This survey was based upon information obtained from tax maps, deed descriptions, previous surveys, existing monumentation, and existing public roads. The reference bearing for this survey is the East line of the Northeast quarter of the Southwest quarter of Section 14 as South 0 degrees 00 minutes 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only. All iron pins set by this survey are 5/8" by 30" and are capped by a 1-1/4" plastic identification cap stamped LPG-6344. The above described property was surveyed by Larry P. Gerstner, Ohio Registered Surveyor No. 6344, on December 18, 2000.

Approved - Mathematically
Hocking County Engineer's Office

L.P.G. DATE 12-22-00




Survey by:

Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138 385-4260

PLAT OF A 6.904 ACRE TRACT FOR HERBERT AND JEANNINE WATKINS

6.904A.

Situated in Laurel Township, Hocking County, Ohio; being part of the West half of the Southwest quarter of Section 14, Township 12, Range 18.




Approved - Mathematically
Hocking County Engineer's Office

BY *R. FN* DATE 5-11-98

LEGEND

- 5/8"x 30" (15" in roadway) iron pin with 1-1/4" plastic ID cap stamped LPG-6344 previously set
- 5/8"x 30" (15" in roadway) iron pin with 1-1/4" plastic ID cap stamped LPG-6344 set
- ⊙ 5/8" iron pin with 1-1/4" plastic ID cap stamped MPB-6803 found
- ⊗ Iron pipe not found



REFERENCES:

- Tax maps
- Deed descriptions
- Previous surveys
- Existing monumentation
- Existing public road

REFERENCE BEARING:

The West line of Section 14 as North 0 degrees 5 minutes 30 seconds East. Bearings are based upon an assumed meridian and are to denote angles only.

CERTIFICATION:

I hereby certify that an actual survey was made under my supervision of the premises shown hereon on the 8th day of May, 1998 and that the plat is a correct representation of the premises as described by said survey.

Larry P. Gerstner
Registered Surveyor No. 6344

Survey by: Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138
(740) 385-4260

SURVEY DESCRIPTION OF A 6.904 ACRE TRACT FOR HERBERT AND JEANNINE WATKINS

Situated in Laurel Township, Hocking County, Ohio; being part of the West half of the Southwest quarter of Section 14, Township 12, Range 18; and being more particularly described as follows:

Commencing for reference at an iron pipe not found at the Northwest corner of the West half of the Southwest quarter of Section 14; thence North 89 degrees 15 minutes 32 seconds East a distance of 803.51 feet to a 5/8" iron pin with 1-1/4" plastic ID cap stamped MPB-6803 found; thence South 0 degrees 00 minutes 00 seconds East a distance of 420.55 feet to a 5/8" iron pin with 1-1/4" plastic ID cap stamped MPB-6803 found and being the point of **Beginning** of the tract of land to be described;

thence North 89 degrees 55 minutes 39 seconds East a distance of 167.30 feet to a 5/8" iron pin set and passing a 5/8" iron pin with plastic ID cap stamped MPB-6803 found at a distance of 147.30 feet;

thence North 65 degrees 23 minutes 25 seconds East a distance of 420.54 feet to a 5/8" iron pin with 1-1/4" plastic ID cap stamped MPB-6803 found;

thence South 1 degree 46 minutes 52 seconds East a distance of 741.50 feet to a 5/8" iron pin set in the center of Township Road 232, Rocky Fork Road, and passing a 5/8" iron pin with 1-1/4" plastic ID cap stamped MPB-6803 found at a distance of 721.50 feet;

thence with the surface of said Township Road 232 the following four bearings and distances:

- 1) North 51 degrees 35 minutes 14 seconds West a distance of 151.09 feet to a 5/8" iron pin set;
- 2) North 50 degrees 32 minutes 09 seconds West a distance of 94.07 feet to a 5/8" iron pin set;
- 3) North 78 degrees 16 minutes 09 seconds West a distance of 109.50 feet to a 5/8" iron pin set off of the road surface;

4) South 42 degrees 13 minutes 35 seconds West a distance of 188.15 feet to a 5/8" iron pin previously set;

thence leaving the surface of said Township Road 232 South 86 degrees 04 minutes 02 seconds West a distance of 78.93 feet to a 5/8" iron pin previously set and passing a 5/8" iron pin previously set at a distance of 30.00 feet;

thence North 51 degrees 59 minutes 30 seconds West a distance of 87.93 feet to a 5/8" iron pin previously set;

thence North 0 degrees 00 minutes 00 seconds East a distance of 480.52 feet to the point of beginning, passing 5/8" iron pins previously set at distances of 95.28 feet, 190.72 feet, 286.42 feet, and 387.87 feet, containing 6.904 acres more or less, and subject to the public easement of said Township Road 232 and any other public or private easements of record.

The above 6.904 acre survey is intended to describe all of the remaining 24.76 acres as deeded to Herbert and Jeannine Watkins, deed references Volume OR54, Page 274, and Volume OR56, Page 178, both of the Hocking County Recorder's Office. This survey was based upon information obtained from tax maps, deed descriptions, previous surveys, existing monumentation, and an existing public road. The reference bearing for this survey is the West line of Section 14 as North 0 degrees 5 minutes 30 seconds East. Bearings are based upon an assumed meridian and are to denote angles only. All iron pins set by this survey are 5/8" by 30" (15" in roadway) and are capped by a 1-1/4" plastic identification cap stamped LPG-6344. The above described property was surveyed by Larry P. Gerstner, Ohio Registered Surveyor No. 6344, on May 8, 1998.

Approved - Mathematically
Hocking County Engineer's Office

BY LFN DATE 5-11-98




Survey by:

Larry P. Gerstner - Engineering and Surveying
East Second Street, Suite A, Logan, Ohio 43138 385-4260

Laurel #14

CHLOE V. HELLER 43.774 AC.
D.B. 145, PG. 369



- = IRON PIPE
 - = RAILROAD SPIKE
 - E— = ELECTRIC LINE
- SCALE 1" = 100'

SURVEY OF:
 10.211 ACRE TRACT
 N. 1/2, SEC. 14, T. 12 N., R. 18 W.
 LAUREL TWP., HOCKING CO.

NOW OR FORMERLY
 ROBERT P. DONLEY
 40 AC.

SURVEYED FOR:
 MRS. CHLOE V. HELLER &
 LAWYERS TITLE INS. CORP.

APPROVED
 HOCKING COUNTY ENGINEER'S OFFICE
 DATE 1-7-75
 BY J. E.

SURVEYED BY:
 HARRY W. ROLFE


Harry W. Rolfe
 REGISTERED SURVEYOR NO. 5231

NOVEMBER 1974

LAUREL 14
1.837Ac.

PLAT OF A 1.837 ACRE TRACT FOR IDA LUTZ

Situated in Laurel Township, Hocking County, Ohio; being part of the Southwest quarter of the Southwest quarter of Section 14, Township 12, Range 18.



REFERENCES:

- Tax maps
- Deed descriptions
- Previous surveys
- Existing monumentation
- Existing public road

Approved - Mathematically
Hocking County Engineer's office
By: *[Signature]* Date 3-13-97

~~PLANNING HEALTH DEPT~~

BY *[Signature]* DATE 3-13-97
MAY NEED PLANNING COMH APPROVAL
FF THIS EVER TRANSFERS

LEGEND

- 5/8" iron pin with 1-1/4" plastic ID cap stamped 4027 found
- 5/8"x 30" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 set
- ⊙ Damaged 5/8" iron pin found
- ▲ PK nail set
- Railroad spike found

REFERENCE BEARING:

The South line of the Southwest quarter of the Southwest quarter of Section 14 as South 90 degrees 00 minutes 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only.

CERTIFICATION:

I hereby certify that an actual survey was made under my supervision of the premises shown hereon on the 11th day of March, 1997 and that the plat is a correct representation of the premises as described by said survey.

[Signature]
Registered Surveyor No. 6344

Survey by: Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138
(614) 385-4260

SURVEY DESCRIPTION OF A 1.837 ACRE TRACT FOR IDA LUTZ

Situated in Laurel Township, Hocking County, Ohio; being part of the Southwest quarter of the Southwest quarter of Section 14, Township 12, Range 18; and being more particularly described as follows:

Beginning at a railroad spike found at the Southwest corner of Section 14 in the center of County Road 9, Kreashbaum Road; thence with said County Road 9 and the West line of Section 14 North 0 degrees 17 minutes 50 seconds West a distance of 120.26 feet to a PK nail set;

thence leaving said County Road 9 and the West line of Section 14 North 89 degrees 55 minutes 49 seconds East a distance of 663.30 feet to a 5/8" iron pin set, passing a damaged 5/8" iron pin found at a distance of 15.66 feet and a 5/8" iron pin with 1-1/4" plastic ID cap stamped 4027 found at a distance of 410.21 feet;

thence South 0 degrees 00 minutes 00 seconds East a distance 121.07 feet to a 5/8" iron pin set;

thence South 90 degrees 00 minutes 00 seconds West a distance of 662.68 feet to the point of beginning, passing a 5/8" iron pin set at a distance of 642.68 feet, and containing 1.837 acres more or less subject to the public easement of County Road 9 and any other public or private easements of record.

The above 1.837 acre survey is intended to describe part of the remaining 29.853 acre surveyed 44.594 acre tract as deeded to Ida Lutz, deed reference Volume 148, Page 564, Hocking County Recorder's Office. This survey was based upon information obtained from tax maps, deed descriptions, previous surveys, existing monument, and an existing public road. The reference bearing for this survey is the South line of the Southwest quarter of the Southwest quarter of Section 14 as South 90 degrees 00 minutes 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only. All iron pins set by this survey are 5/8" by 30" and are capped by a 1-1/4" plastic identification cap stamped LPG-6344. The above described property was surveyed by Larry P. Gerstner, Ohio Registered Surveyor No. 6344, on March 11, 1997.



A handwritten signature of Larry P. Gerstner in cursive script, written over a horizontal line.

Approved - Mathematically
Hocking County Engineer's office
E. J. W. Date 3-13-97

~~SUBDIVISION REGULATIONS NEED~~
PENDING HEALTH DEPT. APPROVAL



BY JM DATE 3-13-97
MAY NEED PLANNING COMM APPROVAL
IF THIS TRACT EVER TRANSFERS

Survey by:
Larry P. Gerstner - Engineering and Surveying
9 East Second Street - Suite A, Logan, Ohio 43138 385-4260

LAUREL 14
13.007A.

PLAT OF A 13.007 ACRE TRACT FOR JEFF LUTZ

Situated in Laurel Township, Hocking County, Ohio; being part of the Southwest quarter of the Southwest quarter of Section 14, Township 12, Range 18.



LEGEND

- 5/8" iron pin with 1-1/4" plastic ID cap stamped 4027 found
- 5/8" x 30" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 set
- Stone found
- ⊙ 5/8" iron pin found
- ⊗ 3/4" OD iron pipe found

Approved - Mathematically
 Hocking County Engineer's Office
 Date 4-1-97
Larry P. Gerstner
 Planning Comm. Approval

REFERENCES:

- Tax maps
- Deed descriptions
- Previous surveys
- Existing monumentation

REFERENCE BEARING:

The South line of the Southwest quarter of the Southwest quarter of Section 14 as South 90 degrees 00 minutes 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only.

CERTIFICATION:

I hereby certify that an actual survey was made under my supervision of the premises shown hereon on the 26th day of March, 1997 and that the plat is a correct representation of the premises as described by said survey.

Larry P. Gerstner
 Registered Surveyor No. 6344


Survey by:
 Larry P. Gerstner - Engineering and Surveying
 9 East Second Street, Suite A, Logan, Ohio 43138
 (614) 385-4260

LAUREL 14
 .310 Ac.
 W 1/2 SW 1/4 -

PLAT OF A 0.310 ACRE TRACT FOR DAVID HENNEN

Situated in Laurel Township, Hocking County, Ohio; being part of the West half of the Southwest quarter of Section 14, Township 12, Range 18.

Approved - Mathematically
 Hocking County Engineer's office
 by J. A. Davis Date 10-23-97



LEGEND



- 5/8" iron pin with 1-1/4" plastic ID cap stamped MPB-6803 found
- 5/8"x 30" (15" in roadway) iron pin with 1-1/4" plastic ID cap stamped LPG-6344 set
- ⊙ Iron pipe not found



David & Patricia Hennen
 OR90-610

Herbert & Jeannine Watkins
 OR54-274,
 OR56-178
 0.310 acres

Alvie Newsome
 201-68



REFERENCES:

- Tax maps
- Deed descriptions
- Previous surveys
- Existing monumentation
- Existing public road

REFERENCE BEARING:

The West line of Section 14 as North 0 degrees 5 minutes 30 seconds East. Bearings are based upon an assumed meridian and are to denote angles only.

CERTIFICATION:

I hereby certify that an actual survey was made under my supervision of the premises shown hereon on the 20th day of October, 1997 and that the plat is a correct representation of the premises as described by said survey.

Larry P. Gerstner
 Registered Surveyor No. 6344

Survey by: Larry P. Gerstner - Engineering and Surveying
 9 East Second Street, Suite A, Logan, Ohio 43138
 (614) 385-4260

SURVEY DESCRIPTION OF A .310 ACRE TRACT FOR DAVID HENNEN

Situated in Laurel Township, Hocking County, Ohio; being part of the West half of the Southwest quarter of Section 14, Township 12, Range 18; and being more particularly described as follows:

Commencing for reference at an iron pipe not found at the Northwest corner of the West half of the Southwest quarter of Section 14; thence North 89 degrees 15 minutes 32 seconds East a distance of 803.51 feet to a 5/8" iron pin with 1-1/4" plastic ID cap stamped MPB-6803 found; thence South 0 degrees 00 minutes 00 seconds East a distance of 901.07 feet to a 5/8" iron pin set, passing a 5/8" iron pin with 1-1/4" plastic ID cap stamped MPB-6803 found at a distance of 420.55 feet and 5/8" iron pins set at distances of 513.20 feet, 614.65 feet, 710.35 feet, and 805.79 feet, and being the point of **Beginning** of the tract of land to be described;

thence South 51 degrees 59 minutes 30 seconds East a distance of 87.93 feet to a 5/8" iron pin set; thence North 86 degrees 04 minutes 02 seconds East a distance of 78.93 feet to a 5/8" iron pin set in the center of Township Road 232, Rocky Fork Road, and passing a 5/8" iron pin set at a distance of 48.93 feet;

thence with the center of said Township Road 232 the following three bearings and distances:
1) South 43 degrees 24 minutes 49 seconds West a distance of 65.00 feet to a 5/8" iron pin set;
2) South 40 degrees 12 minutes 24 seconds West a distance of 87.66 feet to a 5/8" iron pin set;
3) South 41 degrees 13 minutes 58 seconds West a distance of 70.95 feet to a 5/8" iron pin set;
thence leaving the center of said Township Road 232 North 0 degrees 00 minutes 00 seconds West a distance of 216.25 feet to the point of beginning, passing a 5/8" iron pin with 1-1/4" plastic ID cap stamped MBP-6803 found at a distance of 20.00 feet, containing .310 acres more or less, and subject to the public easement of said Township Road 232 and any other public or private easements of record.

The above .310 acre survey is intended to describe part of the remaining 25.07 acres as deeded to Herbert and Jeannine Watkins, deed references Volume OR54, Page 274, and Volume OR56, Page 178, both of the Hocking County Recorder's Office. This survey was based upon information obtained from tax maps, deed descriptions, previous surveys, existing monumentation, and an existing public road. The reference bearing for this survey is the West line of Section 14 as North 0 degrees 5 minutes 30 seconds East. Bearings are based upon an assumed meridian and are to denote angles only. All iron pins set by this survey are 5/8" by 30" (15" in roadway) and are capped by a 1-1/4" plastic identification cap stamped LPG-6344. The above described property was surveyed by Larry P. Gerstner, Ohio Registered Surveyor No. 6344, on October 20, 1997.



Approved - Mathematically
Hocking County Engineer's office
by *MAW* Date *10-23-97*

CONDITIONAL APPROVAL. THIS SURVEY IS NOT TO BE USED AS AN INSTRUMENT OF RECORD WITHOUT PLANNING COMMISSION APPROVAL.

Larry P. Gerstner

Survey by:
Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138 385-4260

LAUREL 14

15.00 A.

PLAT OF A 15.000 ACRE TRACT FOR JEFF LUTZ

Situated in Laurel Township, Hocking County, Ohio; being part of the Southwest quarter of the Southwest quarter of Section 14, Township 12, Range 18.

REFERENCES:

- Tax maps
- Deed descriptions
- Previous surveys
- Existing monumentation



Wesley & Gwen Harmon 215-860

Charles & Ethel Woyan 199-806

N0°17'50"W
103.52'

S59°23'10"W
101.40'

SECTION 15
SECTION 14

N63°14'56"E- 305.15'

S90°00'00"W- 694.93'

Alvie Newsome
201-68

N70°01'54"E
195.02'

N66°40'52"E- 572.59'

S85°58'41"E
268.48'

S56°44'50"E
235.88'

Ida Lutz
148-564
15.000 acres

Paul & Audni Beach
159-658

* Approved - Mathematically
Hocking County Engineer's office
by *LA* Date *4-1-97*

* CONDITIONAL APPROVAL/TRANSFER OF THIS TRACT TO BE USED AS SEPARATE BUILDING SITE PERFORMED AS AN INDEPENDENT PARCEL IN FUTURE WITHOUT PLANNING COMMISSION AND... WITH DEPT. APPROVAL.

LEGEND

- 7/8" iron pin found
- ◉ 5/8" iron pin found
- 5/8" x 30" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 set
- Stone found



SCALE:
1" = 100'

Southeast corner of the Southwest quarter of the Southwest quarter of Section 14

Point of Beginning

N1°53'20"W
303.33'

S1°53'20"E- 680.00'

REFERENCE BEARING:

The South line of the Southwest quarter of the Southwest quarter of Section 14 as South 90 degrees 00 minutes 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only.

CERTIFICATION:

I hereby certify that an actual survey was made under my supervision of the premises shown hereon on the 26th day of March, 1997 and that the plat is a correct representation of the premises as described by said survey.

Larry P. Gerstner
Registered Surveyor No. 6344

Survey by:
Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138
(614) 385-4260

SURVEY DESCRIPTION OF A 15.000 ACRE TRACT FOR JEFF LUTZ

Situated in Laurel Township, Hocking County, Ohio; being part of the Southwest quarter of the Southwest quarter of Section 14, Township 12, Range 18; and being more particularly described as follows:

Commencing for reference at a stone found at the Southeast corner of the Southwest quarter of the Southwest quarter of Section 14; thence North 1 degree 53 minutes 20 seconds West a distance of 303.33 feet to a 5/8" iron pin set and being the point of **Beginning** of the tract of land to be described;
thence North 75 degrees 57 minutes 51 seconds West a distance of 707.47 feet to a 5/8" iron pin set;
thence North 0 degrees 00 minutes 00 seconds West a distance of 173.73 feet to a 5/8" iron pin set;
thence South 90 degrees 00 minutes 00 seconds West a distance 694.93 feet to a 5/8" iron pin set;
thence South 59 degrees 23 minutes 10 seconds West a distance of 101.40 feet to a 5/8" iron pin set on the West line of Section 14;
thence with the West line of Section 14 North 0 degrees 17 minutes 50 seconds West a distance of 103.52 feet to a 7/8" iron pin found;
thence leaving the West line of Section 14 North 63 degrees 14 minutes 56 seconds East a distance of 305.15 feet to a 5/8" iron pin found;
thence North 70 degree 01 minutes 54 seconds East a distance of 195.02 feet to a 5/8" iron pin found;
thence North 66 degrees 40 minutes 52 seconds East a distance of 572.59 feet to a 5/8" iron pin found;
thence South 85 degrees 58 minutes 41 seconds East a distance of 268.48 feet to a 5/8" iron pin found;
thence South 56 degrees 44 minutes 50 seconds East a distance of 235.88 feet to a 5/8" iron pin found;
thence South 1 degree 53 minutes 20 seconds East a distance of 680.00 feet to the point of beginning, containing 15.000 acres more or less.

The above 15.000 acre survey is intended to describe part of the remaining 29.853 acre surveyed 44.594 acre tract as deeded to Ida Lutz, deed reference Volume 148, Page 564, Hocking County Recorder's Office. This survey was based upon information obtained from tax maps, deed descriptions, previous surveys, and existing monumentation. The reference bearing for this survey is the South line of the Southwest quarter of the Southwest quarter of Section 14 as South 90 degrees 00 minutes 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only. All iron pins set by this survey are 5/8" by 30" and are capped by a 1-1/4" plastic identification cap stamped LPG-6344. The above described property was surveyed by Larry P. Gerstner, Ohio Registered Surveyor No. 6344, on March 26, 1997.



* Approved - Mathematically
Hocking County Engineer's Office

by *M* Date 4-1-97

* CONDITIONAL APPROVAL/TRANSFER: Not to be used as separate building site. Transferred as an independent parcel in future without Planning Commission and Health Dept. approval.

A handwritten signature of Larry P. Gerstner, written in black ink over a horizontal line.

Survey by:

Larry P. Gerstner - Engineering and Surveying
9 East Second Street - Suite A, Logan, Ohio 43138 385-4260

LAUREL 14

PLAT OF A 5.002 ACRE TRACT FOR MARTIN AND GAIL LOHN 5.002 Ac.


Situated in Laurel Township, Hocking County, Ohio; being part of the Northeast quarter of the Southwest quarter of Section 14, Township 12, Range 18.

LEGEND

- 5/8" iron pin with 1-1/4" plastic ID cap stamped SEYMOUR & ASSOC. found
- 5/8"x 30" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 set
- ✱ Point


REFERENCES:

- Tax maps
 - Deed descriptions
 - Previous surveys
 - Existing monumentation
 - Existing public road
- Northeast corner of the Northeast quarter of the Southwest quarter of Section 14



SCALE:

1" = 100'



REFERENCE BEARING:

East line of the Northeast quarter of the Southwest quarter of Section 14 as South 0 degrees 00 minutes 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only.

CERTIFICATION:

I hereby certify that an actual survey was made under my supervision of the premises shown hereon on the 4th day of January, 2001 and that the plat is a correct representation of the premises as described by said survey.

Larry P. Gerstner
Registered Surveyor No. 6344

Survey by:

Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138
(740) 385-4260

SURVEY DESCRIPTION OF A 5.002 ACRE TRACT FOR MARTIN AND GAIL LOHN

Situated in Laurel Township, Hocking County, Ohio; being part of the Northeast quarter of the Southwest quarter of Section 14, Township 12, Range 18; and being more particularly described as follows:

Commencing for reference at a 5/8" iron pin with 1-1/4" plastic ID cap stamped SEYMOUR & ASSOC. found at the Northeast corner of the Northeast quarter of the Southwest quarter of Section 14; thence South 0 degrees 00 minutes 00 seconds West a distance of 662.26 feet to a 5/8" iron pin set, passing a 5/8" iron pin set at a distance of 329.88 feet, and being the point of **Beginning** of the tract of land to be described;

thence continuing South 0 degrees 00 minutes 00 seconds West a distance of 328.08 feet to a 5/8" iron pin set;

thence North 90 degrees 00 minutes 00 seconds West a distance of 668.46 feet to a 5/8" iron pin set, passing a 5/8" iron pin set at a distance of 538.12 feet, and passing the center of Township Road 136, Ucker Road, at a distance of 557.35 feet;

thence North 1 degree 30 minutes 44 seconds East a distance of 328.19 feet to a 5/8" iron pin set;

thence South 90 degrees 00 minutes 00 seconds East a distance of 659.80 to the point of beginning, passing the center of Township Road 136, Ucker Road, at a distance of 220.40 feet, passing a 5/8" iron pin set at a distance of 262.88 feet, containing 5.002 acres more or less, and subject to the public easement of said Township Road 136 and any other public or private easements of record.

The above 5.002 acre survey is intended to describe part of the 40 acre Tract One as deeded to Martin R. and Gail Lohn, deed reference Volume OR8, Page 925, Hocking County Recorder's Office. This survey was based upon information obtained from tax maps, deed descriptions, previous surveys, existing monumentation, and an existing public road. The reference bearing for this survey is the East line of the Northeast quarter of the Southwest quarter of Section 14 as South 0 degrees 00 minutes 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only. All iron pins set by this survey are 5/8" by 30" and are capped by a 1-1/4" plastic identification cap stamped LPG-6344. The above described property was surveyed by Larry P. Gerstner, Ohio Registered Surveyor No. 6344, on January 4, 2001.

by - Mathematically
Hocking County Engineer's Office

LPG DATE 1-12-01

Larry P. Gerstner





Survey by:

Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138 385-4260

LAUREL 14
5.00 AC.

PLAT OF A 5.000 ACRE TRACT FOR MARTIN AND GAIL LOHN

Situated in Laurel Township, Hocking County, Ohio; being part of the Northeast quarter of the Southwest quarter of Section 14, Township 12, Range 18.



Approved - Mathematically
Hocking County Engineer's Office
JM Aw DATE 1-11-01

LEGEND

- 5/8" iron pin with 1-1/4" plastic ID cap stamped SEYMOUR & ASSOC. found
- 5/8"x 30" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 set
- ⊙ 1" OD iron pipe found
- ✱ Point

REFERENCES:

- Tax maps
- Deed descriptions
- Previous surveys
- Existing monumentation
- Existing public road

REFERENCE BEARING:

East line of the Northeast quarter of the Southwest quarter of Section 14 as South 0 degrees 00 minutes 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only.

CERTIFICATION:

I hereby certify that an actual survey was made under my supervision of the premises shown hereon on the 4th day of January, 2001 and that the plat is a correct representation of the premises as described by said survey.

Larry P. Gerstner
Registered Surveyor No. 6344

Survey by: Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138
(740) 385-4260

SURVEY DESCRIPTION OF A 5.000 ACRE TRACT FOR MARTIN AND GAIL LOHN

Situated in Laurel Township, Hocking County, Ohio; being part of the Northeast quarter of the Southwest quarter of Section 14, Township 12, Range 18; and being more particularly described as follows:

Beginning at a 5/8" iron pin with 1-1/4" plastic ID cap stamped SEYMOUR & ASSOC. found at the Northeast corner of the Northeast quarter of the Southwest quarter of Section 14; thence South 0 degrees 00 minutes 00 seconds West a distance of 329.88 feet to a 5/8" iron pin set;

thence North 90 degrees 00 minutes 00 seconds West a distance of 651.03 feet to a 5/8" iron pin set, passing a 5/8" iron pin set at a distance of 234.73 feet, and passing the center of Township Road 136, Ucker Road, at a distance of 358.67 feet;

thence North 1 degree 30 minutes 44 seconds East a distance of 345.86 feet to a damaged 1" OD iron pipe found;

thence South 88 degrees 14 minutes 34 seconds East a distance of 323.43 feet to a 1" OD iron pipe found;

thence South 88 degrees 55 minutes 56 seconds East a distance of 318.68 feet to the point of beginning, containing 5.000 acres more or less, and subject to the public easement of said Township Road 136 and any other public or private easements of record.

The above 5.000 acre survey is intended to describe part of the 40 acre Tract One as deeded to Martin R. and Gail Lohn, deed reference Volume OR8, Page 925, Hocking County Recorder's Office. This survey was based upon information obtained from tax maps, deed descriptions, previous surveys, existing monumentation, and an existing public road. The reference bearing for this survey is the East line of the Northeast quarter of the Southwest quarter of Section 14 as South 0 degrees 00 minutes 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only. All iron pins set by this survey are 5/8" by 30" and are capped by a 1-1/4" plastic identification cap stamped LPG-6344. The above described property was surveyed by Larry P. Gerstner, Ohio Registered Surveyor No. 6344, on January 4, 2001.

Approved - Mathematically
Hocking County Engineer's Office

Handwritten initials DATE 1-11-01

Handwritten signature of Larry P. Gerstner




Survey by:

Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138 385-4260

LAUREL 14
6.622 Ac.

PLAT OF A 6.622 ACRE TRACT FOR MARTIN AND GAIL LOHN

Situated in Laurel Township, Hocking County, Ohio; being part of the Northeast quarter of the Southwest quarter and part of the Southeast quarter of the Southwest quarter, both of Section 14, Township 12, Range 18.



LEGEND

- 5/8" iron pin with 1-1/4" plastic ID cap stamped SEYMOUR & ASSOC. found
- 5/8"x 30" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 set or previously set
- ✕ Point
- ▲ MAG nail previously set


REFERENCES:

- Tax maps
- Deed descriptions
- Previous surveys
- Existing monumentation
- Existing public roads

Northeast corner of the Northeast quarter of the Southwest quarter of Section 14

Approved - Mathematically
Hocking County Engineer's Office

MAW DATE *1-12-01*



REFERENCE BEARING:

East line of the Northeast quarter of the Southwest quarter of Section 14 as South 0 degrees 00 minutes 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only.

CERTIFICATION:

I hereby certify that an actual survey was made under my supervision of the premises shown hereon on the 4th day of January, 2001 and that the plat is a correct representation of the premises as described by said survey.

Larry P. Gerstner
Registered Surveyor No. 6344

Survey by:

Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138
(740) 385-4260

SURVEY DESCRIPTION OF A 6.622 ACRE TRACT FOR MARTIN AND GAIL LOHN

Situated in Laurel Township, Hocking County, Ohio; being part of the Northeast quarter of the Southwest quarter and part of the Southeast quarter of the Southwest quarter, both of Section 14, Township 12, Range 18; and being more particularly described as follows:

Commencing for reference at a 5/8" iron pin with 1-1/4" plastic ID cap stamped SEYMOUR & ASSOC. found at the Northeast corner of the Northeast quarter of the Southwest quarter of Section 14; thence South 0 degrees 00 minutes 00 seconds West a distance of 990.34 feet to a 5/8" iron pin set, passing 5/8" iron pins set at distances of 329.88 feet and 662.26 feet, and being the point of **Beginning** of the tract of land to be described;

thence continuing South 0 degrees 00 minutes 00 seconds West a distance of 324.74 feet to a 5/8" iron pin with 1-1/4" plastic ID cap stamped SEYMOUR & ASSOC. found;

thence North 88 degrees 39 minutes 47 seconds West a distance of 676.80 feet to a 5/8" iron pin previously set and passing a 5/8" iron pin previously set at a distance of 628.00 feet;

thence South 0 degrees 18 minutes 08 seconds West a distance of 48.48 feet to a MAG nail previously set in the center of Township Road 232, Rocky Fork Road;

thence with the center of said Township Road 232 the following five bearings and distances;


- 1) North 72 degrees 14 minutes 43 seconds West a distance of 39.09 feet to a MAG nail previously set;
- 2) South 45 degrees 24 minutes 17 seconds West a distance of 92.28 feet to a MAG nail previously set;
- 3) South 73 degrees 49 minutes 17 seconds West a distance of 39.50 feet to a MAG nail previously set;
- 4) North 71 degrees 55 minutes 43 seconds West a distance of 58.58 feet to a MAG nail previously set;
- 5) North 62 degrees 40 minutes 43 seconds West a distance of 214.19 feet to a MAG nail previously set in the edge of said Township Road 232;

thence leaving said Township Road 232 North 57 degrees 09 minutes 32 second East a distance of 468.88 feet to a 5/8" iron pin previously set and passing a 5/8" iron pin previously set at a distance of 9.57 feet;

thence North 1 degree 30 minutes 44 seconds East a distance of 50.57 feet to a 5/8" iron pin set;

thence South 90 degrees 00 minutes 00 seconds East a distance of 668.46 feet to the point of beginning, passing the center of Township Road 136, Ucker Road, at a distance of 111.11 feet, and a 5/8" iron pin set at a distance of 130.34 feet, containing 6.622 acres more or less, and subject to the public easements of said Township Roads 136 and 232 and any other public or private easements of record.

The above 6.622 acre survey is intended to describe part of the 40 acre Tract One and all of the .56 acre Tract Two both as deeded to Martin R. and Gail Lohn, deed reference Volume OR8, Page 925, Hocking County Recorder's Office. This survey was based upon information obtained from tax maps, deed descriptions, previous surveys, existing monumentation, and existing public roads. The reference bearing for this survey is the East line of the Northeast quarter of the Southwest quarter of Section 14 as South 0 degrees 00 minutes 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only. All iron pins set by this survey or previously set are 5/8" by 30" and are capped by a 1-1/4" plastic identification cap stamped LPG-6344. The above described property was surveyed by Larry P. Gerstner, Ohio Registered Surveyor No. 6344, on January 4, 2001.



Hocking County Engineer's Office.

LG

1-12-01

Larry P. Gerstner

Survey by:

Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138 385-4260

LAUREL 14
5.001Ac.

PLAT OF A 5.001 ACRE TRACT FOR MARTIN AND GAIL LOHN



Situated in Laurel Township, Hocking County, Ohio; being part of the Northeast quarter of the Southwest quarter of Section 14, Township 12, Range 18.

LEGEND

- 5/8" iron pin with 1-1/4" plastic ID cap stamped SEYMOUR & ASSOC. found
- 5/8"x 30" iron pin with 1-1/4" plastic ID cap stamped LPG-6344 set
- ✱ Point

REFERENCES:

- Tax maps
- Deed descriptions
- Previous surveys
- Existing monumentation
- Existing public road



REFERENCE BEARING:

East line of the Northeast quarter of the Southwest quarter of Section 14 as South 0 degrees 00 minutes 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only.

CERTIFICATION:

I hereby certify that an actual survey was made under my supervision of the premises shown hereon on the 4th day of January, 2001 and that the plat is a correct representation of the premises as described by said survey.

Larry P. Gerstner
Registered Surveyor No. 6344

Survey by:

Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138
(740) 385-4260

SURVEY DESCRIPTION OF A 5.001 ACRE TRACT FOR MARTIN AND GAIL LOHN

Situated in Laurel Township, Hocking County, Ohio; being part of the Northeast quarter of the Southwest quarter of Section 14, Township 12, Range 18; and being more particularly described as follows:

Commencing for reference at a 5/8" iron pin with 1-1/4" plastic ID cap stamped SEYMOUR & ASSOC. found at the Northeast corner of the Northeast quarter of the Southwest quarter of Section 14; thence South 0 degrees 00 minutes 00 seconds West a distance of 329.88 feet to a 5/8" iron pin set and being the point of **Beginning** of the tract of land to be described;

thence continuing South 0 degrees 00 minutes 00 seconds West a distance of 332.38 feet to a 5/8" iron pin set;

thence North 90 degrees 00 minutes 00 seconds West a distance of 659.80 feet to a 5/8" iron pin set, passing a 5/8" iron pin set at a distance of 396.92 feet, and passing the center of Township Road 136, Ucker Road, at a distance of 439.40 feet;

thence North 1 degree 30 minutes 44 seconds East a distance of 332.49 feet to a 5/8" iron pin set;

thence South 90 degrees 00 minutes 00 seconds East a distance of 651.03 to the point of beginning, passing the center of Township Road 136, Ucker Road, at a distance of 292.36 feet, passing a 5/8" iron pin set at a distance of 416.30 feet, containing 5.001 acres more or less, and subject to the public easement of said Township Road 136 and any other public or private easements of record.

The above 5.001 acre survey is intended to describe part of the 40 acre Tract One as deeded to Martin R. and Gail Lohn, deed reference Volume OR8, Page 925, Hocking County Recorder's Office. This survey was based upon information obtained from tax maps, deed descriptions, previous surveys, existing monumentation, and an existing public road. The reference bearing for this survey is the East line of the Northeast quarter of the Southwest quarter of Section 14 as South 0 degrees 00 minutes 00 seconds West. Bearings are based upon an assumed meridian and are to denote angles only. All iron pins set by this survey are 5/8" by 30" and are capped by a 1-1/4" plastic identification cap stamped LPG-6344. The above described property was surveyed by Larry P. Gerstner, Ohio Registered Surveyor No. 6344, on January 4, 2001.

Reviewed - Mathematically
Hocking County Engineer's Office

MAW DATE 1-11-01

Larry P. Gerstner



Survey by:

Larry P. Gerstner - Engineering and Surveying
9 East Second Street, Suite A, Logan, Ohio 43138 385-4260

Laurel 14

DESCRIPTION OF A 50.84 ACRE PARCEL OF LAND SITUATED IN THE SOUTHEAST QUARTER OF THE SOUTHWEST QUARTER OF SECTION 14 AND NORTHEAST QUARTER OF THE NORTHWEST QUARTER OF SECTION 23 AND THE NORTHWEST QUARTER OF THE NORTHEAST QUARTER OF SECTION 23, TOWNSHIP 12, RANGE 18, LAUREL TOWNSHIP, HOCKING COUNTY, OHIO AND BEING MORE ACCURATELY DESCRIBED AS FOLLOWS:

BEGINNING AT A STONE IN THE SOUTHWEST CORNER OF THE SOUTHEAST QUARTER OF THE SOUTHWEST QUARTER OF SECTION 14; THENCE NORTH 4-57 EAST A DISTANCE OF 276.38 FEET TO AN IRON PIN THE TRUE PLACE OF BEGINNING ; THENCE NORTH 4-57 EAST A DISTANCE OF 1052.89 FEET TO A CORNER POST; THENCE SOUTH 84-00 EAST A DISTANCE OF 303.81 FEET TO A SPIKE IN THE CENTERLINE OF TOWNSHIP ROAD 232; THENCE WITH THE CENTERLINE OF SAID ROAD THE FOLLOWING (11) COURSES AND DISTANCES:


- (1) SOUTH 57-17 EAST A DISTANCE OF 214.19 FEET TO A SPIKE,
- (2) SOUTH 66-32 EAST A DISTANCE OF 58.58 FEET TO A SPIKE,
- (3) NORTH 79-13 EAST A DISTANCE OF 39.50 FEET TO A SPIKE,
- (4) NORTH 50-48 EAST A DISTANCE OF 92.28 FEET TO A SPIKE,
- (5) SOUTH 66-51 EAST A DISTANCE OF 29.27 FEET TO A SPIKE,
- (6) SOUTH 3-30 WEST A DISTANCE OF 166.51 FEET TO A SPIKE,
- (7) SOUTH 16-27 EAST A DISTANCE OF 60.47 FEET TO A SPIKE,
- (8) SOUTH 35-38 EAST A DISTANCE OF 179.12 FEET TO A SPIKE,
- (9) SOUTH 48-25 EAST A DISTANCE OF 166.22 FEET TO A SPIKE,
- (10) SOUTH 31-39 EAST A DISTANCE OF 254.20 FEET TO A SPIKE,
- (11) SOUTH 45-27 EAST A DISTANCE OF 82.61 FEET TO A SPIKE, IN THE CENTERLINE OF TOWNSHIP ROAD 232; THENCE SOUTH 56-48 WEST A DISTANCE OF 116.31 FEET TO A FENCE POST; THENCE SOUTH 27-24 EAST A DISTANCE OF 676.08 FEET TO A POST; THENCE NORTH 82-00 EAST A DISTANCE OF 121.69 FEET TO A POST; THENCE SOUTH 17-47 EAST A DISTANCE OF 110.18 FEET TO AN IRON PIN IN THE CENTERLINE OF STREAM; THENCE WITH THE CENTERLINE OF SAID STREAM THE FOLLOWING (8) COURSES AND DISTANCES:

- (1) SOUTH 43-22 EAST A DISTANCE OF 214.31 FEET TO AN IRON PIN,
- (2) SOUTH 23-26 EAST A DISTANCE OF 110.97 FEET TO AN IRON PIN,
- (3) SOUTH 27-32 WEST A DISTANCE OF 198.35 FEET TO AN IRON PIN,
- (4) SOUTH 11-25 WEST A DISTANCE OF 128.73 FEET TO AN IRON PIN,
- (5) SOUTH 19-50 WEST A DISTANCE OF 134.87 FEET TO AN IRON PIN,

(6) SOUTH 9-59 EAST A DISTANCE OF 202.20 FEET TO AN IRON PIN,
 (7) SOUTH 13-12 WEST A DISTANCE OF 306.43 FEET TO AN IRON PIN,
 (8) SOUTH 9-27 EAST A DISTANCE OF 20.00 FEET TO AN IRON PIN,; THENCE NORTH 85-07 WEST
 A DISTANCE OF 769.41 FEET TO AN IRON PIN; THENCE NORTH 11-16 EAST A DISTANCE OF 584.19 FEET
 TO AN IRON PIN; THENCE ^{NORTH} 35-51 EAST A DISTANCE OF 601.00 FEET TO AN IRON PIN; THENCE SOUTH 89-41
 WEST A DISTANCE OF 186.33 FEET TO AN IRON PIN; THENCE NORTH 72-58 WEST A DISTANCE OF 168.97
 FEET TO AN IRON PIN; THENCE NORTH 53-49 WEST A DISTANCE OF 108.55 FEET TO AN IRON PIN; THENCE
 NORTH 68-42 WEST A DISTANCE OF 116.30 FEET TO AN IRON PIN; THENCE NORTH 49-57 WEST A DISTANCE
 OF 135.82 FEET TO AN IRON PIN; THENCE NORTH 50-11 WEST A DISTANCE OF 175.53 FEET TO AN IRON PIN;
 THENCE NORTH 74-48 WEST A DISTANCE OF 168.53 FEET TO AN IRON PIN; THENCE NORTH 47-19 WEST A
 DISTANCE OF 161.02 FEET TO AN IRON PIN; THENCE NORTH 67-22 WEST A DISTANCE OF 107.40 FEET TO
 AN IRON PIN; THENCE NORTH 42-43 WEST A DISTANCE OF 89.99 FEET TO AN IRON PIN; THENCE NORTH 40-37
 WEST A DISTANCE OF 48.87 FEET TO AN IRON PIN THE TRUE PLACE OF BEGINNING AND CONTAINING 50.84
 ACRES OF LAND SUBJECT TO ALL EASEMENTS AND RIGHT-OF-WAYS OF RECORD WITH 29.74 ACRES BEING IN
 THE SOUTHEAST QUARTER OF THE SOUTHWEST QUARTER OF SECTION 23 AND 10.90 ACRES BEING IN THE NORTH
 EAST QUARTER OF THE NORTHWEST QUARTER OF SECTION 23 AND 10.20 ACRES BEING IN THE NORTHWEST
 QUARTER OF THE NORTHEAST QUARTER OF SECTION 23.

APPROVED
 HOCKING COUNTY ENGINEER'S OFFICE
 DATE 10-23-76
 BY RS

Prepared 10-28-76
W. R. Miller 25 840



E.J. Frey sellout
 Pt E 1/2 NE 1/4 Sec 14 Laurel Twp.
 Jackson County Ohio
 A.W. Seabright
 Apr 4-19 1967

Donated, June 1982, by
 ALBERT W. SEABRIGHT, P.E., P.C.
 COUNTY ENGINEER 1949 - 1964

Am earlier description was voided
 A.W. Seabright
 Apr 26 1967

8" Pignut Hickory N64°45'E 2365
 20" Ash N19°E 47.8'

20" WO N22°E 52.3'
 36" Bptar 564.8 32.30
 (dying)

SW Cor E 1/2
 NE 1/4
 Sec 14

LAUREL 14

ALBERT W. SEABRIGHT
MINING ENGINEER
LOGAN, OHIO

N 79° 04' 45" W
145.52'

S 81° 34' 30" W
206.16'

S 91° 21' W 243.40'

S 59° 08' W 662.66'
- Q Public Road

S 58° 00' W 350.01'

P.P. on East side Road 42.25 distant
+ 26.26 on North side Road 26.30'

28' Twin W.O. N 16° E 38.2'
1 1/2" W. Cherry N 39° E 72.5'

E. J. Frey s & lot
P + E 1/2 NE 1/4 Sec 14 Louis Twp.
Hocking County Ohio

49,9060 ac.

10" Triple Point N 72° W 48.40'
15" Beech N 70° 30' W 42.6'
12" Walnut North 462'

Donated, June 1982, by
ALBERT W. SEABRIGHT, P.E., P.C.
COUNTY ENGINEER 1949 - 1984

Albert W. Seabright
Apr 19 1986

8" Redst Hecoy N 64° 35' E 23.65'
20" Ash N 19° E 298'

SNC
E 1/2 NE 1/4
Sec 14

S 84° 19' E 1365.07'

20" W.O. N 22° E 623'
36" Polar S 64° E 32.00'
(approx)

IP.

IP.

IP.

IP.


1199.97'

N 6° 06' 30" E 1210.67'

IP.

N 6° 12' 40" E 580.01'

IP.



E. T. Frey sellout
 P & E 1/2 NE 1/4 Sec 14 Laurel Twp.
 Hocking County Ohio
 47.7060 ac.

Donated, June 1982, by
 ALBERT W. SEABRIGHT, P.E., P.C.
 COUNTY ENGINEER 1949 - 1984

Albert W. Seabright
 Made over 1967
 Apr 19 1966

28" Twin W.C. N 16° E 38.2'
 14" W. Cherry N 37° E 72.5'

P.P. on South side Road 42.25' distant
 H. Peto on North side Road 26.50'

10" Triple Point N 72° W 48.40'
 10" Beech 170° 20' W 42.6'
 14" Walnut 141° 463'

8" Bg Nut Hickory N 64° 45' E 23.65'
 20" Ash N 19° E 478'

SW Cor
 E 1/2 NE 1/4
 Sec 14

20" N.O. N 22° E 52.3'
 36" B. Jar 564 E 32.30'
 (adjus)

584°-11' E 1365.07

11'

E. J. FREY
Pt. E $\frac{1}{2}$ NE $\frac{1}{4}$ Sec. 14, Laurel T12, R18

Being a part of the East half of the Northeast quarter of Section 14, Laurel Township, T12N, R18W, Hocking County and State of Ohio, and further described as follows: Commencing at an iron pin marking the southwest corner of said half quarter section, an 8" Pig Nut Hickory bears N64 degrees - 45 minutes East 23.65 feet and a 20" Ash bears North 19 degrees - East 47.8 feet; thence on the south line of said half quarter section, South 84 degrees - 17 minutes East 1365.07 feet to an iron pin, a 20" White Oak bears North 22 degrees East 52.3 feet and a 36" Poplar (dying) bears South 64 degrees East 32.30 feet; thence North 6 degrees - 12 minutes - 40 seconds East 580.01 feet to an iron pin, a 10" triple sprouted Pig Nut Hickory bears North 72 degrees West 48.40 feet, a 10" Beech bears North 20 degrees - 30 minutes West 42.6 feet and a 14" Walnut bears North 46.3 feet in the fence row; thence North 6 degrees - 06 minutes - 30 seconds East 1210.67 feet to the center line of the public road and passing an iron pin at 1179.97 feet; thence on the said center line of public road the following courses, North 79 degrees - 04 minutes - 45 seconds West 145.52 feet to a point; thence South 81 degrees - 34 minutes - 30 seconds West 206.16 feet to a spike; thence South 71 degrees - 21 minutes West 243.40 feet to a spike; thence South 59 degrees - 08 minutes West 662.66 feet to an iron pin, a power pole on the south side said road is 42.25 feet distant, and a house power pole on the north side of said road is 26.50 feet distant; thence South 58 degrees - 24 minutes West 350.01

feet to an iron pin set in the west line of said half quarter section, a 28" Twin White Oak bears North 16 degrees East 38.2 feet and a 14" twin Wild Cherry bears North 37 degrees East 72.5 feet; thence on said west line of the half quarter section, South 5 degrees - 47 minutes - 30 seconds West 1045.94 feet to the place of beginning, containing 47.7060 Acres, more or less, but subject to the rights of the public road and electric utility company.

This description prepared from survey by Albert Seabright April 4-19, 1967.

NOTE TO ATTORNEY -

I do not have the name of the Electric Company.

DESCRIPTION OF A 5.12 ACRE PARCEL OF LAND SITUATED IN THE NORTHWEST QUARTER OF SECTION 14, TOWNSHIP 12, RANGE 18, LAUREL TOWNSHIP, HOCKING COUNTY, OHIO AND BEING MORE ACCURATELY DESCRIBED AS FOLLOWS:

BEGINNING AT AN IRON PIN IN THE NORTHWEST CORNER OF SECTION 14; THENCE SOUTH 89°-59'-30" EAST A DISTANCE OF 67.18 FEET TO AN IRON PIN; THENCE SOUTH 0°-01' EAST A DISTANCE OF 275.00 FEET TO AN IRON PIN THE TRUE PLACE OF BEGINNING; THENCE SOUTH 45°-19' EAST A DISTANCE OF 724.13 FEET TO A SPIKE IN THE CENTERLINE OF WILDCAT ~~ROAD~~ ^{ROAD}; THENCE SOUTH 53°-38' WEST A DISTANCE OF 200.00 FEET TO A SPIKE; THENCE SOUTH 53°-59' WEST A DISTANCE OF 328.72 FEET TO A SPIKE; IN THE INTERSECTION OF WILDCAT ROAD AND COUNTY ROAD 4; THENCE WITH THE CENTERLINE OF COUNTY ROAD 4 THE FOLLOWING (3) COURSES AND DISTANCES:

- (1) NORTH 63°-14' WEST A DISTANCE OF 89.71 FEET TO A SPIKE,
- (2) NORTH 63°-56' WEST A DISTANCE OF 27.67 FEET TO A SPIKE,
- (3) NORTH 38°-40' WEST A DISTANCE OF 43.85 FEET TO A SPIKE; THENCE NORTH 0°-01' WEST A DISTANCE OF 756.79 FEET TO AN IRON PIN THE TRUE PLACE OF BEGINNING AND CONTAINING 5.12 ACRES OF LAND SUBJECT TO ALL EASEMENTS AND RIGHT-OF-WAYS OF RECORD.

A SURVEY OF THE ABOVE WAS MADE IN JULY 1979 BY W.R. NORTON REGISTERED SURVEYOR 5465.

Approved - Mathematically
Hocking County Engineer's Office
By W.R. Norton Date 8-13-79

BEING PART OF A 22.99 ACRE TRACT,
O.R. 132, PG. 792, & D.V. 215, PG. 594 IN
THE EAST HALF OF THE NORTHEAST
QUARTER OF SECTION 14, T12, R18,
LAUREL TWP., HOCKING CO.,
STATE OF OHIO

BASIS OF BEARINGS: MAY 1980 SURVEY
BY J.A. MATHIAS OF A 9.46 ACRE TRACT,
D.V. 191, PG. 885

INFORMATION USED FOR THIS SURVEY
WAS TAKEN FROM TAX MAPS, TOPO MAPS,
DEEDS, AND EXISTING MONUMENTATION
FOUND.

Approved Mathematically
Hocking County Engineer's Office
BY *Hws* DATE *1-14-02*

CONDITIONAL APPROVAL/
TRANSFER NOT to be used as
separate building site or
transferred as an independent
parcel in the future without
Planning Commission and/or
Health Department approval


RALPH COKONOUGH
215-594, OR132-792
22.99 AC.

LEGEND


- = 5/8" REBAR FOUND
- = 5/8" REBAR SET w/ PLAS I.D. CAP
- = P.K. NAIL FOUND
- = P.K. NAIL SET

PLAT SHOWING
SURVEY OF A 1.000 ACRE TRACT
FOR DANNY AND AMELIA CALHOUN

CURTIS & SHARON
HAYWOOD
OR 85 - 485 47.71 AC.



P.O.B.
DANNY &
AMELIA
CALHOUN
OR144-388
1.84 AC.



James R. Cartwright date: *12-20-01*
JAMES R. CARTWRIGHT
OHIO REGISTERED SURVEYOR #7486

Laurel
Sec. 14
1.000 Ac.

REAL ESTATE DESCRIPTION

FROM: Ralph Cokonougher

TO: Danny and Amelia Calhoun

The following real estate situated in the County of Hocking in State of Ohio and in the Township of Laurel and being bounded and described as follows:

Being part of a 22.99 acre tract, O.R. 132, page 792, and D.V. 215, page 594 in the East half of the Northeast quarter of Section 14, T12, R18, Congress Lands, and being more particularly described as follows;

Beginning for reference at a 5/8" rebar marking the most Northerly corner of a 1.84 acre tract, O.R, 144, page 388;

Thence South 31 degrees 22 minutes 06 seconds East 241.32 feet to a 5/8" rebar set with plastic I.D. cap, said rebar marking the principal place of beginning of the tract herein to be described;

Thence continuing South 31 degrees 22 minutes 06 seconds East 209.43 feet to a P.K. nail set in the centerline of County Road 4, passing a 5/8" rebar found at 172.43 feet;

Thence North 59 degrees 08 minutes 00 seconds East 208.00 feet in the centerline of said County Road 4 to a P.K. nail set;

Thence North 31 degrees 22 minutes 06 seconds West 209.43 feet leaving the centerline of said County Road 4 to a 5/8" rebar set with plastic I.D. cap, passing a 5/8" rebar set with plastic I.D. cap at 37.00 feet;

Thence South 59 degrees 08 minutes 00 seconds West 208.00 feet to the principal place of beginning, containing 1.000 acres.

Basis of bearings: May 1980 survey by J.A. Mathias of a 9.46 acre tract. D.V. 191,
page 885.

This description was prepared from an actual survey performed by James R.
Cartwright, Ohio Registered Surveyor #7486.

Approved - Mathematically
Hocking County Engineer's Office


BY JWB DATE 1-14-02

CONDITIONAL APPROVAL/
TRANSFER NOT to be used as
separate building site or
transferred as an independent
parcel in the future without
Planning Commission and/or
Health Department approval

James R. Cartwright date: 1-14-02
James R. Cartwright
Ohio Registered Surveyor #7486



14/4
Sec 15
house



Description:



Being a part of section 14 and section 15 T 12 R 18 (Laurel) Hocking County Ohio and bound as follows: Beginning at an iron pin (I.P.) in quarter section line 65.0 ft east of the S.W. corner of the N.W. quarter of section 14; thence N 9° 36' W 237.21 ft. to an I.P.; thence N 37° 29' W 827.28 ft. to an I.P.; thence N 81° 39' W. 522.36 ft. to a point in road, passing an I.P. at 479.76 ft.; thence with the center line of road the following: N 15° 44' E 327.96 ft.; thence N 50° 54' E 504.2 ft.; thence N 77° 51' E 148.86 ft.; thence N 51° 26' E 358.50 ft.; thence S 65° 27' E 105.33 ft.; thence S 20° 07' E 261.70 ft.; thence S 61° 46' E 92.75 ft.; thence N 84° 14' E 340.40 ft. to an I.P.; thence leaving road, S 0° 12' E 1560.54 ft. to a stone in quarter section line; thence West 474.95 ft. to the place of beginning, containing, 36.76 ac - there being approx. 18.38 ac in sec 14 and 18.38 ac in sec 15.

PART OF SURVEY
IN SEC 14 & SEC 15 LAUREL
HOCKING COUNTY O.
for Fuel Corp Rockbridge Rt 1
Scale 1" = 200' Demand, Sifford & Assoc.
March 1970

THIS PAGE
LEFT BLANK
INTENTIONALLY

THIS PAGE
LEFT BLANK
INTENTIONALLY

SEC. 14 & 15
 Laurel



PLAT OF
 5.20 Acres, 1.59 Acres
 in the NW. 1/4 of Section 14,
 and 3.61 Acres in the NE. 1/4
 of Section 15, T12, R18,
 Laurel Township, Hocking
 County - Ohio

Approved - Mathematically *
 Hocking County Engineer's Office
 By AW FN Date 6-8-79

* NOT TO BE TRANSFERRED
 as is until Approved
 By Planning Commission

SUBDIVISION REGULATIONS WAIVED
 BY AW DATES 5-30-80

Surveyed by:
 W. R. Horton
 Reg. Sur. 5465
 May 1979

DESCRIPTION OF A 5.20 ACRE PARCEL OF LAND SITUATED IN THE NORTHWEST QUARTER OF SECTION 14 AND THE NORTHEAST QUARTER OF SECTION 15, TOWNSHIP 12, RANGE 18, LAUREL TOWNSHIP, HOCKING COUNTY, OHIO AND BEING MORE ACCURATELY DESCRIBED AS FOLLOWS:

BEGINNING AT AN IRON PIN IN THE NORTHEAST CORNER OF SECTION 15; THENCE NORTH $89^{\circ}-59'-30''$ EAST A DISTANCE OF 67.18 FEET TO AN IRON PIN; THENCE SOUTH $0^{\circ}-01'$ EAST A DISTANCE OF 1031.79 FEET TO A SPIKE IN THE CENTERLINE OF COUNTY ROAD 4; THENCE WITH THE CENTERLINE OF SAID ROAD THE FOLLOWING (6) COURSES AND DISTANCES:

- (1) NORTH $26^{\circ}-39'$ WEST A DISTANCE OF 51.72 FEET TO A SPIKE,
- (2) NORTH $20^{\circ}-29'$ WEST A DISTANCE OF 172.07 FEET TO A SPIKE,
- (3) NORTH $43^{\circ}-32'$ WEST A DISTANCE OF 66.87 FEET TO A SPIKE,
- (4) SOUTH $85^{\circ}-29'$ WEST A DISTANCE OF 69.70 FEET TO A SPIKE,
- (5) SOUTH $62^{\circ}-36'$ WEST A DISTANCE OF 51.72 FEET TO A SPIKE,
- (6) SOUTH $45^{\circ}-45'$ WEST A DISTANCE OF 43.80 FEET TO A SPIKE,; THENCE NORTH $0^{\circ}-36'$ EAST A DISTANCE OF 828.70 FEET TO AN IRON PIN; THENCE NORTH $89^{\circ}-21'$ EAST A DISTANCE OF 200.32 FEET TO AN IRON PIN THE TRUE PLACE OF BEGINNING AND CONTAINING 5.20 ACRES OF LAND WITH 1.59 BEING IN SECTION 14 AND 3.61 ACRES BEING IN SECTION 15 SUBJECT TO ALL EASEMENTS AND RIGHT-OF-WAYS OF RECORD.

A SURVEY OF THE ABOVE WAS MADE IN MAY 1979 BY W.R. HORTON REGISTERED SURVEYOR 5465.

Approved - Mathematically *
Hocking County Engineer's Office
By AW FN Date 6-8-79


* NOT TO BE TRANSTFERRED
until approved By Planning
Commission.

SUBDIVISION REGULATIONS WAIVED

BY AW DATE 5-30-80

112-118
KNOX - 40 A±

BEGIN - N.W. COR.
OF NE 1/4 OF NE 1/4
OF SEC # 14 - LAUREL TWP.



1,599 A±

167-450
HOLLOWAY
FELDSTEIN
7.86 A±

S-84°58'E - 1071.13

158-475
BEVINS - 25.29 A±

IP FOUND
@ NE COR
SEC # 14
LAUREL TWP.
HOCKING CO. OH.

PLAT FOR CHARLES KNOX
AND THOMAS BEVINS
TRACT TAKEN OUT OF BEVINS-158-475
BEING IN NE 1/4 OF NE 1/4 OF SEC # 14
LAUREL TWP. - HOCKING CO. OHIO
T-12 R-18
SCALE - 1" = 100'
MAY - 1980

J.A. Mathias

Approved - Mathematically
Hocking County Engineer's Office
By *[Signature]* Date 6-10-80

SUBDIVISION REGULATIONS WAIVED *

BY *[Signature]* DATE 6-10-80

* NOT to used as a separate building site or transferred as an independent parcel in the future.

LAUREL 14

Survey for Thomas Bevins to be conveyed to Charles Knox.

Being a part of the Northeast Quarter of the Northeast Quarter of Section 14, Township 12, Range 18, Laurel Township, Hocking County, Ohio, as Recorded in Record of Deeds, Recorders Office Book 158, Page 475 and described as follows: Beginning at the Northwest Corner of the Northeast Quarter of the Northeast Quarter of said Section 14, Township 12, Range 18, thence with the said Section line South 84 degrees 58 minutes East 300.77 feet to an iron pin; thence leaving said Section line, South 7 degrees 03 minutes West, 227.30 feet to an iron pin; thence North 87 degrees 16 minutes West 297.18 feet to an iron pin; thence North 6 degrees 02 minutes East 239.13 feet to the place of beginning, containing 1.599 Acres more or less.


Survey supervised by

J.A. Mathias

J.A. Mathias, Surveyor State of Ohio s-3259.

Surveyed in May, 1980.

Approved - Mathematically
Hocking County Engineer's Office
By: ASC FN Date 6-10-80



SUBDIVISION REGULATIONS WAIVED *

BY ASC DATE 6-10-80

* Not to be used as a separate building site or transferred as an independent parcel in the future.

LAUREL 77

ALBERT W. SEABRIGHT, P.E.
104 NORTH STREET
LOGAN, OHIO 45138

Witness to IP
8" White Oak $S 62^{\circ} 50' E$ 22.0'
10" Maple South 17.5'
12" Leaning Wild Cherry
 $39^{\circ} 30' W$ 9'

Approx. Parallel to
North Section Line 2
 $N 87^{\circ} 16' W$ 296.97'

Witness to IP
16" Quaking Ash $N 9^{\circ} 30' E$ 20.25'
6" Maple $S 82^{\circ} 30' W$ 24.85'
5" Poplar $S 30^{\circ} W$ 12.5'

Donated, June 1982, by
ALBERT W. SEABRIGHT, P.E., P.S.
COUNTY ENGINEER 1949 - 1964

APPROVED
HOCKING COUNTY ENGINEER'S OFFICE
DATE 4-26-77
BY A.S.

West Line East Half Section Line

$56^{\circ} 02' - 22" W$ 1296.41'

PT E 1/2 NE 1/4 Section 14 Laurel Twp T 12N., R 18W.
7.8639 ac. ±

$N 7^{\circ} 02' - 48" E$ 1100.00'

Approx. Parallel to East Section Line 3

Magnetic North 1966

Witness to IP
Power Pole South West 42.25'
House Power Pole North West 26.50'

Witness to IP
28" White Oak $N 16^{\circ} E$ 38.2'
14" Twin Wild Cherry $N 37^{\circ} E$ 22.5'

Start
Route County Road
 $N 58^{\circ} 24' E$ 350.01'

PLAT to ACCOMPANY DEED DESCRIPTION.
PAUL MATTHAES TRACT
For LAPPEN & LILLEY, ATTORNEYS AT LAW.
Set iron pins at corners, Survey Dec 12-15 1966 for
Paul Matthaes Tract, Vol 109 pg 290 Apr 4 1966 (in error,
in accordance with Vol 108 pg 348, Hocking County
Deed Record.
Plat shows Bearing & Distance for each side, part
of which are not cited in either Deed Description.
PT E 1/2 NE 1/4 Laurel Twp. T 12N., R 18W., Hocking County Ohio
Survey by A.W. Seabright P.E.
Apr 23-25 1977



Albert W. Seabright 753
Apr 26 1977
File 30-351

Scale 1" = 200'

LAUREL

Approximately Parallel to North Line Sec 14

Wit to I.P.
8" White Oak
562° 50' E 22.0'
10" Maple South 19.5'
12" Leaning Wild Cherry
59° 38' W 9'

Schematic Sketch
Survey 9ac Tract of Land
East 1/2 NE 1/4 Sec 14 Laurel Twp
Hocking County Ohio
As recorded Vol 108 pg 348
For Paul Matthaes
Original Pins Not Found.
Set 4 Iron Pins
Sketch shows Numbered Survey Sta.
and distance to Property Lines

West Line E 1/2 NE 1/4 Sec 14 Laurel Twp

Part E 1/2 NE 1/4 Sec 14 Laurel Twp
Hocking County Ohio
7.8653 acres

Approximately Parallel to East Line of Sec 117° 02' 48" E 1098.16'

Wit to I.P.
28" White Oak
N 16° E 38.2'
14" Twin Wild Cherry
N 39° E 72.5'

N 58° 24' E
350.01

House PP
26.50

12.25
I.P.

County Road

Wit to I.P.
16" Quaking Ash
N 9° 30' E 20.25'
6" Maple
58° 2' 30" W 24.85'
5" Poplar
53° 30' W 12.5'

1.24'
1.24' off.
1.09'
1.09'
1.09'
1.09'
0.41'
0.41'
0.41'
138 Online



Albert W. Seabright
Dec 12 - 15 1966

Donated, June 1982, by
ALBERT W. SEABRIGHT, P.E., P.C.
COUNTY ENGINEER 1949 - 1982

ALBERT W. SEABRIGHT, P.E.

104 NORTH STREET
LOGAN, OHIO 43118

Deed Description for Paul matthaes Vol. 109/290
Pt. E $\frac{1}{2}$ NE $\frac{1}{4}$ Section 14, Laurel Twp., T12N, R18W, Hocking County, Ohio
repared from survey Dec. 12-15, 1966, setting iron pins according to Vol. 109/290

Being the Grantor's tract of land, situate the East half of the Northeast Quarter of Section 14, Laurel Township, T12N, R18W, Hocking County and State of Ohio, and recorded in Vol. 109, Page 290 (in error) reference Vol. 108, Page 348, both volumes Hocking County Deed Record, and now further described from survey of Dec. 12-15, 1966, as:

Beginning at the intersection of the West line of said East half of the Northeast Quarter and the center line of Starr Route, County Road #4, and also marked by an iron pin from which a 28-inch White Oak bears North 16 degrees East 38.2 feet, and a 14-inch twin Wild Cherry bears North 37 degrees East 72.5 feet; thence with the long chord of the said road center line, North 58 degrees - 24 minutes East 350.01 feet to an iron pin, a power pole to the southwest is 42.5 feet distant and a house power pole to the northwest is 26.5 feet distant; thence leaving said center line and on a line parallel to the east line of said Section 14, North 7 degrees - 02 minutes - 48 seconds East 1100.00 feet to a point and passing an iron pin at 1098.76 feet, a 16-inch Quaking Ash bears North 9 degrees - 30 minutes East 20.25 feet, a 6-inch Maple bears South 82 degrees - 30 minutes West 24.85 feet, and a 5-inch Poplar bears South 30 degrees West 12.5 feet; thence on a line approximately parallel with the north line of said Section 14, North 87 degrees - 16 minutes West 296.97 feet to a point on said west line of the East half of the Northeast Quarter; thence South 6 degrees - 02 minutes - 22 seconds West 1296.35 feet to the place of beginning and passing an iron pin at 1.24 feet, an 8-inch White Oak bears South 62 degrees - 50 minutes East 22.0 feet, a 10-inch Maple bears South 17.5 feet and a 12-inch leaning Wild Cherry bears South 9 degrees - 30 minutes West 9.0 feet, and containing 7.8639 acres, more or less.

This deed description was prepared by Albert W. Seabright, P.E. from survey made by him Dec. 12-15, 1966.


Cancel 14

P. O. Box 26

GEORGE F. SEYMOUR & ASSOCIATES
Engineering, Surveying & Mapping Service
Logan, Ohio 43138

Phone: 614/385-4349

BEING A PART OF THE
WEST HALF OF THE NORTHEAST
QUARTER OF SEC. 14
T12N, R18W, LAUREL TWP
HOCKING CO.



N
SCALE: 1" = 20'
O = IRON PIN
● = FENCE POST

SURVEYED BY

George F. Seymour
REGISTERED SURVEYOR NO. 6544

B. BURKEY

SOUTHEAST CORNER
OF THE WEST HALF OF
THE NORTHEAST QUARTER
OF SEC. 14, T12N, R18W

APPROVED
HOCKING COUNTY ENGINEER'S OFFICE
DATE 4-11-22
BY [Signature]

Description of Survey for Carl Fouch

Being a part of the west half of the Northeast Quarter of Section 14, T12N, R18W, Laurel Township, Hocking County, State of Ohio, and more particularly described as follows:

Beginning at an iron pin set on the southeast corner of the west half of the Northeast Quarter of Section 14, said iron pin being referenced by an 8" Pig Nut Hickory which bears North $64^{\circ} 45'$ East 23.65 feet and a 20" Ash which bears North 19° East 47.8 feet;


Thence with the east-west half section line North $84^{\circ} 58'$ West a distance of 222.5 feet to a corner post being the southeast corner of a 5.94 acre tract as recorded in Deed Book 152 at page 307, Hocking County Recorder's Office;

Thence with the east line of said tract North $10^{\circ} 02'$ West a distance of 769.00 feet to a point in the center of County Road 4;


Thence with the center of said county road North $55^{\circ} 41' 55''$ East a distance of 479.01 feet to a point on the east line of the west half of said Northeast Quarter;

Thence with said east line South $2^{\circ} 11' 35''$ West a distance of 1047.47 feet to the place of beginning, containing 6.526 acres, more or less, subject to all legal highways and easements of record.

The above described tract was surveyed by George F. Seymour, Ohio Registered Surveyor No. 6044, April 5, 1977.



APPROVED
HOCKING COUNTY ENGINEER'S OFFICE
DATE 4-7-77
BY PA



N 15° 44' E

S 89° 22' E 524.66
482.00

N 55° 02' E 629.15

S 37° 29' E

827.28'

Sec. 15

Sec. 14

AC # 227AA

49.690Ac
- .236

49.454

AC # 206AA

.236

West.

SE corner
N.E. Sec 15

APPROVED
HOCKING COUNTY ENGINEER'S OFFICE
DATE 10-18-76
BY R.H.

Laural H.H.

S 89° 45' W 1455.02'

and State of Ohio Grantee s, the receipt whereof is hereby
acknowledged, do hereby grant, bargain, sell and convey to the said

Grantees, RONALD C. McCRADY and VIRGINIA R. McCRADY,

their heirs and assigns forever, the
following **Real Estate** situated in the County of Hocking
in the State of Ohio, and in the Township of
Laurel and bounded and described as follows:

Being a part of Sections 14 and 15, Township 12, Range 18, (Laurel) Hocking
County, Ohio and bounded as follows: beginning at an iron pin in the S. E. Corner
of the N. E. Quarter of Section 15; thence South 1 degree 14 minutes West 655.71
feet to an iron pin; thence South 89 degrees 45 minutes West 1455.02 feet to an iron
pin; thence North 1 degree 24 minutes East 646.26 feet to an iron pin; thence North
88 degrees 41 minutes West 234.4 feet to an iron pin in road; thence with road North
21 degrees 21 minutes East 238.90 feet; thence North 12 degrees 08 minutes East
360.57 feet; thence North 55 degrees 02 minutes East 629.15 feet to an iron pin;
thence North 15 degrees 44 minutes East 46.14 feet to an iron pin; thence leaving
the road and passing an iron pin at 42.6 feet, South 81 degrees 22 minutes East
524.66 feet to an iron pin; thence South 37 degrees 29 minutes East 827.28 feet to
an iron pin; thence South 9 degrees 36 minutes East 237.21 feet to an iron pin in
quarter section line; thence West 65.00 feet to the place of beginning, containing
49.69 acres. *with .2524 Ac. in Sec #14 + 44,6258 Ac. in Sec #15*

The above description was prepared by Dumond and Sifford, Lancaster, Ohio,
who platted said premises for prior Grantors March, 1970.

EXCEPTING THEREFROM the following: Being a part of the Northeast Quarter of
Section 15, T12N, R18W, Laurel Township, Hocking County, State of Ohio, and more
particularly described as follows:

Beginning, for reference, at the southeast corner of the Northeast Quarter of
Section 15, T12N, R18W; thence East a distance of 65.00 feet to an iron pin; thence
North 9 degrees 36 minutes West a distance of 237.21 feet to an iron pin; thence
North 37 degrees 29 minutes West a distance of 827.28 feet to an iron pin, said iron
pin being the principal place of beginning of the tract herein described; thence
South 50 degrees 42 minutes 06 seconds West a distance of 719.63 feet to an iron pin;
thence North 41 degrees 29 minutes 00 seconds West a distance of 389.46 feet to an
iron pin set in the center of County Road 4; thence along said county road North
55 degrees 02 minutes East a distance of 346.13 feet to a point; thence continuing
along said centerline North 15 degrees 44 minutes East a distance of 46.14 feet to

*after
exp.*

a point; thence leaving the center of said county road South 81 degrees 22 minutes
East, passing through an iron pin at 45.34 feet, going a total distance of 524.66
feet to the principal place of beginning, containing 4.8118 acres, more or less,
subject to all legal highways and easements of record.


The above described tract was surveyed by George F. Seymour, Registered Surveyor
No. 6044, October 26, 1976.

Said premises are subject to an oil and gas lease to The Ohio Fuel Gas Company
recorded in Volume 56, Page 75, Records of Leases, Hocking County, Ohio. Since the
Grantees herein have, by this deed, acquired all the minerals and mineral rights in,
on and under said premises except the right of said, The Ohio Fuel Gas Company, its
successors and assigns, said Grantees are entitled to all benefits, rentals and
royalty accruing to the property owner by reason of said lease.

Subject to easement dated May 25, 1971 and recorded in Volume 134, Page 584,
Records of Deeds, Hocking County, Ohio.

BEING A PART OF THE W/2 OF THE SW/4 4.0 AC OF SEC. 14, LAUREL TWP., T-12N, R-18W, HOCKING CO. 6.0 AC OHIO

NOTE: CURVE BEARINGS ARE BASED ON THE WEST LINE OF SEC. 14 AT BEARING $N0^{\circ}05'30''E$.



Approved - Mathematically
Hocking County Engineer's Office
BY MFN DATE 6-16-00

For 4.00 Ac TRACT
CONDITIONAL APPROVAL/
TRANSFER Not to be used as
separate building site or
transferred as an independent
parcel in the future without
Planning Commission and/or
Health Department approval

PLAT PREPARED FROM SURVEY MADE
JULY 22, 1996, BY:
[Signature]
OHIO REGISTERED SURVEYOR NO. 6853



DESCRIPTION OF 4.000 AC. TRACT

Being a part of tracts of land last transferred in Vol. 92, Pg. 231, and Vol. 95, Pg. 811, Hocking Co. Official Records, situated in the W 1/2 of the SW 1/4 of Sec. 14, Laurel Twp., T-12N, R-18W, Hocking Co., Ohio, and being more particularly described as follows:

Beginning at an iron pin previously set on the NW corner of the 5.000 Ac. tract described in O.R. Vol. 92, Pg. 231;

Thence, with the north line of said 5.000 Ac. tract and an extension thereof, N 90 degrees 00' 00" E, passing an iron pin previously set at 225.40 ft., going a total distance of 481.48 ft. to an iron pin previously set on the NE corner of the 5.000 Ac. tract described in O.R. Vol. 95, Pg. 811;

Thence, with the east line of said tract, S 0 degrees 00' 00" E a distance of 365.03 ft. to an iron pin set;

Thence, with a new line, N 89 degrees 37' 10" W a distance of 477.38 ft. to an iron pin set on the west line of the previously cited tract described in O.R. Vol. 92, Pg. 231;

Thence, with the west line of said tract, N 0 degrees 39' 08" W a distance of 361.88 ft. to the place of beginning, containing 4.000 acres, more or less, and being subject to the right-of-way of Twp. Rd. No. 232 and all valid easements.

Cited bearings are based on the west line of Sec. 14 as running N 0 degrees 05' 30" E.

All iron pins described as being set or previously set are 5/8" X 30" with an attached plastic identification cap.

The above description is the result of an actual survey made by Michael P. Berry, Ohio Registered Surveyor No. 6803, on August 22, 1996.

Approved - Mathematically *
Hocking County Engineer's Office

BY RFN DATE 6-16-00


Michael P. Berry #6803

* CONDITIONAL APPROVAL/
TRANSFER Not to be used as
separate building site or
transferred as an independent
parcel in the future without
Planning Commission and/or
Health Department approval

DESCRIPTION OF 6.000 AC. TRACT

Being a part of tracts of land last transferred in Vol. 92, Pg. 231, and Vol. 95, Pg. 811, Hocking Co. Official Records, situated in the W 1/2 of the SW 1/4 of Sec. 14, Laurel Twp., T-12N, R-18W, Hocking Co., Ohio, and being more particularly described as follows:

Beginning at a point in the center of Twp. Rd. No. 232, said point being the SW corner of the 5.000 Ac. tract described in O.R. Vol. 92, Pg. 231;

Thence, with the west line of said 5.000 Ac. tract, N 0 degrees 39' 08" W, passing an iron pin previously set at 23.00 ft., going a total distance of 701.57 ft. to an iron pin set;

Thence, with a new line, S 89 degrees 37' 10" E a distance of 477.38 ft. to an iron pin set on the east line of the 5.000 Ac. tract described in O.R. Vol. 95, Pg. 811;

Thence, with said east line, S 0 degrees 00' 00" E, passing an iron pin previously set at 354.62 ft., going a total distance of 377.62 ft. to a point in the center of Twp. Rd. No. 232;

Thence with the center of said Twp. road the following four (4) courses:


- 1) S 47 degrees 29' 15" W a distance of 43.81 ft. to a point;
- 2) S 53 degrees 28' 13" W a distance of 218.28 ft. to a point;
- 3) S 56 degrees 59' 44" W a distance of 183.49 ft. to a point;
- 4) S 60 degrees 23' 56" W a distance of 123.98 ft. to the place of beginning,

containing 6.000 acres, more or less, and being subject to the right-of-way of Twp. Rd. No. 232 and all valid easements.

Cited bearings are based on the west line of Sec. 14 as running N 0 degrees 05' 30" E.

All iron pins described as being set or previously set are 5/8" X 30" with an attached plastic identification cap.

The above description is the result of an actual survey made by Michael P. Berry, Ohio Registered Surveyor No. 6803, on August 22, 1996.



Michael P. Berry #6803

Approved - Mathematically *
Hocking County Engineer's Office

BY RFN DATE 6-16-00

For transfer credit
* CONDITIONAL APPROVAL/
TRANSFER Not to be used as
separate building site or
transferred as an independent
parcel in the future without
Planning Commission and/or
Health Department approval

EXHIBIT "A"
TRACT II- 2.512 ACRES

Being a part of a tract of land that is now or formerly in the name of Jaye Reedy, as recorded in Official Record 183 at page 142 and Official Record 162 at page 161, Hocking County Recorder's Office, said tract being situated in the East half of the Southwest quarter of Section 14, T12N, R18W, Laurel Township, Hocking County, State of Ohio, and being more particularly described as follows:

Beginning at a 5/8" X 30" iron pin with a plastic identification cap set on the Grantor's North line, from which a 5/8" X 30" iron pin with a plastic identification cap stamped "Seymour & Associates" found on the Northeast corner of the Southeast quarter of the Southwest quarter of Section 14 bears, South 81 degrees 44 minutes 39 seconds East a distance of 151.65 feet;

Thence leaving the Grantor's North line, South 49 degrees 33 minutes 38 seconds West, passing through a point being the beginning of a 30.00 foot wide, shared driveway easement at 132.09 feet, going a total distance of 165.81 feet to a 5/8" X 30" iron pin with a plastic identification cap set in the center of said easement;

Thence along the center of said driveway easement, the following ten courses:

1. South 18 degrees 39 minutes 24 seconds East a distance of 97.20 feet to a 5/8" X 30" iron pin with a plastic identification cap set;
2. South 03 degrees 05 minutes 45 seconds East a distance of 94.18 feet to a 5/8" X 30" iron pin with a plastic identification cap set;
3. North 72 degrees 40 minutes 57 seconds West a distance of 89.33 feet to a 5/8" X 30" iron pin with a plastic identification cap set;
4. North 68 degrees 13 minutes 02 seconds West a distance of 127.56 feet to a 5/8" X 30" iron pin with a plastic identification cap set;
5. North 71 degrees 53 minutes 29 seconds West a distance of 59.73 feet to a 5/8" X 30" iron pin with a plastic identification cap set;
6. North 57 degrees 47 minutes 52 seconds West a distance of 93.72 feet to a 5/8" X 30" iron pin with a plastic identification cap set;
7. North 51 degrees 16 minutes 06 seconds West a distance of 65.67 feet to a 5/8" X 30" iron pin with a plastic identification cap set;
8. North 34 degrees 00 minutes 27 seconds West a distance of 40.17 feet to a 5/8" X 30" iron pin with a plastic identification cap set;
9. North 15 degrees 34 minutes 35 seconds West a distance of 24.36 feet to a 5/8" X 30" iron pin with a plastic identification cap set, and;
10. North 36 degrees 53 minutes 50 seconds West a distance of 37.00 feet to a 5/8" X 30" iron pin with a plastic identification cap set within the right-of-way of Rocky Fork Road (Township Road 232) and the Grantor's West line;


Thence along the right-of-way of Township Road 232, and the Grantor's West line, North 07 degrees 13 minutes 16 seconds East a distance of 100.00 feet to a 1" square iron bar found on the Grantor's North corner and within the right-of-way of Uckor Road (Township Road 136);

Thence leaving the center of said road, and along the Grantor's North line, South 81 degrees 44 minutes 39 seconds East a distance of 525.16 feet to the point of beginning containing 2.512 acres, more or less, and subject to the right-of-way of Rocky Fork Road (Township Road 232), Uckor Road (Township Road 136) and all easements of record.

All 5/8" X 30" iron pins with plastic identification caps set are stamped "Seymour & Associates".

The bearings used in the above described tract were derived from monumentation found on the East line of the Southwest quarter of Section 14 as bearing, North 06 degrees 55 minutes 07 seconds East and are for the determination of angles only.

The above described tract was surveyed by George F. Seymour, Ohio Professional Surveyor No. 6044, in April of 2003.


George F. Seymour, P.S. 6044



MAY 15 2003
Date

Approved - Mathematically
Hocking County Engineer's Office

BY AS DATE 5-20-03

Seymour & Associates
830 W. Hunter St.
Logan, Ohio 43138
(740) 385-4349

EXHIBIT "A"
TRACT I - 6.671 ACRES

Being a part of a tract of land that is now or formerly in the name of Jaye Reedy, as recorded in Official Record 183 at page 142 and Official Record 162 at page 161, Hocking County Recorder's Office, said tract being situated in the East half of the Southwest quarter of Section 14, T12N, R18W, Laurel Township, Hocking County, State of Ohio, and being more particularly described as follows:

Beginning at a 5/8" X 30" iron pin with a plastic identification cap stamped "Seymour & Associates" found on the Northeast corner of the Southeast quarter of the Southwest quarter of Section 14, T12N, R18W;

Thence along the Grantor's East line, and the East line of the Southeast quarter of the Southwest quarter, South 06 degrees 55 minutes 07 seconds West, passing through a 5/8" X 30" iron pin with a plastic identification cap stamped "Seymour & Associates" found at 900.00 feet, going a total distance of 933.97 feet to a point in the center of Rocky Fork Road (Township Road 232);

Thence along the center of Township Road 232, the following seven courses:

1. North 44 degrees 51 minutes 58 seconds West a distance of 118.54 feet to a point;
2. North 31 degrees 51 minutes 53 seconds West a distance of 153.70 feet to a point;
3. North 41 degrees 56 minutes 54 seconds West a distance of 91.50 feet to a point;
4. North 29 degrees 13 minutes 54 seconds West a distance of 235.10 feet to a point;
5. North 46 degrees 17 minutes 54 seconds West a distance of 193.90 feet to a point;
6. North 30 degrees 22 minutes 54 seconds West a distance of 207.09 feet to a point, and;
7. North 07 degrees 13 minutes 16 seconds East a distance of 125.75 feet to a 5/8" X 30" iron pin with a plastic identification cap set and within the right-of-way of Rocky Fork Road (Township Road 232);

Thence leaving the right-of-way of said road, South 36 degrees 53 minutes 50 seconds East a distance of 37.00 feet to a 5/8" X 30" iron pin with a plastic identification cap set in the center of a 30.00 foot wide, shared driveway easement;

Thence along the center of said driveway easement, the following ten courses:

1. South 15 degrees 34 minutes 35 seconds East a distance of 24.36 feet to a 5/8" X 30" iron pin with a plastic identification cap set;
2. South 34 degrees 00 minutes 27 seconds East a distance of 40.17 feet to a 5/8" X 30" iron pin with a plastic identification cap set;
3. South 51 degrees 16 minutes 06 seconds East a distance of 65.67 feet to a 5/8" X 30" iron pin with a plastic identification cap set;
4. South 57 degrees 47 minutes 52 seconds East a distance of 93.72 feet to a 5/8" X 30" iron pin with a plastic identification cap set;
5. South 71 degrees 53 minutes 29 seconds East a distance of 59.73 feet to a 5/8" X 30" iron pin with a plastic identification cap set;
6. South 68 degrees 13 minutes 02 seconds East a distance of 127.56 feet to a 5/8" X 30" iron pin with a plastic identification cap set;
7. South 72 degrees 40 minutes 57 seconds East a distance of 89.33 feet to a 5/8" X 30" iron pin with a plastic identification cap set;
8. North 03 degrees 05 minutes 45 seconds West a distance of 94.18 feet to a 5/8" X 30" iron pin with a plastic identification cap set;
9. North 18 degrees 39 minutes 24 seconds West a distance of 97.20 feet to a 5/8" X 30" iron pin with a plastic identification cap set, and;
10. North 49 degrees 33 minutes 58 seconds East, passing through a point being the termination of said driveway easement at 33.72 feet, going a total distance of 165.81 feet to a 5/8" X 30" iron pin with a plastic identification cap set on the Grantor's North line;


EXHIBIT "A"
TRACT I - 6.671 ACRES (Con't)


Thence along the Grantor's North line, South 81 degrees 44 minutes 39 seconds East a distance of 151.65 feet to the point of beginning containing 6.671 acres, more or less, and subject to the right-of-way of Rocky Fork Road (Township Road 232) and all easements of record.

All 5/8" X 30" iron pins with plastic identification caps set are stamped "Seymour & Associates".

The bearings used in the above described tract were derived from monumentation found on the East line of the Southwest quarter of Section 14 as bearing, North 06 degrees 55 minutes 07 seconds East and are for the determination of angles only.

The above described tract was surveyed by George F. Seymour, Ohio Professional Surveyor No. 6044, in April of 2003.


George F. Seymour, P.S. 6044




MAY 15 03
Date

Approved - Mathematically
Hocking County Engineer's Office

BY JM W.B. DATE 5-20-03


Laurel Twp.
Sec. 14
1,3930

BEING PART OF A 22.99 ACRE TRACT,
O.R. 132, PG. 792, & D.V. 215, PG. 594 IN
THE EAST HALF OF THE NORTHEAST
QUARTER OF SECTION 14, T12, R18,
LAUREL TWP., HOCKING CO.,
STATE OF OHIO



THOMAS & SHARON
PLAGEMAN
D.V. 191, PG. 885
7.8639 AC.

P.O.B.
MOST NORTHERLY
CORNER OF A 1.836
ACRE TRACT



DANNY & AMELIA
CALHOUN
O.R. 144, PG. 388
1.836 AC.

RALPH COKONOUGH
D.V. 215, PG. 594, O.R. 132, PG. 792
22.99 AC.

CONDITIONAL APPROVAL/
TRANSFER Not to be used as
separate building site or
transferred as an independent
parcel in the future without
Planning Commission and/or
Health Department approval

BASIS OF BEARINGS: MAY 1980 SURVEY
BY J. A. MATHIAS OF A 7.8638 ACRE TRACT,
D. V. 191, PG. 885.

INFORMATION USED FOR THIS SURVEY
WAS TAKEN FROM TAX MAPS, TOPS MAPS,
DEEDS, AND EXISTING MONUMENTATION FOUND

Approved - Mathematically
Hocking County Engineer's Office
BY *JWB* DATE 9-16-02

PLAT SHOWING
SURVEY OF A 1.3930 ACRE TRACT
FOR DANNY & AMELIA CALHOUN

LEGEND

- = 5/8" REBAR FOUND
- = 5/8" REBAR SET w/ PLAS. I.D. CAP

James R. Cartwright date: 9-16-02
JAMES R. CARTWRIGHT
OHIO REGISTERED SURVEYOR #7486



REAL ESTATE DESCRIPTION

FROM: Ralph Cokonougher

TO: Danny and Amelia Calhoun

The following real estate situated in the County of Hocking in State of Ohio and in the Township of Laurel and being bounded and described as follows:

Being part of a 22.99 acre tract, O.R. 132, page 792, and D.V. 215, page 594 in the East half of the Northeast quarter of Section 14, T12, R18, Congress Lands, and being more particularly described as follows;

Beginning at a 5/8" rebar found, said rebar marking the most Northerly corner of a 1.836 acre tract, O.R. 144, page 388, said rebar marking the principal place of beginning of the tract herein to be described;

Thence North 07 degrees 02 minutes 48 seconds East 127.80 feet to a 5/8" rebar set with plastic I.D. cap;

Thence South 82 degrees 57 minutes 24 seconds East 164.09 feet to a 5/8" rebar set with plastic I.D. cap;

Thence South 31 degrees 22 minutes 06 seconds East 241.32 feet to a 5/8" rebar found;

Thence South 59 degrees 08 minutes 00 seconds West 208.00 feet to a 5/8" rebar found;

Thence North 31 degrees 22 minutes 06 seconds West 241.32 feet to the principal place of beginning, containing 1.3929 acres.

Basis of bearings: May 1980 survey by J.A. Mathias of a 7.8639 acre tract
D.V. 191, page 885.

This description was prepared from an actual survey performed by James R.
Cartwright, Ohio Registered Surveyor #7486, on 9-16-02.

Approved - Mathematically
Hocking County Engineer's Office

BY JLWB DATE 9-16-02
[Signature]


CONDITIONAL APPROVAL/
TRANSFER Not to be used as
separate building site or
transferred as an independent
parcel in the future without
Planning Commission and/or
Health Department approval

James R. Cartwright date: 9-16-02
James R. Cartwright
Ohio Registered Surveyor #7486



Laurel 14

OK



PLAT OF
 5.47 Acres in the N.W. 1/4
 of Section 14, T. 12, R. 18,
 Laurel Township, Hocking
 County - Ohio

SUBDIVISION REGULATIONS WAIVED
 BY Planning Comm. DATE 8-10-79
 meeting

Surveyed by:
 W. R. Horton
 Reg. Sur. 5465
 July 1979

Approved - Mathematically
 Hocking County Engineer's Office
 By ALG Date 8-10-79
 JN

OK

DESCRIPTION OF A 5.47 ACRE PARCEL OF LAND SITUATED IN THE NORTHWEST QUARTER OF SECTION 14; TOWNSHIP 12; RANGE 18; LAUREL TOWNSHIP; HOCKING COUNTY, OHIO AND BEING MORE ACCURATELY DESCRIBED AS FOLLOWS:

BEGINNING AT AN IRON PIN IN THE NORTHWEST CORNER OF SECTION 14; THENCE SOUTH $89^{\circ}59'30''$ EAST A DISTANCE OF 1378.63 FEET TO AN IRON PIN THE TRUE PLACE OF BEGINNING; THENCE CONTINUING SOUTH $89^{\circ}59'30''$ EAST A DISTANCE OF 400.00 FEET TO AN IRON PIN; THENCE SOUTH $8^{\circ}49'$ WEST A DISTANCE OF 668.87 FEET TO A SPIKE IN THE CENTERLINE OF WILDCAT ROAD; THENCE WITH SAID ROAD THE FOLLOWING (3) COURSES AND DISTANCES:

- (1) NORTH $71^{\circ}44'$ WEST A DISTANCE OF 112.07 FEET TO A SPIKE,
- (2) NORTH $74^{\circ}10'$ WEST A DISTANCE OF 135.00 FEET TO A SPIKE,
- (3) NORTH $72^{\circ}33'$ WEST A DISTANCE OF 142.79 FEET TO A SPIKE; THENCE NORTH $7^{\circ}49'$ EAST A DISTANCE OF 551.38 FEET TO AN IRON PIN THE TRUE PLACE OF BEGINNING AND CONTAINING 5.47 ACRES OF LAND SUBJECT TO ALL EASEMENTS AND RIGHT-OF-WAYS OF RECORD.

A SURVEY OF THE ABOVE WAS MADE IN JULY 1979 BY W.R. NORTON REGISTERED SURVEYOR 5465.

Approved - Mathematically

Hocking County Engineer's Office


B. H. Hays Date 8-10-79

EN

J. VAN FOSSEN

N.W. Cor
N.W. 1/4
Sec. 14

589°59'30"E 1778.63' Iron pin
589°59'30"E 300.11' Iron pin




Scale 1"=100'

K. WOLTZ
N 8° 49' E
668.87'

5.62 Acres

5 0° 34' E
641.96'
CARL FOUCH



5.62 Acres in the N.W. 1/4
of Section 14, T. 12, R. 18,
Laurel Township, Hocking
County - Ohio

Approved - Mathematically
Hocking County Engineer's Office
By R. W. [Signature] Date 6-5-79

SUBDIVISION REGULATIONS WAIVED
BY [Signature] DATE 6-19-79

Surveyed by:
W. R. Horton
reg. sur. 5465
May 1979

DESCRIPTION OF A 5.62 ACRE PARCEL OF LAND SITUATED IN THE NORTHWEST QUARTER OF SECTION 14, TOWNSHIP 12, RANGE 18, LAUREL TOWNSHIP, HOCKING COUNTY, OHIO AND BEING MORE ACCURATELY DESCRIBED AS FOLLOWS:

BEGINNING AT A POINT IN THE NORTHWEST CORNER OF THE NORTHWEST QUARTER OF SECTION 14; THENCE SOUTH $89^{\circ}59'30''$ EAST A DISTANCE OF 1773.63 FEET TO AN IRON PIN THE TRUE PLACE OF BEGINNING; THENCE CONTINUING SOUTH $89^{\circ}59'30''$ EAST A DISTANCE OF 300.11 FEET TO AN IRON PIN; THENCE SOUTH 0° EAST A DISTANCE OF 641.96 FEET TO A SPIKE IN THE CENTERLINE OF WILLCAT HOLLOW ROAD; THENCE WITH THE CENTERLINE OF SAID ROAD THE FOLLOWING (7) COURSES AND DISTANCES:

- (1) SOUTH $65^{\circ}13'$ WEST A DISTANCE OF 61.58 FEET TO A SPIKE,
- (2) SOUTH $71^{\circ}34'$ WEST A DISTANCE OF 70.26 FEET TO A SPIKE,
- (3) SOUTH $76^{\circ}02'$ WEST A DISTANCE OF 62.76 FEET TO A SPIKE,
- (4) SOUTH $82^{\circ}36'$ WEST A DISTANCE OF 40.23 FEET TO A SPIKE,
- (5) NORTH $85^{\circ}47'$ WEST A DISTANCE OF 44.64 FEET TO A SPIKE,
- (6) NORTH $72^{\circ}17'$ WEST A DISTANCE OF 48.43 FEET TO A SPIKE,
- (7) NORTH $71^{\circ}44'$ WEST A DISTANCE OF 100.00 FEET TO A SPIKE; THENCE NORTH $8^{\circ}49'$ EAST A DISTANCE OF 668.87 FEET TO AN IRON PIN THE TRUE PLACE OF BEGINNING AND CONTAINING 5.62 ACRES OF LAND SUBJECT TO ALL EASEMENTS AND RIGHT-OF-WAYS OF RECORD.

A SURVEY OF THE ABOVE WAS MADE IN MAY 1979 BY W.R. HORTON REGISTERED SURVEYOR 5465.

Approved - Mathematically
Hocking County Engineer's Office
By: W.R. Horton Date 6-5-79

PROVISION REGULATIONS WAIVED

W.R. Horton DATE 6-19-79

Laurel 14

N.W. Cor.
Sec. 14
S 589° 59' 30" E
242.18'

S 89° 59' 30" E
536.45'

SEC. LINE

Scale
1" = 100'

5.41 Acres

K. WOLTZ
N 40° 24' W
835.08'

S 23° 08' E
532.28'
K. WOLTZ

S 53° 38' W
197.53'

Wild Cat Rd.

PLAT OF
5.41 Acres in the N.W. 1/4
of Section 14, T.12, R.18,
Laurel Township, Hocking
County - Ohio

Surveyed by:
W.R. Horton
Reg. Sur. 5465
July 1979

Approved - Mathematically
Hocking County Engineer's Office
By W.R.H. Date 8-13-79

3

DESCRIPTION OF A 5.41 ACRE PARCEL OF LAND SITUATED IN THE NORTHWEST QUARTER OF SECTION 14,
TOWNSHIP 12, RANGE 18; LAUREL TOWNSHIP, HOCKING COUNTY, OHIO AND BEING MORE ACCURATELY DESCRIBED
AS FOLLOWS:


BEGINNING AT AN IRON PIN IN THE NORTHWEST CORNER OF SECTION 14; THENCE SOUTH $89^{\circ}59'30''$ EAST
A DISTANCE OF 242.18 FEET TO AN IRON PIN THE TRUE PLACE OF BEGINNING; THENCE CONTINUING SOUTH
 $89^{\circ}59'30''$ EAST A DISTANCE OF 536.45 FEET TO AN IRON PIN; THENCE SOUTH $23^{\circ}08'$ EAST A DISTANCE OF
532.28 FEET TO A SPIKE IN THE CENTERLINE OF WILDCAT ROAD; THENCE WITH SAID ROAD SOUTH $57^{\circ}07'$ WEST
A DISTANCE OF 58.90 FEET TO A SPIKE; THENCE SOUTH $53^{\circ}38'$ WEST A DISTANCE OF 197.53 FEET TO A SPIKE;
THENCE NORTH $40^{\circ}24'$ WEST A DISTANCE OF 835.08 FEET TO AN IRON PIN THE TRUE PLACE OF BEGINNING AND
CONTAINING 5.41 ACRES OF LAND SUBJECT TO ALL EASEMENTS AND RIGHT-OF-WAYS OF RECORD.

A SURVEY OF THE ABOVE WAS MADE IN JULY 1979 BY W.R. KORTON REGISTERED SURVEYOR 5465.

Approved - Mathematically
Hocking County Engineer's Office
By W.R. Korton Date 8-13-79

Laurel OK 14

Scale
1" = 100'



PLAT OF
5.59 Acres in
the N.W. 1/4 of
Section 14,
T 12, R. 18,
Laurel Township,
Hocking County,
Ohio

Approved - Mathematically
Hocking County Engineer's Office
By W.R.H. Date 8-13-79

Surveyed by
W.R. Horton
Reg. Sur. 5465
July 1979

DESCRIPTION OF A 5.59 ACRE PARCEL OF LAND SITUATED IN THE NORTHWEST QUARTER OF SECTION 14, TOWNSHIP 12, RANGE 18, LAUREL TOWNSHIP, HOCKING COUNTY, OHIO AND BEING MORE ACCURATELY DESCRIBED AS FOLLOWS:


BEGINNING AT AN IRON PIN IN THE NORTHWEST CORNER OF SECTION 14; THENCE SOUTH $89^{\circ}59'30''$ EAST A DISTANCE OF 67.18 FEET TO AN IRON PIN THE TRUE PLACE OF BEGINNING; THENCE CONTINUING SOUTH $89^{\circ}59'30''$ EAST A DISTANCE OF 175.00 FEET TO AN IRON PIN; THENCE SOUTH $40^{\circ}24'$ EAST A DISTANCE OF 835.08 FEET TO A SPIKE IN WILDCAT ROAD; THENCE WITH SAID ROAD SOUTH $53^{\circ}38'$ WEST A DISTANCE OF 250.00 FEET TO A SPIKE; THENCE NORTH $45^{\circ}19'$ WEST A DISTANCE OF 724.13 FEET TO AN IRON PIN; THENCE NORTH $0^{\circ}01'$ WEST A DISTANCE OF 275.00 FEET TO AN IRON PIN THE TRUE PLACE OF BEGINNING AND CONTAINING 5.59 ACRES OF LAND SUBJECT TO ALL EASEMENTS AND RIGHT-OF-WAYS OF RECORD.

A SURVEY OF THE ABOVE WAS MADE IN JULY 1979 BY W.R. MORTON REGISTERED SURVEYOR 5465.


Approved - Mathematically
Hocking County Engineer's Office
By RD 5/79 Date 8-13-79

AC
OK.

Laurel 14



5.29 Acres



PLAT OF
 5.29 Acres in the N.W. 1/4
 of Section 14, T.12, R.18,
 Laurel Township, Hocking
 County - Ohio

Surveyed by:
 W. R. Horton
 Reg. Sur. 5465
 July 1979

Approved - Mathematically
 Hocking County Engineer's Office
 By D. J. [Signature] Date 8-10-79
 Jn

DESCRIPTION OF A 5.29 ACRE PARCEL OF LAND SITUATED IN THE NORTHWEST QUARTER OF SECTION 14, TOWNSHIP 12, RANGE 18, LAUREL TOWNSHIP, HOCKING COUNTY, OHIO AND BEING MORE ACCURATELY DESCRIBED AS FOLLOWS.

BEGINNING AT AN IRON PIN IN THE NORTHWEST CORNER OF SECTION 14; THENCE SOUTH $89^{\circ}59'30''$ EAST A DISTANCE OF 778.63 FEET TO AN IRON PIN THE TRUE PLACE OF BEGINNING ; THENCE CONTINUING SOUTH $89^{\circ}59'30''$ EAST A DISTANCE OF 600.00 FEET TO AN IRON PIN; THENCE SOUTH $7^{\circ}49'$ WEST A DISTANCE OF 551.38 FEET TO A SPIKE IN THE CENTERLINE OF WILDCAT ROAD; THENCE WITH SAID ROAD THE FOLLOWING

(4) COURSES AND DISTANCES:

- (1) NORTH $72^{\circ}33'$ WEST A DISTANCE OF 200.00 FEET TO A SPIKE,
- (2) NORTH $76^{\circ}07'$ WEST A DISTANCE OF 42.71 FEET TO A SPIKE,
- (3) SOUTH $87^{\circ}55'$ WEST A DISTANCE OF 43.73 FEET TO A SPIKE,
- (4) SOUTH $73^{\circ}39'$ WEST A DISTANCE OF 41.63 FEET TO A SPIKE; THENCE NORTH $23^{\circ}08'$ WEST A DISTANCE OF 532.28 FEET TO AN IRON PIN THE TRUE PLACE OF BEGINNING AND CONTAINING 5.29 ACRES OF LAND SUBJECT TO ALL EASEMENTS AND RIGHT-OF-WAYS OF RECORD.


A SURVEY OF THE ABOVE WAS MADE IN JULY 1979 BY W.R. MORTON REGISTERED SURVEYOR 5465.

Approved - Mathematically

Hocking County Engineer's Office

By *M. J. [Signature]* Date 8-10-79


SR



TRACT II
49.8458 ACRES

TRACT III
0.1826 ACRES

TRACT I
25.0003 ACRES



NOTE:
BEARINGS DERIVED FROM PREVIOUS SURVEYS AND ARE FOR DETERMINATION OF ANGLES ONLY, AND ARE BASED ON THE EAST LINE OF THE W/2 OF THE S.E.1/4 OF SECTION 14 AS BEARING: S 07°23'13" W



I HEREBY CERTIFY THAT THIS PLAT WAS PREPARED FROM AN ACTUAL FIELD SURVEY OF THE PREMISES IN FEB. OF 1927 AND FROM EXISTING PUBLIC RECORDS AND THAT SAID PLAT CORRECTLY SHOWS THE LIMITS OF THE PARCEL TO BE CONVEYED.

THIS CERTIFICATION WAS MADE BY ME ON THIS 18 DAY OF FEB., 1927

George F. Seymour

GEORGE F. SEYMOUR
OHIO PROFESSIONAL SURVEYOR NO. 6044

LEGEND	
△	5/8" x 30" IRON PIN SET w/IDCAP STAMPED "SEYMOUR & ASSOC."
•	POINT
○	IRON PIN FOUND
□	1" SQUARE IRON BAR FOUND
⊙	CONCRETE IN VITRIFIED CLAY PIPE MONUMENT FOUND
○	3/4" IRON PIPE FOUND
⊗	24" WALNUT TREE

For 3.25 Ac. TRACT I:
SUBDIVISION REGULATIONS WILL BE PENDING HEALTH DEPT. APPROVAL

BY _____ DATE _____

Approved - Mathematically
Hocking County Engineer's Office
J.P.M. Date 2-19-27
Revised 7-4-27

APPROVED
LOGAN-HOCKING COUNTY
HEALTH DEPT
Date 1-7-99 m.h.m.

REVISIONS	
CADD DRG. NO.: L14971.GCD	
LAST REV: 02.18.97 • 11.50	
0.1826 Acre Tract	
ADDED - 2.24.07	
01.06.20 - 3.25 AC	
TRACT DIMED, ADDED	

DEVELOPER: MARK & DANNIE DEVOL

PLAT OF SURVEY

SITUATE IN THE SOUTH HALF OF SECTION 14 AND THE NORTH HALF OF SECTION 23,
T-12-N, R-18-W, LAUREL TOWNSHIP, HOCKING COUNTY, STATE OF OHIO

PROFESSIONAL LAND SURVEYORS
• OH WELL PERMITTING
• LOTS & FARM SURVEYS
• SUB-DIVISIONS
• LAND PLANNING
• CONSTRUCTION

SEYMOUR & ASSOCIATES

630 W. HARTER ST. 385-5954

EXHIBIT "A"

Being a part of the tract of land that is now or formerly in the name of Mark and Dannie Devol as recorded in Official Record 36 at page 466, Hocking County Recorder's Office, said tract being part of the south half of Section 14 and part of the north half of Section 23, T12N, R18W, Laurel Township, Hocking County, State of Ohio, and being more particularly described as follows:

Beginning at a point in the center of Township Road 232, the south line of the west half of the southeast quarter of Section 14 and the grantor's south line from which a 5/8" X 30" iron pin with a plastic identification cap set on the southeast corner of the west half of the southeast quarter of said section bears South 82 degrees 13 minutes 54 seconds East a distance of 941.13 feet;

Thence leaving the center of said road and along the south line of the west half of the southeast quarter and the grantor's south line, North 82 degrees 13 minutes 54 seconds West, passing through a 5/8" X 30" iron pin with a plastic identification cap set at 16.00 feet, going a total distance of 120.72 feet to a 5/8" X 30" iron pin with a plastic identification cap set;

Thence leaving the south line of the west half of the southeast quarter and continuing along the grantor's line the following four courses:

1. South 05 degrees 38 minutes 52 seconds East a distance of 7.86 feet to a 5/8" X 30" iron pin with a plastic identification cap set;
2. South 82 degrees 06 minutes 06 seconds West a distance of 107.98 feet to concrete in vitrified clay pipe monument found;
3. North 25 degrees 53 minutes 54 seconds West, crossing into Section 14 at 44.22 feet, going a total distance of 675.84 feet to concrete in vitrified clay pipe monument found, and;
4. North 59 degrees 17 minutes 35 seconds East, passing through a 5/8" X 30" iron pin with a plastic identification cap set at 98.31 feet, going a total distance of 116.31 feet to a point in the center of Township Road 232;

Thence with a new line along the center of said road the following nine courses:

1. South 31 degrees 51 minutes 53 seconds East a distance of 153.70 feet to a point;
2. South 44 degrees 51 minutes 58 seconds East distance of 205.58 feet to a point;
3. South 38 degrees 48 minutes 27 seconds East a distance of 80.67 feet to a point;
4. South 56 degrees 37 minutes 21 seconds East a distance of 63.81 feet to a point;
5. South 69 degrees 43 minutes 31 seconds East a distance of 44.01 feet to a point;
6. South 41 degrees 21 minutes 32 seconds East a distance of 26.06 feet to a point;
7. South 01 degree 58 minutes 36 seconds East a distance of 87.89 feet to a point;
8. South 07 degrees 40 minutes 35 seconds East a distance of 68.97 feet to a point, and;
9. South 11 degrees 54 minutes 58 seconds East a distance of 97.92 feet to the point of beginning, containing 0.063 acre in Section 23 and 3.193 acres in Section 14, for a total of 3.256 acres, more or less, and subject to the right-of-way of Township Road 232 and all easements of record.

All 5/8" X 30" iron pins with plastic identification caps set are stamped "Seymour & Associates".

The bearings used in the above described tract were based on the east line of the west half of the southeast quarter of Section 14 as bearing South 07 degrees 23' minutes 13 seconds West and are for the determination of angles only.

The above described tract was surveyed by George F. Seymour, Ohio Professional Surveyor No. 6044, in February of 1997.

Approved - Mathematically
Hocking County Engineer's Office

BY *M. Au* DATE *1-7-99*
Pending Health Dept Approval
See Plat




EXHIBIT "A"

Being a part of the tract of land that is now or formerly in the name of Mark and Dannie Devol as recorded in Official Record 36 at page 466, Hocking County Recorder's Office, said tract being part of the east half of the southwest quarter of Section 14, T12N, R18W, Laurel Township, Hocking County, State of Ohio, and being more particularly described as follows:

Beginning at a 5/8" X 30" iron pin with a plastic identification cap set on the northeast corner of the southeast quarter of the southwest quarter of Section 14 and a corner to the grantor;

Thence with a new line along the east line of the southeast quarter of the southwest quarter, South 06 degrees 55 minutes 08 seconds West, passing through a 5/8" X 30" iron pin with a plastic identification cap set at 900.00 feet, going a total distance of 933.97 feet to a point in the center of Township Road 232;

Thence along the center of said road the following seven courses:


1. North 44 degrees 51 minutes 58 seconds West a distance of 118.54 feet to a point;
2. North 31 degrees 51 minutes 53 seconds West a distance of 153.70 feet to a point;
3. North 41 degrees 56 minutes 54 seconds West a distance of 91.50 feet to a point;
4. North 29 degrees 13 minutes 54 seconds West a distance of 235.10 feet to a point;
5. North 46 degrees 17 minutes 54 seconds West a distance of 193.90 feet to a point;
6. North 30 degrees 22 minutes 54 seconds West a distance of 207.09 feet to a point, and;
7. North 07 degrees 13 minutes 16 seconds East a distance of 225.75 feet to a 1" square iron bar found on the north line of the southeast quarter of the southwest quarter;

Thence leaving the center of said road and along the north line of the southeast quarter of the southwest quarter, South 81 degrees 44 minutes 39 seconds East a distance of 676.80 feet to the place of beginning, containing 9.1826 acres, more or less, and subject to the right of way of Township Road 232 and all easements of record.

All 5/8" X 30" iron pins with plastic identification caps set are stamped "Seymour & Associates".

The bearings used in the above described tract were based on east line of the west half of the southeast quarter of Section 14 as bearing South 07 degrees 23 minutes 13 seconds West and are for the determination of angles only.

The above described tract was surveyed by George F. Seymour, Ohio Professional Surveyor No. 6044, in February of 1997.



Approved - Mathematically
Hocking County Engineer's office
By R. E. N. Date 3-9-97

EXHIBIT "A"

Being a part of the tract of land that is now or formerly in the name of Mark and Dannie Devol as recorded in Official Record 36 at page 466, Hocking County Recorder's Office, said tract being part of the west half of the southeast quarter of Section 14, T12N, R18W, Laurel Township, Hocking County, State of Ohio, and being more particularly described as follows:

Beginning at an iron pin found on the northeast corner of the west half of the southeast quarter of Section 14 and the grantor's northeast corner;


Thence along the east line of the west half of the southeast quarter and the grantor's east line, South 07 degrees 23 minutes 13 seconds West a distance of 1140.62 feet to a 5/8" X 30" iron pin with a plastic identification cap set;

Thence leaving the east line of the west half of the southeast quarter and the grantor's east line and with a new line through the grantor's land the following nine courses:

1. North 84 degrees 12 minutes 35 seconds West a distance of 305.78 feet to a 5/8" X 30" iron pin with a plastic identification cap set;
2. South 38 degrees 33 minutes 50 seconds West a distance of 176.62 feet to a 5/8" X 30" iron pin with a plastic identification cap set;
3. South 46 degrees 29 minutes 33 seconds West a distance of 387.09 feet to a 5/8" X 30" iron pin with a plastic identification cap set;
4. South 36 degrees 00 minutes 02 seconds West a distance of 258.41 feet to a 5/8" X 30" iron pin with a plastic identification cap set;
5. South 04 degrees 15 minutes 06 seconds East a distance of 120.94 feet to a 5/8" X 30" iron pin with a plastic identification cap set;
6. South 12 degrees 05 minutes 03 seconds West a distance of 117.52 feet to a 5/8" X 30" iron pin with a plastic identification cap set;
7. South 25 degrees 46 minutes 13 seconds West a distance of 96.64 feet to a 5/8" X 30" iron pin with a plastic identification cap set;
8. South 66 degrees 09 minutes 12 seconds West a distance of 208.00 feet to a 5/8" X 30" iron pin with a plastic identification cap set, and;
9. South 31 degrees 16 minutes 47 seconds West, passing through a 5/8" X 30" iron pin with a plastic identification cap set at 121.88 feet, going a total distance of 140.33 feet to a point in the center of Township Road 232;

Thence continuing with a new line along the center of said road the following five courses:

1. North 41 degrees 21 minutes 32 seconds West a distance of 13.15 feet to a point in the center of a wooden bridge;
2. North 69 degrees 43 minutes 31 seconds West a distance of 44.01 feet to a point;
3. North 56 degrees 37 minutes 21 seconds West a distance of 63.81 feet to a point;
4. North 38 degrees 48 minutes 27 seconds West a distance of 80.67 feet to a point, and;
5. North 44 degrees 51 minutes 58 seconds West a distance of 87.04 feet to a point on the west line of the west half of the southeast quarter;



[continued on page 2]

EXHIBIT "A"

Thence leaving the center of said road and continuing with a new line through the grantor's land and along the west line of the west half of the southeast quarter, North 06 degrees 55 minutes 08 seconds East, passing through a 5/8" X 30" iron pin with a plastic identification cap set at 33.97 feet, going a total distance of 933.97 feet to a 5/8" X 30" iron pin with a plastic identification cap set on a corner to the grantor;

Thence continuing along the west line of the west half of the southeast quarter and along the grantor's westerly line, North 06 degrees 55 minutes 08 seconds East a distance of 1315.08 feet to a 5/8" X 30" iron pin with a plastic identification cap set on the northwest corner of the west half of the southeast quarter and the grantor's northwesterly corner;

Thence along the grantor's north line and the north line of the west half of the southeast quarter, South 81 degrees 59 minutes 57 seconds East a distance of 1271.04 feet to the place of beginning, containing 49.8458 acres, more or less, and subject to the right of way of Township Road 232 and all easements of record.

All 5/8" X 30" iron pins with plastic identification caps set are stamped "Seymour & Associates".

The bearings used in the above described tract were based on east line of the west half of the southeast quarter of Section 14 as bearing South 07 degrees 23 minutes 13 seconds West and are for the determination of angles only.

The above described tract was surveyed by George F. Seymour, Ohio Professional Surveyor No. 6044, in February of 1997.

Approved - Mathematically
Hocking County Engineer's office
By RFN Date 2-19-97




EXHIBIT "A"

Being a part of the tract of land that is now or formerly in the name of Mark and Dannie Devol as recorded in Official Record 36 at page 466, Hocking County Recorder's Office, said tract being part of the west half of the southeast quarter of Section 14, T12N, R18W, Laurel Township, Hocking County, State of Ohio, and being more particularly described as follows:

Beginning at a 5/8" X 30" iron pin with a plastic identification cap set on the east line of the west half of the southeast quarter of Section 14 and the grantor's east line from which an iron pin found on the northeast corner of the west half of the southeast quarter of said section bears, North 07 degrees 23 minutes 13 seconds West a distance of 1140.62 feet;

Thence along the east line of the west half of the southeast quarter and the grantor's east line, South 07 degrees 23 minutes 13 seconds West, passing through a 24" Walnut Tree on the northwest corner of the southeast quarter of the southeast quarter at 180.95 feet, passing through a 5/8" X 30" iron pin with a plastic identification cap set at 1434.81 feet and crossing the center of Township Road 232 at 1444.41 feet, going a total distance of 1510.81 feet to a 5/8" X 30" iron pin with a plastic identification cap set on the south line of Section 14 and the grantor's southeast corner;


Thence along the south line of Section 14 and the grantor's south line, North 82 degrees 13 minutes 54 seconds West, passing through a 5/8" X 30" iron pin with a plastic identification cap set at 95.20 feet, crossing the centerline of Township Road 232 at 115.20 feet, and passing through 5/8" X 30" iron pins with plastic identification caps set at 135.20 feet and 925.13 feet, going a total distance of 941.13 feet to a point in the center of Township Road 232;

Thence leaving the south line of Section 14 and the grantor's south line and with a new line along the center of said road the following four courses:

1. North 11 degrees 54 minutes 58 seconds West a distance of 97.92 feet to a point;
2. North 07 degrees 40 minutes 35 seconds West a distance of 68.97 feet to a point;
3. North 01 degree 58 minutes 36 seconds West a distance of 87.89 feet to a point, and;
4. North 41 degrees 21 minutes 32 seconds West a distance of 12.91 feet to a point;

Thence leaving the center of said road and continuing with a new line through the grantor's land the following nine courses:

1. North 31 degrees 16 minutes 47 seconds East, passing through a 5/8" X 30" iron pin with a plastic identification cap set at 18.45 feet, going a total distance of 140.33 feet to a 5/8" X 30" iron pin with a plastic identification cap set;



[continued on page 2]

EXHIBIT "A"


2. North 66 degrees 09 minutes 12 seconds East a distance of 208.00 feet to a 5/8" X 30" iron pin with a plastic identification cap set;
3. North 25 degrees 46 minutes 13 seconds East a distance of 96.64 feet to a 5/8" X 30" iron pin with a plastic identification cap set;
4. North 12 degrees 05 minutes 03 seconds East a distance of 117.52 feet to a 5/8" X 30" iron pin with a plastic identification cap set;
5. North 04 degrees 15 minutes 06 seconds West a distance of 120.94 feet to a 5/8" X 30" iron pin with a plastic identification cap set;
6. North 36 degrees 00 minutes 02 seconds East a distance of 258.41 feet to a 5/8" X 30" iron pin with a plastic identification cap set;
7. North 46 degrees 29 minutes 33 seconds East a distance of 387.09 feet to a 5/8" X 30" iron pin with a plastic identification cap set;
8. North 38 degrees 33 minutes 50 seconds East a distance of 176.62 feet to a 5/8" X 30" iron pin with a plastic identification cap set, and;
9. South 84 degrees 12 minutes 35 seconds East a distance of 305.78 feet to the place of beginning, containing 25.0003 acres, more or less, and subject to the right of way of Township Road 232 and all easements of record.


All 5/8" X 30" iron pins with plastic identification caps set are stamped "Seymour & Associates".

The bearings used in the above described tract were based on east line of the west half of the southeast quarter of Section 14 as bearing South 07 degrees 23 minutes 13 seconds West and are for the determination of angles only.

The above described tract was surveyed by George F. Seymour, Ohio Professional Surveyor No. 6044, in February of 1997.

Approved - Mathematically
Hocking County Engineer's office
By *GFN* Date 2-19-97





Philip K. and Patricia A. Cooney
Deed Vol. 128, Page 436

Ronald Childers
Deed Vol. 154, Page 111

REFERENCE POINT
N.E. Cor. of Section 15,
Twp. 12, R. 18.

Michael and Martha Petrucci, et al
Deed Vol. 161, Page 440
Deed Vol. 185, Page 368
Deed Vol. 199, Page 321
Official Rec. 11, Page 715
Official Rec. 12, Page 695

PROFESSIONAL LAND SURVEYORS

SEYMOUR & ASSOCIATES

P.O. Box 624
830 W. Hunter St.
Logan, Ohio 43135
614-385-4349



PLAT OF SURVEY


Situated in the State of Ohio, County of Hocking, Township of Laurel and being located in the Northeast Quarter of Section 15 and the Northwest Quarter of Section 14, Township 12, Range 18.

REVISIONS

NO.	DATE	BY	DESCRIPTION
1	11/14/97	JLC	
2	11/15/97	JLC	

DATE DRAWN: 11/14/97
DATE CHECKED: 11/15/97

FOR: Robert Martin



Kent and Kathy Steinmetz
Deed Vol. 198, Page 768

Timothy and Tonya Buchanan
Official Rec. 87, Page 518

Barbara Brown
Deed Vol. 221, Page 394

Carole Hayes
Deed Vol. 220, Page 850
Deed Vol. 219, Page 313

Robert Martin
Official Rec. 105, Page 147

Robert Martin
Official Rec. 96, Page 8

Leonard and Anna Shroyer
Deed Vol. 217, Page 446

Dorothy Spencer
Deed Vol. 217, Page 116

James Grow and Linda Hilbert
Deed Vol. 196, Page 573

REFERENCES:
Tax Maps
Previous surveys
Deeds as Noted

NOTE:
The bearing system for this plat is based on evidence found on the North line of Section 15 and bears N 89° 00' 34" E and is for the determination of angles only.

- LEGEND**
- △ 5/8" iron pin set 30" in length with plastic ID cap inscribed "SEYMOUR & ASSOC."
 - ⊗ Railroad spike found
 - Iron pipe found
 - 5/8" iron pin found
 - Point

Approved - Mathematically
Hocking County Engineer's Office
v. M. Brown 12-8-97
Pending Health Dept Approval
Sec 4.1026 Ac. Tract

I HEREBY CERTIFY THAT THIS PLAT WAS PREPARED FROM AN ACTUAL FIELD SURVEY OF THE PREMISES IN 1977 AND FROM EXISTING PUBLIC RECORDS AND THAT SAID PLAT CORRECTLY SHOWS THE LIMITS OF THE PARCEL TO BE CONVEYED.

THIS CERTIFICATION WAS MADE BY ME ON THIS 5 DAY OF Dec, 1997.

George F. Seymour

GEORGE F. SEYMOUR
OHIO PROFESSIONAL SURVEYOR NO. 6044
©1997 SEYMOUR & ASSOCIATES

EXHIBIT "A"

Being a part of the tract of land that is now or formerly in the name of Robert Martin as recorded in Official Record 105 at page 147, Hocking County Recorder's Office, said tract being part of the northeast quarter of Section 15, T12N, R18W, Laurel Township, Hocking County, State of Ohio and being more particularly described as follows:

Beginning at a point on the grantor's north line and the north line of Section 15 from which the northeast corner of said section bears North 89 degrees 00 minutes 34 seconds East a distance of 500.57 feet, said beginning point being referenced by an iron pipe found which bears North 00 degrees 59 minutes 26 seconds West a distance of 1.31 feet;

Thence leaving the north line of Section 15 and with a new line through the grantor's land the following three courses:

1. South 30 degrees 08 minutes 10 seconds East a distance of 576.75 feet to a 5/8" X 30" iron pin with a plastic identification cap set;
2. South 53 degrees 00 minutes 40 seconds West a distance of 701.13 feet to a 5/8" X 30" iron pin with a plastic identification cap set, and;
3. South 36 degrees 59 minutes 20 seconds East, passing through a 5/8" X 30" iron pin with a plastic identification cap set at 187.46 feet, going a total distance of 212.46 feet to a point within the right-of-way of County Road 4 and on the grantor's south line;

Thence within said right-of-way and the grantor's south line South 42 degrees 37 minutes 04 seconds West a distance of 61.00 feet to a point;

Thence leaving said right-of-way and with a new line through the grantor's land the following two courses:

1. North 36 degrees 59 minutes 20 seconds West, passing through a 5/8" X 30" iron pin with a plastic identification cap set at 25.42 feet, going a total distance of 818.47 feet to a 5/8" X 30" iron pin with a plastic identification cap set, and;
2. North 00 degrees 59 minutes 26 seconds West a distance of 469.70 feet to a 5/8" X 30" iron pin with a plastic identification cap set on the grantor's north line and the north line of Section 15;


Thence along the grantor's north line and the north line of Section 15, North 89 degrees 00 minutes 34 seconds East a distance of 684.61 feet to the place of beginning, containing 14.6624 acres, more or less, and subject to the right-of-way of County Road 4 and all easements of record.

Also included with the above described tract is a 20.0 foot wide easement for ingress and egress, the centerline being more particularly described as follows:

Beginning, for reference, at a 5/8" X 30" iron pin with a plastic identification cap set on the northwest corner of the above described tract;

Thence along the west line of said tract the following two courses:

1. South 00 degrees 59 minutes 26 seconds East a distance of 469.70 feet to a 5/8" X 30" iron pin with a plastic identification cap set, and;
2. South 36 degrees 59 minutes 20 seconds East a distance of 594.06 feet to a point being the principal place of beginning for the easement herein described;



[continued on page 2]

EXHIBIT "A"

Thence leaving the west line of the above described tract and along the center of said easement the following four courses:

1. South 41 degrees 22 minutes 24 seconds West a distance of 23.21 feet to a point;
2. South 26 degrees 55 minutes 48 seconds West a distance of 87.83 feet to a point;
3. South 08 degrees 21 minutes 04 seconds West a distance of 67.78 feet to a point, and;
4. South 02 degrees 05 minutes 17 seconds East a distance of 197.56 feet to a point in the center of County Road 4 and the termination point of the easement.

All 5/8" X 30" iron pins with plastic identification caps set are stamped "Seymour & Associates".

The bearings used in the above described tract were based on the north line of Section 15 as bearing North 89 degrees 00 minutes 34 seconds East and are for the determination of angles only.

The above described tract was surveyed by George F. Seymour, Ohio Professional Surveyor No. 6044, in November of 1997.

Approved - Mathematically
Hocking County Engineer's office
JAW Date 12-8-97




EXHIBIT "A"

Being a part of the tract of land that is now or formerly in the name of Robert Martin as recorded in Official Record 105 at page 147, Hocking County Recorder's Office, said tract being part of the northeast quarter of Section 15, T12N, R18W, Laurel Township, Hocking County, State of Ohio and being more particularly described as follows:

Beginning at a 5/8" X 30" iron pin with a plastic identification cap set on the grantor's north line and the north line of Section 15 from which the northeast corner of said section bears North 89 degrees 00 minutes 34 seconds East a distance of 1185.18 feet;

Thence leaving the north line of Section 15 and with a new line through the grantor's land the following two courses:

1. South 00 degrees 59 minutes 26 seconds East a distance of 469.70 feet to a 5/8" X 30" iron pin with a plastic identification cap set, and;
2. South 36 degrees 59 minutes 20 seconds East, passing through a 5/8" X 30" iron pin with a plastic identification cap set at 793.05 feet, going a total distance of 818.47 feet to a point within the right-of-way of County Road 4 and on the grantor's south line;

Thence within said right-of-way and the grantor's south line the following four courses:

1. South 42 degrees 37 minutes 04 seconds West a distance of 84.45 feet to a point;
2. South 49 degrees 37 minutes 04 seconds West a distance of 124.48 feet to a point;
3. South 47 degrees 19 minutes 04 seconds West a distance of 50.62 feet to a point, and;
4. South 42 degrees 52 minutes 15 seconds West a distance of 47.21 feet to a 5/8" iron pin found on a corner to the grantor;


Thence leaving said right-of-way and continuing along the grantor's south line the following two courses:

1. North 00 degrees 33 minutes 41 seconds West a distance of 141.29 feet to a 5/8" iron pin found and;
2. South 89 degrees 32 minutes 22 seconds West a distance of 631.39 feet to an iron pipe found on the grantor's southwest corner;

Thence along the grantor's west line the following seven courses:

1. North 00 degrees 42 minutes 33 seconds East a distance of 154.53 feet to an iron pipe found;
2. North 00 degrees 22 minutes 39 seconds East a distance of 147.85 feet to an iron pipe found;
3. North 01 degrees 29 minutes 59 seconds West a distance of 149.63 feet to an iron pipe found;
4. North 01 degree 03 minutes 53 seconds West a distance of 149.74 feet to an iron pipe found;
5. North 01 degree 23 minutes 18 seconds West a distance of 295.49 feet to an iron pipe found;
6. North 00 degrees 28 minutes 22 seconds East a distance of 147.89 feet to an iron pipe found, and;
7. North 00 degrees 37 minutes 33 seconds East a distance of 147.69 feet to an iron pipe found on the grantor's northwest corner and the north line of Section 15;

Thence along the grantor's north line and the north line of Section 15, North 89 degrees 00 minutes 34 seconds East, passing an iron pipe found at 114.38 feet which bears North 00 degrees 59 minutes 26 seconds West a distance of 1.85 feet from the property line, going a total distance of 361.71 feet to the place of beginning, containing 14.6682 acres, more or less, and subject to the right-of-way of County Road 4 and all easements of record.



[Continued on page 2]

EXHIBIT "A"

The above described tract is subject to a 20.0 foot wide easement for ingress and egress, the center line being more particularly described as follows:

Beginning at a point within the right-of-way of County Road 4 and on the south line of the above described tract from which a 5/8" iron pin found on the most southerly corner of said tract bears South 42 degrees 52 minutes 15 seconds West a distance of 41.95 feet;

Thence leaving said road and the south line of said tract and along the center of said easement the following four courses:

1. North 02 degrees 05 minutes 17 seconds West a distance of 197.56 feet to a point;
2. North 08 degrees 21 minutes 04 seconds East a distance of 67.78 feet to a point;
3. North 26 degrees 55 minutes 48 seconds East a distance of 87.83 feet to a point, and;
4. North 41 degrees 22 minutes 24 seconds East a distance of 23.21 feet to a point being on the easterly line of the above described tract and the termination of said easement, containing 0.1730 acre, more or less.

All 5/8" X 30" iron pins with plastic identification caps set are stamped "Seymour & Associates".

The bearings used in the above described tract were based on the north line of Section 15 as bearing North 89 degrees 00 minutes 34 seconds East and are for the determination of angles only.

The above described tract was surveyed by George F. Seymour, Ohio Professional Surveyor No. 6044, in November of 1997.

Approved - Matthew G. ...
Hocking County Engineer's Office
G. F. Seymour Date 12-8-97




EXHIBIT "A"

Being a part of the tract of land that is now or formerly in the name of Robert Martin as recorded in Official Record 105 at page 147 and Official Record 96 at page 8, Hocking County Recorder's Office, said tract being part of the northeast quarter of Section 15, T12N, R18W, Laurel Township, Hocking County, State of Ohio and being more particularly described as follows:

Beginning, for reference, at the northeast corner of Section 15, said beginning corner being reference by an iron pipe found which bears South 00 degrees 59 minutes 26 seconds East a distance of 0.50 feet;

Thence along the north line of Section 15, South 89 degrees 00 minutes 34 seconds West a distance of 500.57 feet to a point, said point being reference by a 5/8" iron pin found which bears North 00 degrees 59 minutes 26 seconds West a distance of 1.31 feet;

Thence leaving the north line of Section 15, South 30 degrees 08 minutes 10 seconds East a distance of 576.75 feet to a 5/8" X 30" iron pin with a plastic identification cap set and the principal place of beginning for the tract herein described;

Thence with a new line through the grantor's land, South 30 degrees 08 minutes 10 seconds East, passing through a 5/8" X 30" iron pin with a plastic identification cap set at 280.04 feet, going a total distance of 308.59 feet to a point within the right-of-way of County Road 4 and the grantor's south line;

Thence within said right-of-way and the grantor's south line the following ten courses:

1. South 88 degrees 43 minutes 53 seconds West a distance of 69.57 feet to a point;
2. South 61 degrees 50 minutes 53 seconds West a distance of 51.63 feet to a point;
3. South 44 degrees 59 minutes 53 seconds West a distance of 43.72 feet to a point;
4. South 47 degrees 24 minutes 04 seconds West a distance of 185.31 feet to a point;
5. South 54 degrees 49 minutes 04 seconds West a distance of 74.64 feet to a point;
6. South 68 degrees 01 minute 04 seconds West a distance of 63.65 feet to a point;
7. South 75 degrees 45 minutes 32 seconds West a distance of 34.67 feet to a point;
8. South 75 degrees 49 minutes 04 seconds West a distance of 47.85 feet to a point;
9. South 69 degrees 38 minutes 04 seconds West a distance of 62.14 feet to a point, and;
10. South 54 degrees 02 minutes 04 seconds West a distance of 57.41 feet to a point;

Thence leaving the right-of-way of said road and the grantor's south line and with a new line through the grantor's land the following two courses:

1. North 36 degrees 59 minutes 20 seconds West, passing through a 5/8" X 30" iron pin with a plastic identification cap set at 25.00 feet, going a total distance of 212.46 feet to a 5/8" X 30" iron pin with a plastic identification cap set, and;
2. North 53 degrees 00 minutes 40 seconds East a distance of 701.13 feet to the principal place of beginning, containing 4.1026 acres, more or less, and subject to the right-of-way of County Road 4 and all easements of record.

All 5/8" X 30" iron pins with plastic identification caps set are stamped "Seymour & Associates".

The bearings used in the above described tract were based on the north line of Section 15 as bearing North 89 degrees 00 minutes 34 seconds East and are for the determination of angles only.

The above described tract was surveyed by George F. Seymour, Ohio Professional Surveyor No. 6044, in November of 1997.



Approved - Mathematically
Hocking County Engineer's office
by *JM* Date *12-8-97*
Pending Health Dept Approval

EXHIBIT "A"

Being a part of the tract of land that is now or formerly in the name of Robert Martin as recorded in Official Record 105 at page 147 and Official Record 96 at page 8, Hocking County Recorder's Office, said tract being part of the northeast quarter of Section 15 and part of the northwest quarter of Section 14, T12N, R18W, Laurel Township, Hocking County, State of Ohio and being more particularly described as follows:

Beginning at the northeast corner of Section 15, the northwest corner of Section 14 and the grantor's north line, said beginning point being reference by an iron pipe found which bears South 00 degrees 59 minutes 26 seconds East a distance of 0.50 feet;

Thence along the north line of Section 14 and the grantor's north line, North 89 degrees 00 minutes 34 seconds East a distance of 66.65 feet to an iron pipe found on the grantor's northeast corner;

Thence leaving the north line of Section 14 and along the grantor's east line the following two courses:

1. South 01 degree 00 minutes 30 seconds East a distance of 273.80 feet to an iron pipe found, and;
2. South 00 degrees 23 minutes 18 seconds East, passing through a 5/8" X 30" iron pin with a plastic identification cap set at 700.42 feet, going a total distance of 755.46 feet to railroad spike found on the grantor's southeast corner and within the right-of-way of County Road 4;

Thence along the grantor's south line and within the right-of-way of said road the following three courses:

1. North 27 degrees 24 minutes 07 seconds West a distance of 51.63 feet to a point;
2. North 21 degrees 14 minutes 07 seconds West, crossing into Section 15 at 152.42 feet, going a total distance of 171.76 feet to a point, and;
3. North 44 degrees 17 minutes 07 seconds West a distance of 66.75 feet to a point;

Thence leaving the grantor's south line and the right-of-way of County Road 4 and with a new line through the grantor's land, North 30 degrees 08 minutes 10 seconds West, passing through 5/8" X 30" iron pins with plastic identification caps set at 28.55 feet and 308.59 feet, going a total distance of 885.34 feet to a point on the grantor's north line and the north line of Section 15, said point being referenced by a 5/8" iron pin found which bears North 00 degrees 59 minutes 26 seconds West a distance of 1.31 feet;


Thence along the grantor's north line and the north line of Section 15, North 89 degrees 00 minutes 34 seconds East, passing an iron pipe found which bears North 00 degrees 59 minutes 26 seconds West a distance of 2.27 feet from the property line at 300.90 feet, going a total distance of 500.57 feet to the place of beginning, containing 1.5887 acres in Section 14 and 4.9566 acres in Section 15, for a total of 6.5453 acres, more or less, and subject to the right-of-way of County Road 4 and all easements of record.

All 5/8" X 30" iron pins with plastic identification caps set are stamped "Seymour & Associates".

The bearings used in the above described tract were based on the north line of Section 15 as bearing North 89 degrees 00 minutes 34 seconds East and are for the determination of angles only.

The above described tract was surveyed by George F. Seymour, Ohio Professional Surveyor No. 6044, in November of 1997.

Approved - Mathematically
Hocking County Engineer's Office
G. F. Seymour Date 12-8-97



DESCRIPTION OF 26.8452 AC. TRACT

Being a part of a tract of land last transferred in Vol. 56, Pg. 178, Hocking Co. Official Records, situated in the W 1/2 of the SW 1/4 of Sec. 14, Laurel Twp., T-12N, R-18W, Hocking Co., Ohio, and being more particularly described as follows:

Beginning at an iron pipe found on the NW corner of said W 1/2 of the SW 1/4 of Sec. 14;

Thence, with the north line of said W 1/2, N 89 degrees 15' 32" E a distance of 803.51 ft. to an iron pin set;

Thence, with a new line, South, passing an iron pin set at 1096.63 ft., going a total distance of 1119.63 ft. to a point in the center of Twp. Rd. No. 232;

Thence with the center of said Twp. road the following eleven (11) courses:

- 1) S 43 degrees 33' 10" W a distance of 102.90 ft. to a point;
- 2) S 47 degrees 29' 15" W a distance of 149.24 ft. to a point;
- 3) S 53 degrees 28' 13" W a distance of 218.28 ft. to a point;
- 4) S 56 degrees 59' 44" W a distance of 183.49 ft. to a point;
- 5) S 60 degrees 23' 56" W a distance of 123.98 ft. to a point;
- 6) S 53 degrees 31' 12" W a distance of 36.59 ft. to a point;
- 7) S 40 degrees 20' 57" W a distance of 40.57 ft. to a point;
- 8) S 32 degrees 32' 51" W a distance of 88.13 ft. to a point;
- 9) S 20 degrees 07' 01" W a distance of 115.74 ft. to a point;
- 10) S 28 degrees 22' 24" W a distance of 55.55 ft. to a point;

11) S 37 degrees 14' 40" W a distance of 31.66 ft. to a point on the west line of Sec. 14, said point being referenced by an iron pin set which bears N 4 degrees 32' 13" E a distance of 38.10 ft.;

Thence, with said west line, N 0 degrees 05' 30" E, passing an iron pin set at 1373.10 ft. and an iron pin found at 1480.26 ft., going a total distance of 1885.51 ft. to the place of beginning, containing 26.8452 acres, more or less, and being subject to the right-of-way of Twp. Rd. No. 232 and all valid easements.

Cited bearings are based on the west line of Sec. 14 as running N 0 degrees 05' 30" E.

All iron pins described as being set are 5/8" X 30" with an attached plastic identification cap.

The above description is the result of an actual survey made by Michael P. Berry, Ohio Registered Surveyor No. 6803, on August 22, 1996.

Approved - Mathematically
Hocking County Engineer's office
By R.F.N. Date 9-5-96


Michael P. Berry #6803

DESCRIPTION OF 5.000 AC. TRACT

~~TRACT "A"~~

Being a part of a tract of land last transferred in Vol 56, Pg. 178, Hocking Co. Official Records, situated in the W 1/2 of the SW 1/4 of Sec. 14, Laurel Twp., T-12N, R-18W, Hocking Co., Ohio, and being more particularly described as follows:

Beginning at an iron pin set on the west line of Sec. 14, said pin being referenced by an iron pipe found on the NW corner of the W 1/2 of the SW 1/4 which bears N 0 degrees 05' 30" E a distance of 512.41 ft.;

Thence, with a new line, East, a distance of 174.16 ft. to an iron pin set;

Thence S 0 degrees 39' 08" E, passing an iron pin set at 1040.45 ft., going a total distance of 1063.45 ft. to a point in the center of Twp. Rd. No. 232;

Thence with the center of said Twp. road the following six (6) courses:

1) S 53 degrees 31' 12" W a distance of 36.59 ft. to a point;

2) S 40 degrees 20' 57" W a distance of 40.57 ft. to a point;

3) S 32 degrees 32' 51" W a distance of 88.13 ft. to a point;

4) S 20 degrees 07' 01" W a distance of 115.74 ft. to a point;

5) S 28 degrees 22' 24" W a distance of 55.55 ft. to a point;

6) S 37 degrees 14' 40" W a distance of 31.66 ft. to a point on the west line of Sec. 14, said point being referenced by an iron pin set which bears N 4 degrees 32' 13" E a distance of 38.10 ft.;

Thence, with said west line, N 0 degrees 05' 30" E a distance of 1373.10 ft. to the place of beginning, containing 5.000 acres, more or less, and being subject to the right-of-way of Twp. Rd. No. 232 and all valid easements.

Cited bearings are based on the west line of Sec. 14 as running N 0 degrees 05' 30" E.

All iron pins described as being set are 5/8" X 30" with an attached plastic identification cap.

The above description is the result of an actual survey made by Michael P. Berry, Ohio Registered Surveyor No. 6803, on August 22, 1996.


Michael P. Berry #6803

Approved - Mathematically
Hocking County Engineer's office
By RFN Date 9-5-96

DESCRIPTION OF 5.000 AC. TRACT

~~TRACT "B"~~

Being a part of a tract of land last transferred in Vol. 56, Pg. 178, Hocking Co. Official Records, situated in the W 1/2 of the SW 1/4 of Sec. 14, Laurel Twp., T-12N, R-18W, Hocking Co., Ohio, and being more particularly described as follows:

Beginning, for reference, at an iron pin set on the west line of Sec. 14, said pin being referenced by an iron pipe found on the NW corner of said W 1/2 of the SW 1/4 which bears N 0 degrees 05' 30" E a distance of 512.41 ft.;

Thence East a distance of 174.16 ft. to an iron pin set, said pin being the principal place of beginning for the tract herein described;

Thence continuing East a distance of 225.40 ft. to an iron pin set;

Thence S 0 degrees 16' 19" W, passing an iron pin set at 910.90 ft., going a total distance of 936.51 ft. to a point in the center of Twp. Rd. No. 232;

Thence with the center of said Twp. road the following two (2) courses:

1) S 56 degrees 59' 44" W a distance of 120.49 ft. to a point;

2) S 60 degrees 23' 56" W a distance of 123.98 ft. to a point;

Thence, leaving said Twp. road, N 0 degrees 39' 08" W, passing an iron pin set at 23.00 ft., going a total distance of 1063.45 ft. to the principal place of beginning, containing 5.000 acres, more or less, and being subject to the right-of-way of Twp. Rd. No. 232 and all valid easements.

Cited bearings are based on the west line of Sec. 14 as running N 0 degrees 05' 30" E.

All iron pins described as being set are 5/8" X 30" with an attached plastic identification cap.

The above description is the result of an actual survey made by Michael P. Berry, Ohio Registered Surveyor No. 6803, on August 22, 1996.


Michael P. Berry #6803

Approved - Mathematically
Hocking County Engineer's office
By MFN Date 9-5-96

DESCRIPTION OF 5.000 AC. TRACT

TRACT "C"

Being a part of a tract of land last transferred in Vol. 56, Pg. 178, Hocking Co. Official Records, situated in the W 1/2 of the SW 1/4 of Sec. 14, Laurel Twp., T-12N, R-18W, Hocking Co., Ohio, and being more particularly described as follows:

Beginning, for reference, at an iron pin set on the west line of Sec. 14, said pin being referenced by an iron pipe found on the NW corner of said W 1/2 of the SW 1/4 which bears N 0 degrees 05' 30" E a distance of 512.41 ft.;

Thence East, passing an iron pin set at 174.16 ft., going a total distance of 399.56 ft. to an iron pin set, said pin being the principal place of beginning for the tract herein described;

Thence continuing East a distance of 256.08 ft. to an iron pin set;

Thence South, passing an iron pin set at 719.65 ft., going a total distance of 742.65 ft. to a point in the center of Twp. Rd. No. 232;

Thence with the center of said Twp. road the following Three (3) courses:

- 1) S 47 degrees 29' 15" W a distance of 43.81 ft. to a point;
- 2) S 53 degrees 28' 13" W a distance of 218.28 ft. to a point;
- 3) S 56 degrees 59' 44" W a distance of 63.00 ft. to a point;

Thence, leaving Twp. Rd. No. 232, N 0 degrees 16' 19" E, passing an iron pin set at 25.61 ft., going a total distance of 936.51 ft. to the principal place of beginning, containing 5.000 acres, more or less, and being subject to the right-of-way of Twp. Rd. No. 232 and all valid easements.

Cited bearings are based on the west line of Sec. 14 as running N 0 degrees 05' 30" E.

All iron pins described as being set are 5/8" X 30" with an attached plastic identification cap.


The above description is the result of an actual survey made by Michael P. Berry, Ohio Registered Surveyor No. 6803, on August 22, 1996.


Michael P. Berry #6803

Approved Mathematically
Hocking County Engineer's office
By R. FN Date 9-5-96

STATE OF OHIO
 HOCKING COUNTY
 LAUREL TOWNSHIP
 SECTION 14
 T12 R18

PROPERTY OWNED BY CARL E. AND LOIS ANNABELLE FOUCH




- IRON PIN
- CORNER FENCE POST

[Signature]

DESCRIPTION
CARL E. FOUCH & LOIS A. FOUCH TRACT

Being a part of the west half of the NE Quarter of Section No. 14, Laurel Township, T12N, R18W, Hocking County and State of Ohio and further described as follows: Commencing at an iron pin marking the SE corner of said $\frac{1}{2}$ Section, an 8" Pig nut Hickory bears N64°45'E, 23.65 ft. and a 20" Ash bears N19°E, 47.8 ft; thence on the south line of said $\frac{1}{2}$ Quarter Section N84°58'W, 222.5 ft. to a fence corner post, the actual point of beginning of the tract being conveyed; thence, N10°02'W, 769 ft. to a point in the center of County Road No. 4 passing an iron pin at 739 ft; thence along the center line of County Road No. 4 S65°46'W, 23.5 ft; S 67°46'W, 50 ft.; S 69°31'W, 50 ft.; S73°31'W, 50 ft.; S 75°38'W, 50 ft.; S80°51'W, 50 ft.; N 85°27'W, 50 ft.; N 77°40'W, 21.75 ft.; thence, leaving County Road No. 4, S 4°20'E, 17.0 ft. to a corner fence post; thence continuing S 4°20'E, 633.5 ft. to a corner fence post on the south line of said $\frac{1}{2}$ Quarter Section; thence along south line of the $\frac{1}{2}$ Quarter Section S 84°58'E, 417.82 ft. to a corner fence post and the place of beginning of this tract and containing 5.94 Acres, more or less.

APPROVED
HOCKING COUNTY ENGINEER'S OFFICE
DATE 1-10-75
BY R. E.



584° 49' E 685.2

Road

Concrete Tile Monument

Witness
 1/2" White Oak 577° 00' W 46'
 1/2" Poplar at run 52.830° E 23.5'

10.467 ac.

SE 1/4 of SW 1/4 Sec 14

SW 1/4 of SE 1/4 Sec 14

Concrete Tile Monument

Pool

Concrete Tile Monument

Stone

584° 35' E 1353.0
174.73.78

Sec Line Sec 14
Sec. 23

Concrete Tile Monument

.059 ac.

NE 1/4 of NW 1/4 Sec 23

Lot 2

Homer Shein Property
 Transfer to Smith & Johnson.
 Sec 14 & 23 Laurel Twp Hocking Co.
 A.W. Seabright Logan Ohio July 4 1935.
 All Bearings given in Deed and Plat are Magnetic

Residue of Homer Schein Land
Sec. 14-22-23, Laurel Township
Hocking County, Ohio


Being a part of Sections 14, 22, and 23, Laurel Township, T12N, R16W,
Hocking County, and State of Ohio, and further described as follows:

PARCEL 1. Being the Southeast quarter of the Southwest quarter of said Section 14, except the following tract: Beginning at a point on the quarter section line which point bears South 84 degrees - 35 minutes East 1353 feet and North 4 degrees - 34 minutes East 93.35 feet from a stone placed on the South line of Section 14, said stone being the Southwest corner of said Southeast quarter of the Southwest quarter; thence North twenty-eight degrees - 15 minutes West 519.35 feet to a concrete monument; thence North 56 degrees - 58 minutes East 116.31 feet to a concrete monument in the center of a road; thence by said road North 44 degrees - 18 minutes West 91.5 feet; thence North 31 degrees - 35 minutes West 235.1 feet, North 48 degrees - 39 minutes West 193.1 feet; thence North 32 degrees - 44 minutes West 207.9 feet; thence North 2 degrees - 40 minutes East 217.41 feet to a concrete monument in the North line of said Southeast quarter of Southwest quarter; thence South 84 degrees - 49 minutes East 685.2 feet to the said quarter section line; thence with the said quarter section line, South 4 degrees - 34 minutes East 1248.42 feet to the place of beginning, containing 10.467 Acres, leaving in said tract herein conveyed 31.4 Acres, more or less.

PARCEL 2. Being in the Southwest corner of the Southwest quarter of the Southeast quarter of said Section 14 and beginning at a point on the South line of said Section 14, said beginning point being South 84 degrees - 35 minutes East 1413.78 feet from the stone at the Southwest corner of the Southeast quarter of the Southwest quarter; thence North 28 degrees - 15 minutes West 112.12 feet; thence South 4 degrees - 34 minutes West 93.35 feet; thence South 84 degrees - 35 minutes East 60.78 feet to the place of beginning, containing 0.13 Acres.


PARCEL 3. Being the Northwest quarter of the Northwest quarter and Lot 2 of said Section 23, containing 94 Acres, but excepting from Lot 2 a small tract of land described as follows: Beginning at a point in the North line of said Section 23 which point bears South 84 degrees - 35 minutes East 1413.78 feet from the stone placed on said North line of Section 23 and being the Southwest corner of the Southeast quarter of the Southwest quarter of Section 14; thence with said North line of Section 23, South 84 degrees - 35 minutes East 126.46 feet to the center of a run; thence down the center of said run South 8 degrees - 00 minutes East 4.14 feet; thence leaving said run South 77 degrees - 45 minutes West 24.01 feet to an 8 inch birch on line; thence continuing on said line, South 77 degrees - 45 minutes West 83.97 feet to a point; thence North 28 degrees - 15 minutes West 44.22 feet to the place of beginning, containing 0.059 Acres, and leaving in said parcel 93.941 Acres, more or less.

BEING 30.0 FT. WIDE DEDICATED EASEMENTS ACROSS PART OF THE W/2 OF THE SW/4 OF SEC. 1A, LAUREL TWP., T-12N, R-13W, HOCKING CO., OHIO



H. E. J. WATKINS
 OR. VOL. 54, P. 274
 OR. VOL. 56, P. 178

S. E. E. DABUSH
 O.R. VOL. 84, P. 921



Approved - Mathematically
 Hocking County Engineer's office
 By *[Signature]* Date 2-14-97
 Easements Only

PLAT PREPARED FROM SURVEY
 MADE JAN. 28, 1997, BY:

[Signature]
 OHIO REGISTERED SURVEYOR NO. 6503



DESCRIPTION OF 30.0 FT. EASEMENT

EASEMENT NO. 2

Being a non-exclusive 30.0 ft. wide easement for the purpose of ingress & egress across tracts described in O.R. Vol. 90, Pg. 608 and O.R. Vol. 84, Pg. 917, being situated in the W 1/2 of the SW 1/4 of Sec. 14, Laurel Twp., T-12N, R-18W, Hocking Co., Ohio. The centerline of said easement is described as follows:


Beginning at a point on the south line of the 11.8452 Ac. tract described in O.R. Vol. 90, Pg. 610, said point being referenced by the NW corner of the 5.000 Ac. tract described in O.R. Vol. 90, Pg. 608, which bears East a distance of 176.68 ft.;

Thence with the center of a private roadway the following nine (9) courses:

- 1) S 1 degree 00' 00" E a distance of 112.06 ft. to a point;
- 2) S 38 degrees 33' 14" E a distance of 50.41 ft. to a point;
- 3) S 60 degrees 44' 27" E a distance of 100.68 ft. to a point;
- 4) S 64 degrees 48' 35" E a distance of 59.55 ft. to a point;
- 5) S 61 degrees 36' 02" E a distance of 79.12 ft. to a point;
- 6) S 40 degrees 05' 11" E a distance of 37.66 ft. to a point;
- 7) S 62 degrees 06' 51" E a distance of 22.21 ft. to a point;
- 8) S 77 degrees 15' 25" E a distance of 65.43 ft. to a point;
- 9) S 89 degrees 03' 30" E a distance of 80.38 ft. to a point of termination

on the east line of said 5.000 Ac. tract described in O.R. Vol. 90, Pg. 608.

The above description is the result of an actual survey made by Michael P. Berry, Ohio Registered Surveyor No. 6803, on January 28, 1997.


 Michael P. Berry #6803

DESCRIPTION OF 30.0 FT. EASEMENT

EASEMENT NO. 1

Being a non-exclusive 30.0 ft. wide easement for the purpose of ingress & egress across tracts described in O.R. Vol. 56, Pg. 178, O.R. Vol. 90, Pg. 610, O.R. Vol. 90, Pg. 608, and O.R. Vol. 84, Pg. 917, being situated in the W 1/2 of the SW 1/4 of Sec. 14, Laurel Twp., T-12N, R-18W, Hocking Co., Ohio. The centerline of said easement is described as follows:


Beginning at a point on the east line of the 5.000 Ac. tract described in O.R. Vol. 84, Pg. 921, said point being referenced by the SE corner of said 5.000 Ac. tract which bears S 0 degrees 39' 08" E a distance of 403.84 ft.;



Thence with the center of an existing roadway the following nine (9) courses:


- 1) S 75 degrees 05' 08" E a distance of 66.98 ft. to a point;
- 2) S 85 degrees 20' 46" E a distance of 88.12 ft. to a point;
- 3) N 81 degrees 43' 24" E a distance of 55.89 ft. to a point;
- 4) N 85 degrees 17' 48" E a distance of 71.37 ft. to a point;
- 5) N 74 degrees 10' 28" E a distance of 82.58 ft. to a point;
- 6) N 64 degrees 09' 15" E a distance of 126.28 ft. to a point;
- 7) N 58 degrees 22' 45" E a distance of 165.28 ft. to a point;
- 8) N 56 degrees 06' 14" E a distance of 101.13 ft. to a point;
- 9) N 86 degrees 04' 02" E a distance of 61.49 ft. to a point of termination


in the center of Twp. Rd. No. 232.

The above description is the result of an actual survey made by Michael P. Berry, Ohio Registered Surveyor No. 6803, on January 28, 1997.


 Michael P. Berry #6803

Approved - 
 Hocking County Engineer's office
 By  Date 2-14-97
 Easements only





LUTZ
VOL-121-PAGE 452 REF
44.594 AC±

JESSE VORHEES

LARRY VORHEES
6 ACRES

JESSE VORHEES
VOL. 109-28
SEC # 22

APPROVED
HOCKING COUNTY
ENGINEERS OFFICE
LOGAN, OHIO 43134
DEC 26 1913
S.E.

STATE OF OHIO
HOCKING CO.
LAUREL TWP - SEC # 14
T-12
R-18

DESCRIPTION

LUTZ - 44.594 ACRES

Situated in the Township of Laurel, County of Hocking, State of Ohio and being a part of the southwest quarter of Section 14, Town 12, Range 18, bounded and described as follows:

Beginning at a track spike in County Road 9, said spike being the southwest corner of Section 14; thence with said section line and County Road 9 North $3^{\circ}40'$ East 334.60 feet to a point; thence South $87^{\circ}19'$ East 104.84 feet to an iron pin, passing an iron pin at 16.00 feet; thence North $0^{\circ}30'$ East 312.46 feet to an iron pin, passing an iron pin at 30.00 feet; thence South $63^{\circ}21'$ West 101.40 feet to an iron pin; thence North $3^{\circ}40'$ East 139.93 feet to a point in Township Road 232, passing an iron pin at 103.52 feet; thence with said Township Road the following courses: North $30^{\circ}36'$ East 296.80 feet; North $59^{\circ}11'$ East 566.47 feet; North $49^{\circ}52'$ East 265.53 feet; North $44^{\circ}58'$ East 420.97 feet; South $74^{\circ}51'$ East 109.50 feet; South $47^{\circ}07'$ East 94.07 feet; thence leaving Township Road 232 South $20^{\circ}25'$ West 430.93 feet to an iron pin; passing an iron pin at 33.75 feet; thence South $86^{\circ}29'$ East 312.25 feet to an iron pin; thence South $2^{\circ}05'30''$ West 1337.01 feet to a stone; thence N $86^{\circ}03'31''$ West 1475.86 feet to the place of beginning, passing an iron pin at 841.71 feet and containing 44.594 acres more or less, subject to the rights of way of County Road 9 and Township Road 232.

Prepared by:

William M. Watkins

Registered Surveyor #5216

APPROVED
HOCKING COUNTY
ENGINEERS OFFICE
LOGAN, OHIO 43138

DEC 26 1973

J.E

REFERENCES:
 DEEDS AS NOTED
 COUNTY TAX MAPS
 PREVIOUS SURVEYS
 EXISTING MONUMENTS

- LEGEND**
- ▲ - 3/8" IRON PIN SET W/ I.D. CAP STAMPED "SEYMOUR & ASSOC."
 - ⊙ - 3/4" IRON PIPE FOUND
 - ⊠ - 1" SQUARE IRON BAR FOUND
 - - POINT
 - ⊙ - CONC. IN VITRIFIED CLAY PIPE MONUMENT FOUND
 - - IRON PIN FOUND

NOTE:
 BEARINGS DERIVED FROM PREVIOUS SURVEYS AND ARE FOR USE AS A GUIDE ONLY. TAKE BEARINGS ON THE EAST SIDE OF THE W. 1/2 OF THE S.E. 1/4 OF SECTION 14 AS BEARINGS:
 S07°23'13"W

SCALE:
 1" = 200'
 0 100 200

Approved Mathematically
 Hocking County Engineer's Office
 Date 5-9-95

I HEREBY CERTIFY THAT AN ACTUAL SURVEY WAS MADE UNDER MY DIRECT SUPERVISION OF THE PREMISES SHOWN HEREON ON THE 6th DAY OF MAY 1995, AND THAT THE PLAT IS A CORRECT REPRESENTATION OF THE PREMISES AS DETERMINED BY SAID SURVEY. I FURTHER CERTIFY THAT THERE ARE NO ENCROACHMENTS EITHER WAY ACROSS ANY BOUNDARY EXCEPT AS SHOWN HEREON.


George F. Seymour
 PROFESSIONAL SURVEYOR NO. 6644

SHEET	REVISIONS	
1/1		
JOB	DRAWN	DATE
L14042	FB	5/6/95

PLAT OF SURVEY

BEING PARTS OF THE W. 1/2 OF THE S.E. 1/4 & THE S.E. 1/4 OF THE S.W. 1/4 OF SECTION 14 & PART OF THE N.E. 1/4 OF SECTION 23 AND BEING SITUATE IN TOWN 12 NORTH - RANGE 18 WEST - LAUREL TOWNSHIP - HOCKING COUNTY - STATE OF OHIO.

SURVEYED FOR: MARK & DANNIE DEVOL



PROFESSIONAL LAND SURVEYORS

- OIL WELL PERMITTING
- LOTS & FARM SURVEYS
- SUB-DIVISIONS
- LAND PLANNING
- CONSTRUCTION

SEYMOUR & ASSOCIATES

P.O. Box 424
 Logan, Ohio 44756
 69 S. MARKET ST. 385-5954




EXHIBIT "A"

Thence continuing along the grantor's westerly line and along the center of said road the following five courses:

- [1] North 41 degrees 56 minutes 54 seconds West a distance of 91.50 feet to a point;
- [2] North 29 degrees 13 minutes 54 seconds West a distance of 235.10 feet to a point;
- [3] North 46 degrees 17 minutes 54 seconds West a distance of 193.90 feet to a point;
- [4] North 30 degrees 22 minutes 54 seconds West a distance of 207.09 feet to a point, and;
- [5] North 07 degrees 13 minutes 16 seconds East a distance of 225.75 feet to a 1" square iron bar found at the intersection of the centerline of Township Road No. 232 and Township Road No. 136;

Thence leaving the center of Township Road No. 232 and Township Road No. 136 and continuing along a westerly line to the grantor, South 81 degrees 44 minutes 39 seconds East a distance of 676.80 feet to a 5/8" X 30" iron pin with a plastic identification cap set on the west line of the southeast quarter of Section 14;


Thence continuing along the grantor's westerly line and along the west line of the southeast quarter, North 06 degrees 55 minutes 08 seconds East a distance of 1315.08 feet to a 5/8" X 30" iron pin with a plastic identification cap set on the northwest corner of the west half of the southeast quarter and the grantor's northwest corner;

Thence along the grantor's north line and the north line of the west half of the southeast quarter, South 81 degrees 59 minutes 57 seconds East a distance of 1271.04 feet to the place of beginning, containing 0.0632 acre in Section 23 and 87.2201 acres in Section 14, for a total of 87.2833 acres, more or less, and subject to the right of way of Township Road No. 232, Township Road No. 136 and all easements of record.

All 5/8" X 30" iron pins with plastic identification caps set are stamped "Seymour & Associates".

The bearings used in the above described tract were based on east line of the west half of the southeast quarter of Section 14 as bearing South 07 degrees 23 minutes 13 seconds West and are for the determination of angles only.

The above described tract was surveyed by George F. Seymour, Ohio Professional Surveyor No. 6044, May 6, 1995.



Approved - Mathematically
Hocking County Engineer's office
By *JM* Date *5-9-95*

EXHIBIT "A"

Being a part of the tract of land that is now or formerly in the name of Mark and Dannie Devol as recorded in Official Record 36 at page 466, Hocking County Recorder's Office, said tract being part of the west half of the southeast quarter and part of the southeast quarter of the southwest quarter of Section 14 and part of the northeast quarter of Section 23, T12N, R18W, Laurel Township, Hocking County, State of Ohio and being more particularly described as follows:

Beginning at an iron pin found on the northeast corner of the west half of the southeast quarter of Section 14 and the grantor's northeast corner;

Thence along the east line of the west half of the southeast quarter and the grantor's east line, South 07 degrees 23 minutes 13 seconds West, passing through a 24" Walnut Tree at the southwest corner of the northeast quarter of the southeast quarter at 1321.57 feet, passing through a 5/8" X 30" iron pin with a plastic identification cap set at 2575.43 feet and crossing the centerline of Township Road No. 232 at 2585.03 feet, going a total distance of 2651.43 feet to a 5/8" X 30" iron pin with a plastic identification cap set on the southeast corner of the west half of the southeast quarter and the grantor's southeast corner;


Thence along the south line of Section 14, the north line of Section 23 and the grantor's south line, North 82 degrees 13 minutes 54 seconds West, passing through a 5/8" X 30" iron pin with a plastic identification cap set at 95.20 feet, crossing the center of Township Road No. 232 at 115.20 feet, passing through 5/8" X 30" iron pins with plastic identification caps set at 135.20 feet and 925.13 feet, crossing the center of Township Road No. 232 at 941.13 feet and passing through a 5/8" X 30" iron pin with a plastic identification cap set at 957.13 feet, going a total distance of 1061.85 feet to a 5/8" X 30" iron pin with a plastic identification cap set;

Thence leaving the south line of Section 14 and continuing along the grantor's south line, South 05 degrees 38 minutes 52 seconds East a distance of 7.86 feet to a 5/8" X 30" iron pin with a plastic identification cap set;

Thence continuing along the grantor's south line, South 82 degrees 06 minutes 06 seconds West a distance of 107.98 feet to a concrete in vitrified clay pipe found on the grantor's most southerly corner;

Thence along the grantor's westerly line the following two courses:

- [1] North 25 degrees 53 minutes 54 seconds West, crossing the section line between Section 23 and 14 at 44.22 feet, going a total distance of 675.84 feet to a concrete in vitrified clay pipe monument found, and;
- [2] North 59 degrees 17 minutes 35 seconds East, passing through a 5/8" X 30" iron pin with a plastic identification cap set at 98.31 feet, going a total distance of 116.31 feet to a point in the center of Township Road No. 232;



[continued on page 2]

PLAT OF SURVEY

FOR

IDA LUTZ TO DELINEATE A 2.254 ACRE PARCEL OF LAND OUT OF HER 44.59 TRACT (D.B. 148 P. ~~559~~ ⁵⁶⁴), SITUATED IN THE SOUTHWEST QUARTER OF SECTION 14, TWP 12, RANGE 18, LAUREL TOWNSHIP, HOCKING COUNTY, OHIO.

SURVEY REFERENCES

TAX MAPS
TOPOGRAPHIC MAPS
SURROUNDING DEEDS
SURROUNDING SURVEYS
EXISTING MONUMENTATION

BASIS OF BEARINGS: N 3° 40' E BEARING SHOWN ON WEST LINE SECTION 14 TAKEN FROM A SURVEY PLAT OF A FORMER SURVEY IN AREA.

IDA LUTZ
44.59 ACRES
148 ——— ⁵⁶⁴

IDA LUTZ
44.59 ACRES
148 ——— ⁵⁶⁴



BOBBY RUSSEL WILLIARD
0.072 AC. 148 ——— 662
0.600 AC. 121 ——— 453

2.254 ACRES



SCALE: 1" = 50'
0 25 50 75 100

- DENOTES I.P. FOUND
- ☆ DENOTES 5/8" I.P. SET WITH ALUM. I.D. CAP
- ▲ DENOTES R.R. SPK. FOUND
- DENOTES P.K. NAIL SET

Approved Mathematically
Hocking County Engineer's Office
Date 1/14/82

SOUTHWEST CORNER OF SECTION 14,
TP. 12, R. 18, LAUREL TWP, HOCKING
COUNTY, OHIO.

SECTION 14
SECTION 23



I HEREBY CERTIFY THAT THIS PLAT CONFORMS TO A SURVEY MADE BY ME AND BOB MOORE IN JANUARY 1982, AND THAT WE HAVE FOUND THE LINES AND MARKED THEM AS SHOWN HEREON.

DATED: JANUARY 13, 1982.

BY Henry N. Jones, Jr.
HENRY N. JONES, JR. REGISTERED SURVEYOR NO. 4027

Deed Book. 2,254 Ac for Ida Lutz, Laurel Twp, Sec. 14

Being a part of a 44.59 acre tract of land transferred to Ida Lutz as shown of record in deed Book 148 page ~~659~~⁵⁶⁴, situated in the Township of Laurel, County of Hocking, State of Ohio and being a part of the southwest quarter of Section 14, Twp. 12, Range 18 and more particularly described as follows;

Beginning for a point of reference at a railroad spike found at the southwest corner of Section 14, Twp. 12, Range 18, Laurel Township, Hocking County, Ohio this said point being also the south west corner of the Grantors 44.59 acre tract;

Thence North $3^{\circ} 40'$ East with and along the Section line between Section 14 and Section 15 and the line of Kreash-Baum^{road} for a distance of 120.26 feet to a P.K. nail set in Kreash-Baum road; the true place of beginning of This description

Thence continuing North $3^{\circ} 40'$ East with the section line & Kreash-Baum road for a distance of 214.34 feet to a P.K. nail set;

Thence South $87^{\circ} 19'$ East with and along the line between the Grantor and Bobby Russel Williard 0.072 acre parcel (D.B. 148 p. 662) for a distance of 104.84 feet to an iron pin found, passing an iron pin found on line at 16.00 feet;

Thence North $82^{\circ} 09' 56''$ E for a distance of 310.19 feet to a $\frac{5}{8}$ inch iron pin set with an aluminum identification Cap;

Thence South $3^{\circ} 20' 58''$ West for a distance of 279.54 feet to a $\frac{5}{8}$ inch iron pin set with an aluminum identification

line & Kreash-Baum road for a distance of 214.34 feet to a P.K. nail set;

Thence South $87^{\circ} 19'$ East with and along the line between the Grantor and Bobby Russel Williard 0.072 acre parcel (D.B. 148 p. 662) for a distance of 104.84 feet to an iron pin found, passing an iron pin found on line at 16.00 feet;

Thence North $82^{\circ} 09' 56''$ E for a distance of 310.19 feet to a $\frac{5}{8}$ inch iron pin set with an aluminum identification cap;

Thence South $3^{\circ} 20' 58''$ West for a distance of 279.54 feet to a $\frac{5}{8}$ inch iron pin set with an aluminum identification cap;

Thence North $86^{\circ} 07'$ West for a distance of 410.34 feet to the P.K. nail at the true place of beginning of this description, passing a $\frac{5}{8}$ inch iron pin set on line, with an aluminum identification cap at 394.56 feet, containing 2.254 acres, more or less, of land, subject to highway and any other

easelements of record.

This description prepared by Henry N. Jones, Jr., Registered Surveyor No 4027 from a survey of the premises made in January 1982.

The basis of bearings used in this description is the bearing shown on a survey plat ($N 3^{\circ} 40' E$) of a former survey on the Section line between Section 14 and Section 15 and used in description of Grantors 44.59 acre tract:

Approved - Mathematically

Hocking County Engineer's Office

By Hen K6 Date 1-14-82


SUBDIVISION REGULATIONS WAIVED
PENDING HEALTH DEPT. APPROVAL

BY Hen K6 DATE 1-14-82

HENRY N. JONES, JR.
PHONE 614-332-4353
14964 CLAPPER HOLLOW ROAD
LAURELVILLE, OH 43135

PLAT OF SURVEY

FOR
 IDA LUTZ TO DELINEATE A 12.483 ACRE PARCEL OF LAND OUT OF HER 42.336 TRACT (D.B. 148 P 564)
 SITUATED IN THE WEST HALF OF THE SOUTHWEST QUARTER OF SECTION 14, TP 12, RANGE 18, LAUREL
 TOWNSHIP, HOCKING COUNTY, OHIO.



JOSEPH & GREGORY FOX
 58 ACRES
 180 ——— 328

RONALD & DARLA MURDOCK
 2.014 ACRES
 153 ——— 85

12.483 ACRES

IDA LUTZ 42.336 ACRES 148 ——— 564


BULL 40 ACRES 149 ——— 257
 COLIN & DIANA
 S 2° 05' 30" W 264.40'
 PAUL & AUDNI BEACH 29.74 ACRES 159 ——— 658

SECTION 15
 SECTION 14

SECTION 14
 SECTION 23

SOUTHWEST CORNER SECTION 14
 TWP 12, R. 18, LAUREL TWP,
 HOCKING COUNTY, OHIO

Approved: *[Signature]*
 Hocking County Engineer's Office
 Date 5-19-82



SURVEY REFERENCES

- TAX MAPS
- TOPOGRAPHIC MAPS
- FORMER SURVEYS
- SURROUNDING DEEDS
- EXISTING MONUMENTATION
- FENCE LINES

LEGEND

- ☆ DENOTES 5/8" I.P. SET WITH PLASTIC I.D. CAP
- DENOTES IRON PIN FOUND
- DENOTES R.R. SPK FOUND
- DENOTES TRANSIT POINT NAIL

BASIS OF BEARINGS: BEARINGS SHOWN ON
 CENTER LINE ROCKY FORK ROAD ON FORMER
 SURVEY OF ORIGINAL TRACT.

I HEREBY CERTIFY THAT THIS PLAT CONFORMS TO A SURVEY MADE BY ME & BOB MOORE
 IN MAY 1982 AND THAT WE HAVE FOUND THE LINES AND MARKED THEM AS SHOWN HEREON.

DATED: MAY 19, 1982.

BY *[Signature]*
 HENRY N. JONES, JR. REGISTERED SURVEYOR NO. 4027



Deed No. 12.483 Acres, Ida Lutz, Section 14, Laurel Twp

Approved - Mathematically
Hocking County Engineer's Office

AW 77 Date 5-19-82

Being a part of a 42.336 acre tract of land transferred to IDA LUTZ as shown of record in Deed Book 148 page 564, situated in the west half of Section 14, Twp. 12, Range 18, Laurel Township, Hocking County, Ohio and more particularly described as follows;

Beginning for a point of reference at a Railroad spike found at the southwest corner of the abovesaid Section 14;

Thence North $3^{\circ} 40'$ East with and along the west line of Section 14 for a distance of 700.82 feet to an iron pin found, passing an iron pin found on line at 597.30 feet; this iron pin at 700.82 feet distance being the true place of beginning of this description;

Thence North $3^{\circ} 40'$ East for a distance of 36.41 feet to a nail in the center of Rocky Fork Road (Twp Road No 232)

Thence Northeasterly with and along the center of Rocky Fork Road the following six courses;

North $30^{\circ} 36'$ East	for a distance of	296.80 feet	to a nail;
North $59^{\circ} 11'$ East	" " " "	566.47	" " " " ;
North $49^{\circ} 52'$ East	" " " "	265.53	" " " " ;
North $44^{\circ} 58'$ East	" " " "	420.97	" to an I.P. found;
South $74^{\circ} 51'$ East	" " " "	109.50	" to a nail;
South $47^{\circ} 07'$ East	" " " "	94.07	" " " " ;

Thence South $20^{\circ} 25'$ West for a distance of 430.93 feet to an iron pin found, passing a $\frac{5}{8}$ inch iron pin set on line with a plastic identification cap at 33.75 feet;

Thence South $86^{\circ} 29'$ East for a distance of 312.25 feet to an iron pin found at the northeast corner of the Southwest Quarter of the Southwest Quarter of Section 14;

Thence South $2^{\circ} 05' 30''$ West for a distance of 353.57 feet to a $\frac{5}{8}$ inch iron pin set with a plastic identification cap;

Thence North $52^{\circ} 46' 55''$ West for a distance of

235.94 feet to a $\frac{5}{8}$ inch Iron Pin set with a plastic identification cap;

Thence North $82^{\circ} 01' 44''$ West for a distance of 268.62 feet to a $\frac{5}{8}$ inch iron pin set with a plastic identification cap;

Thence South $70^{\circ} 34' 59''$ West for a distance of 572.37 feet to a $\frac{5}{8}$ inch iron pin set with a plastic identification cap;

Thence South $74^{\circ} 02' 59''$ West for a distance of 195.27 feet to a $\frac{5}{8}$ inch iron pin set with a plastic identification cap;

Thence South $67^{\circ} 17' 04''$ West for a distance of 305.68 feet to the iron pin at the true place of beginning of this description, containing 12.483 acres of land, more or less, subject to Highway and any other easements of record.

This description prepared by Henry N. Jones, Jr., Registered Surveyor No. 4027, from a survey of the premises made in May, 1982.

The Basis of bearings used in this description is the bearings shown on a plat of survey along Rocky Fork Road courses used in a former survey of the original Lutz tract;

HENRY N. JONES, JR.
PHONE 614-332-4353
14964 CLAPPER HOLLOW ROAD
LAURELVILLE, OH 43135

Henry N. Jones Jr.
Reg. Surv. 4027